

## **GC-2 Spill Site Trimming Protocol Demonstration Plan**

Commencing on March 16, 2006 at 10:00 a.m.

1. Use of Bobcat skid steer loader with 40' trimmer attachment for initial test. Trimmer will enter from the outside perimeter edge to avoid cross contamination.
2. Test area will be grid C-5 and/or C-4. Test area was discussed with John Engles (ADEC).
3. Task force leader in conjunction with SOSC will serve as spotters for trimmer operator and determine the path and trimming depth of cut.
4. Will use skid steer loader staged inside the perimeter for removal of trimmed materials.
5. Recovered materials will be manifested for disposal by BP environmental personnel per waste disposal plan.
6. Upon successful demonstration of the above small scale protocol a large scale trimming demonstration using a 72" trimming head will commence using the same basic protocol.
7. Upon completion of the large scale demonstration a determination will be made on final protocols for long term trimming operations of the effected area. Trimming operations are expected to take 14 days to complete after process approval.