


CITY OF CHEFORKNAK, ALASKA

2012 PUMP HOUSE REPAIRS

IN COOPERATION WITH STATE OF ALASKA
VILLAGE SAFE WATER AND THE CITY OF
CHEFORKNAK, ALASKA

95% ISSUED FOR REVIEW



Location Map

CE₂
ENGINEERS, INC.

PO BOX 232946 ANCHORAGE, AK 99523 PH: 907-349-1010 FAX: 907-349-1015



Consultant

RECORD DRAWING CERTIFICATE

THESE DRAWINGS REFLECT RECORDED
INFORMATION OBTAINED DURING
CONSTRUCTION.
INFORMATION PROVIDED HEREIN IS
ACCURATE TO THE BEST OF MY
KNOWLEDGE.

NAME

DATE

Construction Foreman

FINAL DESIGN

(Date)

ADEC APPROVAL

(Date)

Construction Period

(From)

(To)

As-Built

(Date)


SHEET INDEX

No.

Title


A1.1 COVER SHEET AND DRAWING INDEX
A1.2 PUMP HOUSE FOUNDATION AND FLOOR PLAN
REPAIR DETAILS

G:\ACAD\CHEFORNAK\2012 PUMP HOUSE REPAIRS\A1.1 FLOOR PLAN.dwg, 9/13/2012 3:26:01 PM, Flash, \\CE2MAIN\LANIER MP C2050\LD520C PCL 6



MECHANICAL FLOOR PLAN

1 EXISTING FLOOR PLAN 1989
A1.1 SCALE: 1/4" = 1'-0"




2 PROPOSED FLOOR PLAN
A1.1 SCALE: 1/4" = 1'-0"

SCOPE OF WORK FOR THE WATER PLANT REPAIRS PROJECT

THE EXISTING 4,000 GAL WELDED STEEL WATER STORAGE TANK HAS BEEN LOCATED IN THE EAST END OF THE PUMP HOUSE FOR THIRTY YEARS. DURING THAT TIME, FILTER BACKWASH WATER UNDER THE BUILDING HAS CAUSED SETTLEMENT OF THREE KEY PILES UNDER THE TANK. SWEATING OF THE TANK HAS CAUSED ROT ON THE FLOOR. BOTH OF THESE SITUATIONS HAVE CAUSED THE POSSIBILITY OF FLOOR AND TANK FAILURE. TO PROVIDE A TEMPORARY REMEDY UNTIL THE NEW PUMP HOUSE IS CONSTRUCTED, IT IS PROPOSED THAT THE WATER TANK BE RELOCATED ON A REINFORCED FLOOR.

STEPS IN THE RELOCATION AND REPAIR PROJECT

1. ARRANGE WITH SCHOOL TO HAVE THEIR POTABLE WATER TANKS FULL SO THAT THEY DO NOT HAVE TO DRAW WATER FROM THE WELL AND WATER CIRCULATION SYSTEM.
2. SET UP A TEMPORARY PRESSURE PUMP AND TANK SYSTEM TO PROVIDE PRESSURIZED WATER TO THE EXISTING WATER DISTRIBUTION LOOP DURING THE TANK MOVE.
3. TAKE EXISTING PRESSURE PUMPS OUT OF SERVICE AND MOVE THEM AND THE DISCHARGE PIPING OUT OF THE WAY OF THE TANK MOVE.
4. REINFORCE FLOOR AS SHOWN IN DETAIL 3 THIS SHEET AND DETAIL B SHEET A1.2 WITH STEEL BEAMS WELDED TO EXISTING PILE.
5. REINFORCE FLOOR SURFACE WITH PLYWOOD AS SHOWN IN DETAIL 1 SHEET A1.2. LAY DOWN CONTAINMENT MEMBRANE BUT DO NOT BUILD RIM ASSEMBLY.
6. EMPTY WATER OUT OF THE TANK AND DISCONNECT ALL PIPING CONNECTIONS TO THE TANK. CLEAN OUT RUST, SEDIMENT, AND WIREBRUSH.
7. RELOCATE THE TANK TO THE NEW POSITION SHOWN IN DETAIL 2 THIS SHEET. USE LUMBER AND PIPE ROLLERS TO MOVE THE TANK.
8. CUT HOLES IN TANK FOR TANK OUTLET AND OVERFLOW PIPING. PLUG EXISTING PIPING PENETRATIONS AND USE FOAM INSULATION OR WOOD TO MAKE A SMOOTH SURFACE OVER THE PLUGS AND MANHOLE TO PREVENT CHAFING OF THE PVC LINER.
9. INSTALL NSF-COMPLIANT PVC TANK LINER INTO TANK. CUT HOLES FOR PENETRATIONS AND INSTALL SIDEWALL TANK FITTINGS.
10. INSTALL PVC PUMP SUCTION PIPING AND FITTINGS TO THE NEW TANK. RELOCATE ORIGINAL PRESSURE PUMPS AND DISCHARGE MANIFOLD AND APPURTENANCES. INSTALL NEW PVC SUCTION MANIFOLD FOR THESE ORIGINAL PUMPS.
11. INSTALL PVC PIPING FROM WELL AND FILTERS TO TANK. FIT DISCHARGE INTO TOP OF TANK.
12. INSTALL EMERGENCY OVERFLOW PIPING INTO TANK, ROUTE PIPING TO EAST END OF BUILDING AND PENETRATE END WALL.
13. CONSTRUCT CONTAINMENT RIM AS SHOWN IN SECTION A SHEET A1.2.
14. DISINFECT TANK PER AWWA C652-11 METHOD 3 AS FOUND IN SECTION 4.3 OF THE STANDARD. DISCHARGE SUPERCHLORINATED WATER AFTER NEUTRALIZATION WITH SODIUM THIOSULFATE.
15. TAKE TWO BAC-T SAMPLES 30 MINUTES APART AND SEND TO YUKON-KUSKOKWIM HEALTH CORP. (YKHC) FOR TESTING. AFTER THE SUCCESSFUL BAC-T TESTS, THE TANK CAN BE RETURNED TO SERVICE.



3 EXISTING / PROPOSED FOUNDATION PLAN
A1.1 SCALE: 1/4" = 1'-0"

RECORD DRAWING CERTIFICATE	DATE
THESE DRAWINGS REFLECT RECORDED INFORMATION OBTAINED DURING CONSTRUCTION. INFORMATION PROVIDED HEREIN IS ACCURATE TO THE BEST OF MY KNOWLEDGE.	NAME

SCALE:	AS SHOWN
CONSTRUCTION RECORD	FIELD BOOK
STAKING	FOREMAN
AS-BUILT	INSPECTOR

STATE OF ALASKA	49th	PAUL C. WENGER	CE-10270
REGISTERED PROFESSIONAL ENGINEER			

2012 PUMP HOUSE REPAIRS	PUMP HOUSE FOUNDATION & FLOOR PLAN	CHEFORNAK, ALASKA
-------------------------	------------------------------------	-------------------


PROJECT NO.	DATE	DESIGNED	POW	DRAWN	LAWICM	APPROVED	POW
	AUG 2012						

Project No.	DATE	DESIGNED	POW	DRAWN	LAWICM	APPROVED	POW
	AUG 2012						


Project No.	DATE	DESIGNED	POW	DRAWN	LAWICM	APPROVED	POW
	AUG 2012						

Project No.	DATE	DESIGNED	POW	DRAWN	LAWICM	APPROVED	POW
	AUG 2012						

G:\ACAD\CHEFORNAK\2012 PUMP HOUSE REPAIRS\A1.2 DETAILS.dwg, 9/13/2012 3:42:12 PM, Fleish, \\CEZMAIN\LANIER MP C2050\LD520C PCL 6



1 PROPOSED FLOOR REINFORCEMENT
A1.2 SCALE: 3/4" = 1'-0"




2 PRESSURE PUMPS PROPOSED PIPING ISOMETRIC
A1.2 SCALE: NTS


MATERIALS SCHEDULE

- 1-1/4"x2-1/2" SCH 40 SS PIPE NIPPLE
- 1-1/4" SS REINFORCED FEMALE ADAPTER, PVC SOCXSR FIPT, SPEARS #835-012SR
- 2"x1-1/4" REDUCER COUPLING SOC, PVC SPEARS #829-250
- 2" TRUE UNION BALL VALVE, VITON SEALS SOCXSOC SPEARS #2339-020
- 2" PVC 90° EL SOC, SPEARS #806-020
- 2" PVC TEE SOC, SPEARS #801-020
- 2" PVC 45° EL, SOC SPEARS #817-020
- 2" PVC UNION, VITON SEALS, SOCXFIPT SPEARS #859-020
- 2"x3" L SCH 40 SS NIPPLE MxM
- 2" BRASS BALL VALVE, FULL PORT, Fx F, 600# WOG, RED-WHITE FIGURE 5544F-2" OR EQUAL
- 2" TANK ADAPTER WITH NEOPRENE GASKET, SOCXF, SPEARS #871-020 OR EQUAL, 2" SUCTION ASSY BUILT FOR TANK w/ 2" PVC AND 2" 90° EL
- PIPE SUPPORT BASE USING UNISTRUT: P1000T CHANNEL, P2942 POST BASE, 1/2"x1" BOLT, 1/2" SPRING NUT, P117 PIPE CLAMP FOR 2" NOM. PIPE, P2860-10 PLASTIC END CAP
- 2" PVC SS REINFORCED FEMALE ADAPTOR, SPIG X F, SPEARS#878-020SR; 2" TYPE F CAMLOK ADAPTOR, M CAM X M, POLYPRO, PT COUPLINGS #2770620; 2" TYPE V DUST CAP, PT COUPLINGS #2771120

NOTE: ALL PVC PIPE AND FITTINGS SHALL BE SCHEDULE 80 WHERE APPLICABLE.



A PROPOSED FLOOR CONTAINMENT AND RIM SECTION
A1.2 SCALE: 3" = 1'-0"



B PROPOSED STEEL BEAM REINFORCEMENT
A1.2 SCALE: 1-1/2" = 1'-0"

RECORD DRAWING CERTIFICATE	
THESE DRAWINGS REFLECT RECORDED INFORMATION OBTAINED DURING CONSTRUCTION. INFORMATION PROVIDED HEREIN IS ACCURATE TO THE BEST OF MY KNOWLEDGE.	
SCALE: AS SHOWN	IF NOT ONE INCH ON THIS SHEET, ADJUST SCALE ACCORDINGLY.
CONSTRUCTION RECORD	
FIELD BOOK	STAKING
FOREMAN	INSPECTOR
2012 PUMP HOUSE REPAIRS	
REPAIR DETAILS	
CHEFORNAK, ALASKA	
CE2 ENGINEERS, INC.	
PO BOX 22346 ANCHORAGE, AK 99523 PH: 907-546-1010 FAX: 907-546-1015	
Project No.	DATE
BY	BY
REVISION	REVISION
Project No.	DATE
Designed	PCW
Drawn	LAWICM
Approved	PCW
Sheet No.	A1.2
SHEET	OF