Alaska Clean Water Fund - State Fiscal Year 2027 (SFY27) Project Priority List - Base and General Supplemental Funding

Net Resources Available to Provide Assistance = $215.8 million

(1) Within Funding Limits column indicates that the project is within the current fundable limit of the Alaska Clean Water Fund. Large projects (over $5 million) may be phased based on projected funding needs during the next year. Loan applications may be submitted for any project within the funding limits that is ready to proceed.

(2) Loan forgiveness is subject to change depending on the readiness of projects to proceed.

(3) Loan terms will be finalized when a loan agreement is offered. The finance rate will be based on a calculation identified in Alaska Administrative Code (18 AAC 76).

(4) Individual Pro Fi projects are reviewed and assigned a weighted score based on the total project cost. The overall score for the Pro Fi questionnaire is the sum of weighed scores for all of the Pro Fi projects.

Placement on this Project Priority List does not constitute either a guarantee of a loan offer or a decision that all of the estimated project costs will be deemed eligible for funding.

Rank	Score	Potential Equivalency Project	Within Funding Limits (1)	APDES Permit Number	Clean Water Needs Category	Applicant	Project Name and Description	Requested Loan Amount	Disadvantaged Community Tier	Subsidy (2) Loan Forgiveness	Green Project Category	Green Project Estimate	Requested Loan Term	Anticipated Project Start Date	Added to PPL
TREATMENT WORKS PROJECT QUESTIONNAIRES															
1	195	---	X	AK0021440	III-B	Ketchikan	**Park Avenue Harris St. Revitalization and Creek Hardening** - Replace approximately 1,800 linear feet of aging and deteriorated corrugated metal sewer pipe with corrosion resistant pipe.	$3,800,000	Tier 2	$0	Energy Efficiency	TBD	5 to 20	7/10/2028	SFY26-1
2	182(4)	X	X	AK0022551	I III-A III-B	Anchorage Water and Wastewater Utility (AWWU)	**SFY26 Programmatic Financing (Pro Fi) Loan** - Planning, design, engineering, and construction activities for eligible wastewater infrastructure projects included in the Capital Improvement Budget that may be financed through the SFY26 Pro Fi loan agreement (see attached Pro Fi project list).	$26,664,500	Tier 1	$0	---	---	20	TBD	SFY26-1
3	180	---	X	2007-DB0003	III-B	Nome Joint Utility System	**Front and N Lift Station** - Replace the Front and N lift station that was originally constructed in 1982 with a larger diameter wet well to accommodate wastewater needs and facilitate maintenance and operations.	$1,500,000	Tier 3	$500,000	---	---	5 to 20	TBD	SFY26-4
4	175(4)	X	X	AK0023213	I III-A III-B	Juneau	**Programmatic Financing (Pro Fi) Loan** - The applicant has provided a list of eligible projects including planning, design, engineering, and construction activities for wastewater infrastructure projects with disbursements planned in calendar year 2026 and 2027 that are located throughout Juneau (see attached Pro Fi project list).	$1,770,000	Tier 1	$0	---	---	5 to 20	6/1/2026	SFY26-4
5	165	---	X	AK0021890	I	Seward	**Wastewater Lagoon Disinfection Construction –** To maintain compliance with Alaska Pollutant Discharge Elimination permits, disinfection process and equipment will be installed at the Lowell Point lagoon and the Spring Creek lagoon.	$6,404,000	Tier 4	$2,000,000	---	---	20 to 30	9/9/2026	SFY26-4
6	160	---	X	AK0021393	I	North Pole	**North Pole Utility Wastewater Effluent Discharge** - Design and construct approximately 9,300 linear feet of new effluent discharge pipe to release effluent to the Tanana River.	$3,500,000	Tier 2	$500,000	---	---	20 to 30	4/13/2027	SFY26-4
7	155	---	X	2007-DB0003	III-B	Nome Joint Utility System	**Front Street Sewer Main Replacement** - Replace failing water mains that are nearly 40 years old along and adjacent to Front Street from Bering Street to Steadman Street in coordination with Alaska Department of Transportation's road improvement project.	$2,750,000	Tier 3	$0	---	---	5 to 20	5/15/2028	SFY26-4
8	150	---	X	---	III-B	Saint Paul	**Small Boat Harbor Sewer Utility Expansion** - Extend and upgrade sewer infrastructure to support commercial activity within Saint Paul's small boat harbor area including replacement of approximately 460 feet of existing harbor force main with new gravity mains; addition of approximately 1,050 feet of gravity collection mains, six new manholes, and a sewer lift station.	$2,700,000	Tier 2	$500,000	---	---	5	5/15/2026	SFY27-1
9	140	---	X	AK0021474	II	Sitka	**WWTP Effluent Disinfection System** - Design and construct an on-site disinfection system in order to meet the new limit requirements for fecal coliform and enterococcus effluent under the discharge permit issued in 2024.	$11,000,000	Tier 3	$1,000,000	---	---	20 to 30	1/1/2029	SFY26-1
10	131(4)	X	X	AK0022551	I III-A III-B	Anchorage Water and Wastewater Utility (AWWU)	**SFY27 Programmatic Financing (Pro Fi) Loan** - Planning, design, engineering, and construction activities for eligible wastewater infrastructure projects included in the Capital Improvement Budget that may be financed through the SFY27 Pro Fi loan agreement (see attached Pro Fi project list).	$4,995,000	Tier 1	$0	---	---	20	TBD	SFY26-4
11	130	X	X	AK0023213	I	Juneau	**Juneau Douglas Treatment Plant (JDTP) Vactor Receiving Station** – Construct a building to receive and process waste from Vactor trucks and septage haulers. Upgrade the JDTP headworks with two new coarse screens, a new grit removal system, and the non-portable water system to supply the new building and equipment.	$5,417,900	Tier 1	$0	---	---	5 to 20	TBD	SFY25-1
12	125	---	X	AKG573019	III-B	Selawik	**Vacuum Station** - Address deficiencies and install redundancy in all critical components of the vacuum station including vacuum tank level control, sewage discharge pumps, vacuum pumps and control panel, water circulating pumps, boiler repairs and flooring replacement.	$495,000	Tier 4	$495,000	TBD	$390,000	30	TBD	SFY25-2
13	120	---	X	2007-DB0003	TBD	Nome Joint Utility System	**Equipment Response / Storage / Office Facility** - Construct a building to support sewer utility, amalgamate ancillary facilities, reduce operating costs, protect equipment, and improve health and safety of the work environment. The facility will also support the drinking water utility. The cost of construction would be split between the Alaska Clean Water Fund and the Alaska Drinking Water Fund.	$5,025,000	Tier 3	$0	Energy Efficiency	$1,000,000	20 to 30	7/15/2027	SFY26-4
14	115	---	X	---	III-B	Wasilla	**Community Septic System Replacement** – Replace the City-owned or maintained larger community septic tanks to handle current demand and prevent leaking into ground and surface waters.	$600,000	Tier 4	$600,000	---	---	5 to 20	7/15/2026	SFY26-3

Rank	Score	Potential Equivalency Project	Within Funding Limits [1]	APDES Permit Number	Clean Water Needs Category	Applicant	Project Name and Description	Requested Loan Amount	Disadvantaged Community Tier	Subsidy [2] Loan Forgiveness	Green Project Category	Green Project Estimate	Requested Loan Term	Anticipated Project Start Date	Added to PPL
15	115	---	X	AK0021385	III-B	Haines Borough	**Wastewater Collection System Phase 1** - Repair or replace approximately 100 manholes, perform a CCTV inspection of the entire sewer system and connecting sewer laterals, and recommend repairs for Phases 2 and 3.	$1,676,125	Tier 4	$1,676,125	Energy Efficiency	TBD	20 to 30	9/25/2026	SFY26-4
16	110	---	X	---	III-B	Gambell	**Lift Station Pumps -** Purchase and install four lift station pumps and four lift station float controls in existing lift stations.	$52,472	Tier 4	$52,472	---	---	20 to 30	8/17/2026	SFY27-1
17	105	---	X	----	III-B	King Cove	**Uptown Lift Station Restoration –** Design purchase and install new control panels and replace two existing lift station pumps.	$138,600	Tier 3	$138,600	---	---	20 to 30	TBD	SFY25-3
18	100	---	X	AK0021458	III-B	Petersburg Borough	**Pump Station 3 Replacement** – Replace the original drywell pumps with three high efficiency submersible pumps along with a new wet well and valve vault.	$2,000,000	Tier 2	$100,000	---	---	20 to 30	9/1/2025	SFY25-3
19	100	---	X	---	III-B	Bethel	**City Subdivision Lift Station Panels -** Procure, install, and commission approximately 175 new lift station panels for each household, along with the purchase of an additional ten panels to maintain as critical spares.	$3,300,000	Tier 4	$2,000,000	---	---	5 to 20	8/17/2026	SFY27-1
20	95	---	X	----	III-B	Petersburg Borough	**Waterfront Pre-Treatment Plan** - In association with construction of a vessel haul-out facility, construct a concrete washdown pad with filtration system, extend the sewer collection system, construct a new sewer lift station, grit chamber, oil water separator, filter vault, and a utility building with a hydronic boiler. Discharges from the vessel washdown pad will be pre-treated prior to entering the sanitary system and will be subject to standards required by EPA in the discharge permit.	$3,196,033	Tier 2	$0	---	---	20 to 30	TBD	SFY25-2
21	95	---	X	---	---	Russian Mission	**Russian Mission Landfill and Access Road –** Refinance a US Department of Agriculture Rural Development loan that provides financial assistance for a project that will cap and close an existing landfill as well as construct a new landfill.	$140,000	Tier 4	$0	---	---	5 to 20	10/31/2026	SFY26-4
22	90	---	X	---	III-B	Wasilla	**Wasilla Wastewater Treatment Facility Upgrades** – Construct additional digestors, required piping, and a shared operational facility that would house new blowers for the digestor operations as well as de-water equipment to improve treatment capacity at the Wastewater Treatment Plant for domestic wastewater and septic tank solids.	$6,000,000	Tier 4	$1,400,000	---	---	20 to 30	7/15/2026	SFY26-3
23	90	---	X	AKG521030	VII	Homer	**Bay Ave Lift Station Replacement** - Replace a 30-year old damaged sewer lift station with non-functional hatch lid, poorly located within a street intersection, by relocating to new location.	$660,000	Tier 2	$500,000	---	---	20 to 30	5/14/2027	SFY26-4
24	90	---	X	---	TBD	Deering	**Deering Sewer Expansion -** Construct a two-cell lagoon, an above ground 3,000-foot force main, and replace faulty vacuum valves and broken toilets.	$2,117,280	Tier 4	$2,000,000	---	---	20 to 30	8/31/2026	SFY27-1
25	85	---	X	AKG521030	VII	Homer	**Lift Station SCADA Upgrades** - Replace the outdated SCADA system to reduce security risk and increase functionality of eight lift stations.	$350,000	Tier 2	$0	---	---	20 to 30	5/14/2027	SFY26-4
26	65	---	X	AKG573025	I	Togiak	**Lagoon Dredging** - Design for de-watering, engineering services, dredging of the lagoon to re-attain the original treatment volume, de-watering the sludge, and disposal costs for de-watered sludge, or purchasing the dredging equipment, de-watering bags, and necessary accessories that will allow the City to dredge the lagoon and dispose of the de-watered debris.	$2,000,000	Tier 4	$2,000,000	---	---	20 to 30	TBD	SFY26-1
27	60	X	X	AK0022951	I	Juneau	**Pyrolysis of Per- and Polyfluorinated Substances (PFAS)-Impacted Biosolids -** Add a pyrolysis thermal treatment at the Mendenhall Wastewater Treatment Plant to treat biosolids to avoid shipping PFAS-impacted biosolids out-of-state for disposal. In addition, this project proposes improvements to the Supervisory Control and Data Acquisition Industrial Control System. This project is partially funded through an Emerging Contaminants loan executed in April 2026.	$8,750,000	Tier 1	$0	---	---	5 to 20	4/1/2026	SFY25-1
28	55	---	X	---	III-B	Kodiak	**Aleutian Homes Phase VII Sewer Replacement** - Replace approximately 2,100 feet of 70-year-old sewer main, services lines, and manholes.	$3,600,000	Tier 1	$0	---	---	20 to 30	8/1/2026	SFY26-2
29	50	---	X	----	III-B	Petersburg Borough	**SCADA Rehabilitation and Upgrade Project** – Replace the outdated remote telemetry units throughout the collection system by installing and configuring a new SCADA system to provide advanced monitoring, alarm notifications, and protection devices on the power supply units for the wastewater plant and major lift stations.	$250,000	Tier 2	$0	---	---	20 to 30	5/1/2026	SFY26-3
30	50	---	X	AK0053481	---	Kodiak Island Borough	**Kodiak Island Borough Landfill Cell 2 Design** – Design Cell 2 at the landfill to include a fully engineered liner system, leachate collection infrastructure, stormwater controls, access roads, and gas management components as necessary. The design will optimize available space while incorporating environmental protection measures to safeguard surrounding soil, groundwater, and surface water resources.	$3,000,000	Tier 2	$500,000	---	---	5	4/1/2026	SFY26-2
31	45	---	X	AKG521030	VII	Homer	**WWTP Clarifier Coating Replacement** - Remove the existing coating from the clarifiers and apply a new coating that meets current industry standards for performance and longevity.	$765,000	Tier 2	$0	---	---	20 to 30	10/1/2026	SFY26-4
32	45	---	X	AKG521030	VII	Homer	**WWTP Digester Coating Replacement** - Remove the coating from the digesters and apply a new coating that meets current industry standards for performance and longevity.	$490,000	Tier 2	$0	---	---	20 to 30	10/1/2026	SFY26-4
33	40	---	X	AK0021385	II	Haines Borough	**Recondition WWTP Clarifier and Tanks** – Recondition Haines Wastewater Treatment Plant's clarifier steel tank, the concrete digester tank, weir, and chlorine contact chamber along with the replacement of the aeration valves, piping, and diffusers.	$80,000	Tier 4	$80,000	---	---	20 to 30	TBD	SFY25-1
34	35	---	---	---	III-B	Bethel	**Hauled Utilities Operation Center** – Design and construct a new hauled utilities operation center with at least two sallyport bays to separate the sewer haul trucks and water haul trucks to reduce contamination risks.	$30,096,000	Tier 4	$0	---	---	5 to 20	4/1/2026	SFY26-3
35	35	---	X	---	III-B	Petersburg Borough	**Wastewater Disinfection Study -** Conduct an engineering and design study to determine the appropriate path for developing and constructing a disinfection facility to comply with new fecal coliform discharge limits.	$150,000	Tier 4	$150,000	---	---	20 to 30	7/1/2026	SFY27-1

Rank	Score	Potential Equivalency Project	Within Funding Limits [1]	APDES Permit Number	Clean Water Needs Category	Applicant	Project Name and Description	Requested Loan Amount	Disadvantaged Community Tier	Subsidy [2] Loan Forgiveness	Green Project Category	Green Project Estimate	Requested Loan Term	Anticipated Project Start Date	Added to PPL
36	25	---	X	AK0021890	I	Seward	**Public Works Facility: Wastewater** – Build a new facility to house public works departments including personnel, equipment, materials and supplies for the water, wastewater, and street departments. The estimated cost is the portion of the building planning, design and construction associated with the wastewater utility.	$7,626,925	Tier 2	$0	---	---	20 to 30	9/25/2026	SFY26-2
37	15	---	X	---	TBD	Nome Joint Utility System	**Utility Equipment Amendment** - Replace aging equipment such as the Vactor truck, Digger Derrick, fuser, and pickup trucks which are used to maintain and repair vital water and sewer systems.	$1,007,500	Tier 3	$0	---	---	5 to 20	TBD	SFY25-1
38	10	---	X	---	III-B	Bethel	**High Pressure Jetters** - Purchase two dual gas jetters with a hotbox to heat water to thaw frozen sewage pipes.	$80,000	Tier 4	$0	---	---	5	6/20/2026	SFY26-4
							SUBTOTAL	***$154,147,335***		***$16,192,197***		***$1,390,000***			
SUSTAINABLE INFRASTRUCTURE PLANNING PROJECT QUESTIONNAIRES															
1	45	---	X	AK0021440	---	Ketchikan	**Infiltration and Inflow Study** - Conduct a study to identify sources of excessive inflow/infiltration to the wastewater treatment plant and make recommendations for needed repairs.	$75,000	Tier 2	$75,000	---	---	Less than 5	6/2/2025	SFY25-3
2	45	---	X	---	III-B	Bethel	**Sewer Haul Truck System Assessment** - Conduct an assessment and evaluation to optimize performance and energy/fuel use of the existing hauled sewer system.	$37,500	Tier 4	$37,500	---	---	5	6/1/2026	SFY26-4
3	40	---	X	----	III-B	Petersburg Borough	**Infiltration and Inflow (I&I) Study** – Complete a study to identify sources of I&I in the collection system using flow monitoring, closed circuit television (CCTV), or other appropriate methods and identify sections of the collection system that require repairs.	$200,000	Tier 2	$75,000	---	---	20 to 30	5/1/2026	SFY26-3
4	35	---	X	AK0021385	II	Haines Borough	**Beach Road Sewer Main Rehabilitation Design** – Design a plan to address deficiencies and non-compliant connections of sewer main along Beach Road.	$75,000	Tier 4	$75,000	---	---	5 to 20	2/2/2026	SFY26-4
5	35	---	X	---	III-B	Petersburg Borough	**Pre-Treatment Program Development -** Design and develop a pretreatment program to prevent point source pollutants from entering the wastewater collection system.	$150,000	Tier 2	$75,000	---	---	20 to 30	7/1/2026	SFY27-1
							SUSTAINABLE INFRASTRUCTURE PLANNING LOAN SUBTOTAL	***$537,500***		***$337,500***		***$0***			
MICRO LOAN QUESTIONNAIRES (UPPER LIMIT OF $500,000)															
1	55	---	X	----	---	Hooper Bay	**Equipment Purchase -** Replace aging equipment used to maintain the sewer lagoon and to repair sewer lines damaged due to extreme weather events and other hazards.	$500,000	Tier 4	$500,000	---	---	10	TBD	SFY24-1
2	25	---	X	AKG573025	---	Togiak	**Vacuum/Jetter Truck** - Purchase a vacuum or a vacuum/jetter combo truck to assist in removing debris and sludge from sewer lines and septic systems.	$500,000	Tier 4	$500,000	---	---	30	TBD	SFY26-1
							MICRO LOAN SUBTOTAL	***$1,000,000***		***$1,000,000***		***$0***			
NONPOINT SOURCE PROJECT QUESTIONNAIRES															
1	80	---	X	---	VII-E	Nome Joint Utility System	**Tank Farm Relocation** - Perform site assessment and/or complete remediation associated with the site of the aboveground fuel storage tanks.	$4,500,000	Tier 3	---	---	---	5 to 20	TBD	SFY25-3
3	75	---	X	----	III-B	King Cove	**Landfill Cell Capping and Closure** – Complete a partial closure of the King Cove Landfill system as required by State regulations (18 ACC 60.390) to stabilize slopes and minimize infiltration of liquids, prevent soil erosion, and protect against the release of hazardous constituents into King Cove Bay.	$59,390	Tier 3	$59,390	---	---	5 to 20	2/28/2026	SFY26-3
4	60	X	X	----	III-B	Anchorage	**Interim Landfill Covering Plan and Implementation –** Evaluate current landfill operations, forecast future disposal needs, and develop an Interim Landfill Covering Plan to reduce stormwater infiltration and leachate generation at the facility. Based on the evaluation, place interim cover over approximately 40 percent of the existing landfill footprint.	$3,500,000	Tier 1	---	---	---	20 to 30	4/30/2026	SFY27-1
5	0	---	X	----	II	Fairbanks North Star Borough	**Cell 2 & 3 Partial Closure** – Complete a partial closure of cells 2 & 3 at the Fairbanks Solid Waste Facility to prevent runoff into the drainage canals that lead into the Tanana River.	$7,000,000	Tier 1	---	---	---	5	7/1/2027	SFY26-3
							NONPOINT SOURCE SUBTOTAL	***$15,059,390***		***$59,390***		***$0***			
AMENDMENT TO EXISTING LOAN AGREEMENT															
1	145	---	X	AK0021440	III-B	Ketchikan	**Water St Sewer Mains –** Replace/Rehabilitation – Change in scope and increase in loan amount for 481211-S. Replace or rehabilitate existing sewer lines and other elements that have been determined to be significant contributors to inflow and infiltration at the Charcoal Point Wastewater Treatment Plan and also contribute to a general decline in water quality in the area.	$2,500,000	Tier 2	$500,000	Energy Efficiency	TBD	5 to 20	11/1/2027	SFY26-4
3	60	---	X	AK0022497	I	Palmer	**Headworks Rehabilitation** - Increase in loan amount for loan 671331-SE. Complete engineering and design, including construction documents, for the rehabilitation and improvement of the headworks building and installation of a tertiary filter/screening system after the secondary clarifiers.	$500,000	Tier 2	$500,000	---	---	20 to 30	2/1/2026	SFY26-4

Rank	Score	Potential Equivalency Project	Within Funding Limits [1]	APDES Permit Number	Clean Water Needs Category	Applicant	Project Name and Description	Requested Loan Amount	Disadvantaged Community Tier	Subsidy [2] Loan Forgiveness	Green Project Category	Green Project Estimate	Requested Loan Term	Anticipated Project Start Date	Added to PPL
4	---	---	X	AK572028	III-B	Ketchikan Gateway Borough	**Forest Park Drive Sewer Mains Replacement** – Change in scope for loan 482021. Replace approximately 2,200 linear feet of piping, manholes, and sewer stubs due to circumferential deformity, joint displacement, penetrating roots, bellies, and fats-oils-grease buildup contributing to potential backups and discharges of untreated wastewater. Work may also entail addressing inflow and infiltration issues by replacing corroded cross-road culverts and relocation of services as necessary to be below the depth of adjoining ditches.	---	Tier 2	---	---	---	20 to 30	7/1/2026	SFY26-2
5	---	---	X	2007-DB0003	III-B	Nome Joint Utility System	**Bering St/Seppala Dr Water and Sewer Improvements** – Change in Scope for Loan 627251-SG: Replace leaking sections of 40-year-old Sclaircore direct bury sewer main and replace spot sections of pipe due to sagging in coordination with an Alaska Department of Transportation and Public Facilities project.	---	Tier 3	---	---	---	5 to 20	5/26/2025	SFY25-3
6	---	---	X	AK0021474	II	Sitka	**Lake and Monastery Sewer Improvements –** Increase in loan amount for 783251-GE. Replacement of approximately 2,430 linear feet of sewer main, 11 manholes, and 47 sewer services on Lake, Monastery, Kinkead, and Hirst Streets.	$2,450,000	Tier 1	---	Energy Efficiency	$298,000	20 to 30	9/15/2026	SFY26-3
							LOAN AMENDMENTS SUBTOTAL	***$5,450,000***		***$1,000,000***		***$298,000***			
							Total Funding Requested (All Categories)	***$ 176,194,225***		***$18,589,087***		***$1,688,000***			

Alaska Clean Water Fund
Programmatic Financing (Pro Fi) Projects

Applicant: Anchorage Water and Wastewater Utility
SFY26 Loan Request on PPL: $26,664,500
Loan Repayment Term: 20 years

Year			SRF #	Sub Project Name	Description
SFY25	SFY26		C-19-05f	King Street Fuel Storage Improvements	Relocate the existing fuel storage and dispensing system. This project will also streamline the traffic pattern within the facility.
SFY25	SFY26		C-22-02	Pump Station (PS) 12 Force Main Interceptor C - Gravity Junction Rehab	Assess and rehabilitate Pump Station 12, force mains, gravity junction box, and the receiving 48-inch gravity sewer. The culverts that support the force mains for the Campbell Creek crossing will also be assessed and rehabilitated as part of the project.
SFY25	SFY26		C-24-01	Eagle River Wastewater Treatment Facility (ERWWTF) Ultraviolet (UV) and Washwater Upgrades	Increase ultraviolet (UV) disinfection capacity to address current Alaska Pollutant Discharge Elimination System (APDES) permit limits for fecal coliform effective March 1, 2020. Rehabilitate deficiencies identified during the preparation of the ERWWTF Plan.
SFY25	SFY26		C-25-01	FOG Receiving Station	Investigate, recommend improvements, design, and construct energy efficient and other related performance contracting services. Recommended improvements may include energy efficient lighting upgrades, HVAC and control upgrades, a pressure wash system at the Girdwood WWTF, and a new Fats, Oil and Grease (FOG) receiving station.
SFY25	SFY26		C-25-02	Girdwood I-I PhIA (previously identified as Girdwood R&R Ph1)	Upgrade 17 sewer services which include approximately 512 feet of sewer service replacement, dewatering, sewer flow control, traffic control, creek by-passing, landscaping and surface restoration.
	SFY26			Eagle River Wastewater Treatment Facility (ERWWTF) Tertiary Filter Improvements	Replace sand filter at ERWWTF with compressible media filters, disk filters or pile cloth filters.
	SFY26			Algot Strom Subdivision Sewer Upgrades	Replace existing 4-inch pipe with 8-inch sewer main.
	SFY26			Worst Subdivision Sewer Lining	Rehabilitate 16-inch sewer trunk in Worst Subdivision.
	SFY26			Anchorage Wastewater Treatment Facility (AWWTF) NPDES Permit Renewal	Renew AWWTF NPDES permit.
	SFY26			King Street Warm Storage Building Upgrade	Develop new warm vehicle storage building to house equipment necessary to maintain the AWWU water and sewer infrastructure.
		SFY27		Anchorage International Airport (AIA) C Concourse Sewer Rehabilitation	Rehabilitate approximately 270 linear feet of corrugated metal pipe and asbestos concrete pipe that has structural deficiencies.
		SFY27		Campbell View Sewer Rehabilitation	Rehabilitate approximately 287 linear feet of 8-inch ductile iron sewer main that has structural deficiencies along an unnamed road segment south of West Dimond Boulevard and west of Blackberry Street.
		SFY27		AWWTF Sludge Dewatering II	Replace aged sludge dewatering equipment.
		SFY27		Eagle River WWTF Polymer System	Replace the existing polymer system that is beyond its useful life.
		SFY27		W 42nd Beechcraft Constellation Sewer Rehabilitation	Rehabilitate approximately 1,200 linear feet of asbestos concrete and ductile iron pipe at the end of its useful life.
		SFY27		Spenard Barbara Forrest Sewer Rehabilitation	Rehabilitate approximately 300 linear feet of ductile iron sewer main in degraded structural condition.
		SFY27		West 58th and Arctic Sewer Rehabilitation	Replace approximately 535 linear feet of sewer main and 3 manholes.
		SFY27		Girdwood I-I Phase IIA	Rehabilitate 100 manholes.

Alaska Clean Water Fund
Programmatic Financing (Pro Fi) Projects

Applicant: City and Borough of Juneau
Loan Request on PPL: $1,770,000
Loan Repayment Term: 20 years

Number	Sub Project Name	Description
CBJ-PF-CW-01	Downtown Streets - South Franklin to Thune	Design the replacement of aging wastewatercollection system including sewer mains, valves, services, manholes, cleanouts, bypass structure and other appurtenances under the state road through downtown Juneau.
CBJ-PF-CW-02	Glacier Highway - Ross Way to Salmon Creek	Design the replacement of aging wastewatercollection system including sewer mains, valves, services, manholes, cleanouts, bypass structure and other appurtenances
CBJ-PF-CW-03	Foster Avenue	Design the replacement of aging wastewatercollection system including sewer mains, valves, services, manholes, cleanouts, bypass structure and other appurtenances
CBJ-PF-CW-04	Gruening Park Forcemain	Assess condition of the forcemain. Design the replacement or rehabilitation of the forcemain, as appropriate.