AUTHORIZATION TO DISCHARGE UNDER THE ALASKA POLLUTANT DISCHARGE ELIMINATION SYSTEM

FOR

GENERAL PERMIT AKG315100 - MOBILE OIL AND GAS EXPLORATION FACILITIES IN STATE WATERS IN COOK INLET

ALASKA DEPARTMENT OF ENVIRONMENTAL CONSERVATION
Wastewater Discharge Authorization Program
555 Cordova Street
Anchorage, AK 99501

In compliance with the provisions of the Clean Water Act (CWA), 33 U.S.C. Part1251 et seq., as amended by the Water Quality Act of 1987, P.L. 100-4, this permit is issued under provisions of Alaska Statutes (AS) 46.03; the Alaska Administrative Code (AAC) as amended; and other applicable State laws and regulations.

Owners and operators of facilities engaged in oil and gas exploration, located in Cook Inlet within Offshore and Coastal Subcategories of the Oil and Gas Extraction Point Source Category (40 CFR 435, Subparts A and D) are authorized to discharge to waters of the United States, only in accordance with effluent limits, monitoring requirements, and other conditions set forth herein.

A COPY OF THIS GENERAL PERMIT

MUST BE KEPT AT THE SITE WHERE DISCHARGES OCCUR.

This permit is effective **March 9**, 2015.

This permit and the authorization to discharge shall expire at midnight on March 8, 2020.

The applicant shall reapply for a permit reissuance on or before December 7, 2019, 90 days before the expiration of this permit.

Wade Strickland	February 6, 2015
Signature	Date
Wade Strickland	Program Manager
Printed Name	Title

TABLE OF CONTENTS

1.0 PERMIT COVERAGE 6

1.1 Coverage and Eligibility 6
1.2 Notice of Intent Review and Permit Coverage Determination Process 6
1.3 Authorized Discharges 8
1.4 Prohibitions 8
1.5 Requiring an Individual Permit 10
1.6 Notification Requirements 11
1.7 Permit Expiration 11

2.0 LIMITS AND MONITORING REQUIREMENTS 12

2.1 Requirements for all Discharges 12
2.2 Requirements for Drilling Fluids and Drill Cuttings (Discharge 001) 13
2.3 Requirements for Deck Drainage (Discharge 002) 23
2.4 Requirements for Domestic Wastewater (Discharge 003) 23
2.5 Requirements for Graywater (Discharge 004) 25
2.6 Requirements for Miscellaneous Discharges (Discharges 005-013) 26
2.7 Requirements for Test Fluid Discharges (019) 28
2.8 WET Testing Requirements 29
2.9 Reporting of Monitoring Requirements 32
2.10 Mixing Zone and Modification of Effluent Limits 33
2.11 Best Management Practices Plan 34
2.12 Cooling Water Intake Structure Requirements 36
2.13 Removed Substances 37

3.0 SPECIAL CONDITIONS 38

3.1 Quality Assurance Project Plan 38

APPENDIX A STANDARD CONDITIONS A-1

APPENDIX B ACRONYMS B-1

APPENDIX C DEFINITIONS C-1

APPENDIX D COOK INLET COVERAGE AREA D-1

APPENDIX E SPP METHOD E-1

APPENDIX F PROTOCOL FOR THE DETERMINATION OF DEGRADATION OF NON-AQUEOUS BASED FLUIDS IN A MARINE CLOSED BOTTLE BIODEGRADATION TEST SYSTEM: MODIFIED ISO 11734 ..... F-1

APPENDIX G DETERMINATION OF CRUDE OIL CONTAMINATION IN NON-AQUEOUS DRILLING FLUIDS BY GAS CHROMATOGRAPHY/MASS SPECTROMETRY (GC/MS) G-1

APPENDIX H CWA Part 316(b) Cooling Water Intake Structure (CWIS) Requirements H-1

ATTACHMENT 1 NOTICE OF INTENT INFORMATION 1-1

ATTACHMENT 2 NONCOMPLIANCE NOTIFICATION..... 2-1

LIST OF TABLES

Table 1: Schedule of Submissions 4

Table 2: Effluent Limitations and Monitoring Requirements for Drilling Fluids and Drill Cuttings (Discharge 001)..... 14

Table 3: Effluent Limitations and Monitoring Requirements Deck Drainage (Discharge 002)..... 23

Table 4: Effluent Limitations and Monitoring Requirements for Domestic Wastewater (Discharge 003) 24

Table 5: Effluent Limitations and Monitoring Requirements for Graywater (Discharge 004) 25

Table 6: Effluent Limitations and Monitoring Requirements for Miscellaneous Discharges 005-013.... 26

Table 7: WET Trigger Levels for Surface Discharges 27

Table 8: WET Trigger Levels for Submerged Pipe Discharges 28

Table 9: Effluent Limitations and Monitoring Requirements for Test Fluids (019) 28

Table E- 1: Conditions[1] for conducting 96 hour NAF and 10-day SBM sediment toxicity test with *L plumulosus* E-12

Table E- 2: Test acceptability requirements[1] for 10-day NAF and 96 hour SBM test with *L plumulosus* E-13

Table E- 3: Culture conditions for L plumulosus E-14

Table F- 1: Test Acceptability Criteria F-9

Table G- 1: Gas Chromatograph/Mass Spectrometer (GS/MS) Operating Conditions..... G-10

Table G- 2: Approximate Retention Times for Compounds G-10

Table G- 3: Recommended Ion Mass Numbers..... G-13

SCHEDULE OF SUBMISSIONS

The Schedule of Submissions summarizes some of the required submissions and activities the applicant must complete and/or submit to the Alaska Department of Environmental Conservation (DEC or Department) during the term of this permit. All deadlines for the Schedule of Submissions are based on the postmark date of the submittal. The applicant is responsible for all submissions and activities even if they are not summarized below.

Table 1: Schedule of Submissions

Permit Part	Submittal	Frequency	Due Date	Submit Documentation To*
1.1.2 and 1.6	Notice of Intent (NOI) for new applicants to discharge from a new, recommencing, or expanding facility	1/permit cycle	45 days prior to discharge	Permitting – Appendix A, Part 1.1.1.
1.1.2	NOI for an existing permittee authorized under the Environmental Protection Agency (EPA) - issued AKG315000 (2007 EPA-issued Permit)	1/permit cycle	45 days prior to discharge	Permitting
1.1.2 and 1.6.2	Plans and Report supporting Request for Waiver from Minimum Treatment requirements, or documentation of previous plan and waiver approvals.	1/permit cycle	With submittal of NOI (Attachment 1)	Permitting – Appendix A, Part 1.1.1.
1.7	NOI for an authorized applicant if the applicant intends to continue operations and discharges beyond the term of this permit	1/permit cycle	90 days before expiration of the general permit	Permitting – Appendix A, Part 1.1.1.
2.11	Best Management Practices (BMP) Plan Certification	1/permit cycle	BMP Plan shall be ready to implement upon submittal of an NOI, the applicant shall certify in writing that the BMP Plan has been prepared and is ready to implement prior to initial discharge	Compliance – Appendix A, Part 1.1.1.
2.2.8.	Drilling Fluids Plan	1/permit cycle	The Drilling Fluids Plan (DFP) shall be submitted with, or prior to, a complete NOI for review and comment.	Permitting
2.2.8.2	Environmental Study Plan	1/permit cycle	The Environmental Study Plan shall be submitted with, or prior to, a complete NOI for review and comment.	Permitting
2.2.7.5	Environmental Reports	1/year/site	180 Days following final sample collection.	Compliance

Permit Part	Submittal	Frequency	Due Date	Submit Documentation To*
2.2.6.2	End-of-Well (EOW) Report	1/Well	90 Days following well completion	Compliance
2.9.1	Discharge Monitoring Reports (DMRs)	1/month	20th day following the discharge period.	Compliance
3.1.1	Quality Assurance Project Plan (QAPP)	1/Permit cycle	QAPP shall be ready to implement upon submittal of an NOI, the applicant shall certify in writing that the QAPP Plan has been prepared and is ready to implement 45 days prior to initial discharge	Compliance
Appendix A 3.4.1	Oral notification of noncompliance	As Necessary	Within 24 hours from the time the applicant becomes aware of the circumstances of noncompliance	Compliance – Appendix A, Part 1.1.2.
Appendix A 3.4.1	Written documentation of noncompliance	As Necessary	Within five business days after the applicant becomes aware of the circumstances	Compliance – Appendix A, Part 1.1.2.
* See Appendix A Part, 1.1 for addresses				

1.0 PERMIT COVERAGE

1.1 Coverage and Eligibility

1.1.1 Existing *mobile* facilities for oil and gas exploration in Cook Inlet that have obtained coverage under the 2007 EPA-issued Permit (existing permittee): Owners or operators of existing mobile facilities with administratively extended coverage under the 2007 EPA-issued Permit will be granted coverage upon submitting an updated and complete Notice of Intent (NOI) and documentation of wastewater plan and (if applicable) waiver approvals in accordance with 18 AAC 72. See Section 1.6 for notification requirements.

1.1.2 Applicants for new mobile oil and gas exploration facilities (new applicants) that meet the criteria for coverage under this permit will be granted coverage upon submittal of a complete NOI in accordance with 18 AAC 83.210(b), treatment system plan review per 18 AAC 72.200 and 72.600, and (if applicable) a waiver request for minimum treatment requirements per 18 AAC 72.060. See Permit Part 1.6 for notification requirements prior to discharging within state waters in Cook Inlet.

1.1.3 An applicant eligible for a waiver of the secondary treatment requirements under 18 AAC 72.050(a)(4) will be authorized to discharge graywater under this permit. Discharged graywater must meet primary treatment standards (as defined under 18 AAC 72.990(50)(B)). See Permit Part 1.2 for NOI submittal requirements.

1.1.4 An applicant may request a mixing zone authorization from DEC by completing the mixing zone section of the NOI.

1.1.5 Authorization to discharge requires written notification from the Department that coverage has been granted, that a mixing zone has been authorized (if applicable), and that a specific permit number has been assigned to the operation.

1.2 Notice of Intent Review and Permit Coverage Determination Process

1.2.1 An applicant must submit a complete NOI form (See ATTACHMENT 1) and all required plans, engineering reports, and (if applicable) a request to waive the minimum treatment requirements associated with 18 AAC 72.050.

1.2.2 An existing permittee must submit a complete NOI form (See ATTACHMENT 1) and BMP certification along with documentation of approved plans, engineering reports, and (if applicable) a waiver for minimum treatment requirements associated with 18 AAC 72.050.

1.2.3 The Department will review a NOI for completeness and accuracy. If an NOI is found to be incomplete, the Department will notify the applicant of the needed changes to the NOI submittal.

1.2.4 Prior to discharging to waters of the United States (US), an applicant must submit plans for approval per 18 AAC 72.200 and/or 18 AAC 72.600. The plans shall be prepared by a licensed Alaska engineer and submitted with the NOI and be accompanied by the appropriate fee required by 18 AAC 72.955.

1.2.5 Under 18 AAC 72.060, an applicant may request a waiver from the requirements of 18 AAC 72.050(a)(4) by submitting an engineering report in accordance with 18 AAC 72.050(d)(1)-(5) and 18 AAC 72.060(b). The engineering report shall be prepared by a licensed Alaska engineer, submitted with the NOI, and be accompanied by the appropriate fee required by 18 AAC 72.955.

1.2.6 The Department will review the engineering plans and report to determine if the request for waiver of minimum treatment requirements of 18 AAC 72.050 should be granted and if the applicant is eligible for coverage under this permit. This determination will be made prior to authorization under this permit.

1.2.7 The Department will make a determination regarding the appropriateness of granting permit coverage at a proposed discharge location or area of operation.

1.2.7.1 Location coordinates provided in the NOI for each proposed discharge location or area of operation will be used to determine if a discharge is prohibited by this permit or would require application for an Alaska Pollutant Discharge Elimination System (APDES) individual permit.

1.2.8 The Department will review the applicant submittal to authorize a standard sized cylindrically shaped 100 meter mixing zone for specific discharges and parameters per Section 2.10.

1.2.8.1 When authorizing a standard size cylindrically shaped 100 meter mixing zone, the Department will consider whether the discharges requested are consistent with permit conditions.

1.2.9 Upon completion of the NOI review, the Department will either:

1.2.9.1 Prepare and transmit a written coverage determination specifying whether (1)

The information required by 18 AAC 72.050(d)(1) – (5) is sufficient to waive minimum treatment requirements required by 18 AAC 72.050, and (2) a standard size cylindrically shaped mixing zone is authorized per Section 2.9; or

1.2.9.2 Notify the applicant of needed changes to the NOI submittal; or

1.2.9.3 Deny coverage under the permit and require an applicant to submit an individual permit application.

1.3 Authorized Discharges

1.3.1 This permit authorizes and places conditions on discharges from mobile oil and gas exploration facilities that are located within Cook Inlet (see Figure 1) under the Offshore and Coastal Subcategories of the Oil and Gas Extraction Point Source Category (40 CFR Part 435, Subparts A and D) as adopted by reference at18 AAC 83.010(g)(3).

1.3.2 This permit authorizes the following discharges from mobile facilities related to oil and gas exploration:

Discharge Number	Discharge Description
001	Drilling Fluids and Drill Cuttings
002	Deck Drainage
003	Domestic Wastewater
004	Graywater
005	Desalination Unit Wastes
006	Blowout Preventer Fluid
007	Boiler Blowdown
008	Fire Control System Test Water
009	Non-Contact Cooling Water
010	Uncontaminated Ballast Water
011	Bilge Water
012	Excess Cement Slurry
013	Mud, Cuttings, and Cement at the Seafloor
019	Test Fluids

1.4 Prohibitions

1.4.1 This permit prohibits the discharge of any waste streams, including spills and other unintentional or non-routine discharges of pollutants that are not part of the normal operation of the facility.

1.4.2 This permit prohibits the discharge to any receiving water that is listed on the Clean Water Act (CWA) Section 303(d) list as impaired for failure to meet a water quality standard (WQS) and the facility discharges a pollutant that causes or contributes to the impairment.

1.4.3 This permit prohibits the discharge of any pollutant that is not expressly authorized in the permit.

1.4.4 This permit prohibits discharges shoreward of the 10-meter mean lower low water (MLLW) isobaths. The applicant is responsible for clearly identifying sites in the NOI with respect to prohibited areas to demonstrate applicability of coverage under the permit. The area of coverage for the permit is generally depicted in the figure in Appendix D.

1.4.5 An applicant should contact DEC if there is uncertainty whether discharges will be located in a prohibited area. This permit prohibits discharges to the following areas:

1.4.5.1 Within the boundaries or within 4,000 meters of a coastal marsh, river delta, river mouth, designated State Game Refuge, State Game Sanctuary, State Critical Habitat Area, National Park, or Area Meriting Special Attention (ASMA). The seaward edge of a coastal marsh is defined as the seaward edge of emergent wetland vegetation.

1.4.5.1.1 The following are located in the vicinity of the permit coverage area:

State Game Refuge:	Susitna Flats Trading Bay
State Critical Habitat Area:	Kalgin Island Redoubt Bay Clam Gulch Kachemak Bay
National Park:	Lake Clark
ASMA:	Port Graham/Nanwalek

1.4.5.1.2 The legal descriptions of state specialty areas are found in AS 16.20 Conservation and Protection of Alaska Fish and Game. Further Information can be obtained from:

Alaska Department of Fish and Game (ADF&G)
333 Raspberry Road
Anchorage, AK 99501
Phone (907) 267-2342

Or

ADF&G Division of Habitat Soldotna Office
514 Funny River Road
Soldotna, AK 99669
Phone (907) 714-2475

1.4.5.2 In Kamishak Bay, west of the line from Cape Douglas to Chinitna Point.

1.4.5.3 In Chinitna Bay, inside of the line between the points of the shoreline at latitude 59˚52’45” N, longitude 152˚48’18” W on the north and latitude 59˚46’12” N, longitude 153˚00’24” W on the south (Figure 1).

1.4.5.4 In Tuxedni Bay, inside of the lines on either side of Chisik Island (Figure 1).

1.4.5.4.1 From latitude 60˚04’06” N, longitude 152˚34’12” W on the mainland to the southern tip of Chisik Island (latitude 60˚05’45” N, longitude 152˚33’30” W).

1.4.5.4.2 From the point on the mainland at latitude 60˚13’45” N, longitude 152˚32’42” W to the point on the north side of Snug Harbor on Chisik Island (latitude 60˚06’36” N, longitude 152˚32’54” W).

1.4.5.5 Within tracts identified in the Alaska Department of Natural Resources, Oil and Gas Division’s Mitigation Measure Analysis: Cook Inlet, revised March 2012.

1.5 Requiring an Individual Permit

1.5.1 The Department may require an applicant authorized to discharge under a general permit to apply for and obtain coverage under an individual permit, or any interested person may petition the Department to take this action.

1.5.2 The Department will notify the applicant in writing by certified mail that an individual permit application is required. If an applicant fails to submit an individual permit application by the date required in the notification, coverage under this permit is automatically terminated at the end of the day specified for application submittal.

1.5.3 An applicant authorized by this permit may request to be excluded from the coverage of this permit by applying for an individual permit. The applicant shall submit an individual permit application (APDES permit application Form 1 and Form 2C and Form 2M if applicable) with reasons supporting the request to the Department at the address in Appendix A, Part 1.1.1.

1.5.4 When an individual permit is issued to an applicant otherwise covered by this permit, the applicability of this permit to the applicant is automatically terminated on the effective date of the individual permit.

1.5.5 When an individual permit is denied to an applicant otherwise covered by this permit, the applicant is automatically reinstated under this permit on the date of such denial, unless the applicant cannot meet the conditions of the permit or otherwise specified by the Department.

1.5.6 An applicant excluded from this permit solely because the applicant already has an individual permit may request that the individual permit be revoked and that the applicant be covered by this permit. Upon revocation of the individual permit, and if the applicant can comply with the terms of this permit, this permit shall apply to the applicant.

1.6 Notification Requirements

1.6.1 To obtain permit coverage as a first time permittee of a mobile exploration facility eligible for this permit, the new applicant of a mobile exploration facility shall submit plans and engineering reports necessary to obtain approval to discharge and receive approval of a waiver from minimum treatment requirements if applicable. The information shall be submitted with a complete NOI and an engineering report supporting the request for a waiver from minimum treatment requirements as described in ATTACHMENT 1 of this permit.

1.6.1.1 Notification must be made 45 days prior to discharge from a new, recommencing, or expanded facility.

1.6.2 An existing permittee of a mobile exploration facility who submitted an NOI prior to the expiration date of the EPA-issued 2007 Permit AKG-31-5000 is required to submit a new NOI along with documentation demonstrating previous approval of plan review and waiver from minimum treatment requirements under 18 AAC 72.060, if applicable.

1.6.3 The NOI shall be signed by the owner, or other signatory authority, in accordance with Appendix A, Part 1.12 (Signature Requirements), and a copy must be in accordance with Appendix A, Part 1.11 (Monitoring and Records).

1.6.4 The permittee must notify DEC in writing at least 30 days prior to recommencing discharges after cessation of seasonal drilling activities or when relocating to a different drilling site.

1.6.5 A mixing zone request may be included with the NOI.

1.6.6 The Department will authorize a standard size cylindrically shaped 100 meter radius mixing zone centered over the outfall pipe or discharge pipe terminus and extending from the sea floor to the sea surface.

1.6.7 The applicant must submit an NOI to DEC at the address in Appendix A, Part 1.1.1.

1.7 Permit Expiration

This permit will expire at midnight on March 8, 2020. A permittee wishing to continue coverage under a reissued permit must submit a new NOI at least 180 days prior to the expiration of this permit, as described in Standard Conditions, Appendix A, Part 1.3.

2.0 LIMITS AND MONITORING REQUIREMENTS

2.1 Requirements for all Discharges

2.1.1 During the effective period of this permit, the permittee is authorized to discharge pollutants within the area of coverage set forth in Sections 1.4 and Appendix D, in accordance with the limits and conditions set forth herein.

2.1.2 This permit authorizes the discharge of only those pollutants resulting from facility processes, waste streams, and operations that have been clearly identified in the NOI.

2.1.3 The permittee must collect all effluent samples from the effluent stream of each discharge after the last treatment unit prior to discharge into the receiving waters, except as otherwise required by discharge-specific sections of this permit.

2.1.4 The permittee must comply with the effluent limits in this permit at all times unless otherwise indicated, regardless of the frequency of monitoring or reporting required by other provisions of this permit.

2.1.5 Unless specifically addressed in this permit, the permittee shall not discharge free oil, floating solids, debris, sludge, deposits, foam, scum, or other residues of any kind.

2.1.6 The discharge of dispersants to marine waters in response to oil or other hazardous waste spills is not authorized by this permit. The permittee must report all discharges of surfactants, dispersants, and detergents in the EOW Report.

2.1.7 The permittee must separate area drains for washdown and rainfall that may be contaminated with oil and grease from those area drains that would not be contaminated so that the waste streams are not comingled. Deck drainage that is contaminated with oil and grease must be processed through an oil-water separator prior to discharge.

2.1.8 The permittee shall not discharge diesel oil, halogenated phenol compounds, trisodium nitrilotriacetic acid, sodium chromate, or sodium dichromate.

2.1.9 If any discharges are comingled, the most stringent effluent limit for each individual discharge shall be applied to the resulting discharge. If the individual discharge is not authorized, the comingled discharge is not authorized.

2.1.10 If requested, the permittee must provide DEC with a sample of any waste stream in the manner specified by DEC as soon as practicable after the request.

2.1.11 The discharge of maintenance waste such as removed paint and materials associated with surface preparation and coating applications is prohibited. Such materials shall be contained and collected. All collected material shall be disposed of at an appropriate shore-based facility. Prior to conducting sandblasting or similar maintenance activities, operators must develop and implement a BMP plan for the containment, collection and disposal of waste materials.

2.2 Requirements for Drilling Fluids and Drill Cuttings (Discharge 001)

2.2.1 The discharge of non-aqueous based drilling fluids is prohibited except for situations where such fluids adhere to drill cuttings at facilities within the Territorial Seas, as defined 40 CFR Part 435.

2.2.2 In addition to requirements in Section 2.1, the permittee must comply with the following effluent limitations and monitoring requirements:

Table 2: Effluent Limitations and Monitoring Requirements for Drilling Fluids and Drill Cuttings (Discharge 001)

Discharge	Pollutant Parameter	Effluent Limitations	Monitoring Requirements	
		Average Monthly and Maximum Daily Limits	Measurement Frequency	Sample Type
Water-based fluids and cuttings	Suspended Particulate Phase toxicity [1]	Minimum 96-hour LC_{50} of 30,000 ppm	Monthly and End-of-Well [2]	Grab
	Free oil	No discharge [3]	Daily	Grab
	Diesel oil [4]	No discharge	Daily	Grab
	Mercury	1 mg/kg [5]	Once per well	Grab
	Cadmium	3 mg/kg [5]	Once per well	Grab
	Volume Million Gallons (MG)	Report average and maximum daily and monthly total	Monthly	Estimate
	Depth Dependent Discharge Rate 0 to 5 meters >5 to 20 meters >20 to 40 meters >40 meters	No discharge 500 barrels (bbl)/hr 750 bbl/hr 1,000 bbl/hr	Continuous during discharge	Estimate
Non-aqueous fluids	Drilling fluids	No discharge	Daily	Observation
Non-aqueous stock base fluid (C_{16}-C_{18} internal olefin, C_{12}-C_{14} ester or C_8 ester)	Mercury	1 mg/kg [5]	Annual	Grab
	Cadmium	3 mg/kg [5]	Annual	Grab
	Polynuclear Aromatic Hydrocarbons (PAH)	mass ratio [6] < $1x10^{-5}$	Annual	Grab
	Sediment toxicity	ratio [7] < 1.0	Annual	Grab
	Biodegradation rate	ratio [8] < 1.0	Annual	Grab
	Volume (MG)	Report average and maximum daily and monthly total	Monthly	Estimate
Non-Aqueous Fluids (NAF) which adhere to drill cuttings (Territorial Seas Only per 40 CFR Part 435) [15]	Free Oil	No discharge [3]	Daily	Grab
	Diesel oil [2]	No discharge	Daily	Grab
	SPP toxicity [1]	Minimum 96-hour LC_{50} of 30,000 ppm	Monthly and End-of-Well [2]	Grab
	Sediment toxicity	Drilling fluid sediment toxicity ratio [9] < 1.0	Annual	Grab
	Formation oil	No discharge [10]	Daily	Grab
	Base fluid retained on drill cuttings (C_{16}-C_{18} internal olefin stock [11])	6.9 g NAF base fluid/100 g wet drill cuttings [12]	Daily [13]	Grab
	Base fluid retained on drill cuttings [14] (C_{12}-C_{14} ester or C_8 ester stock)	9.4 g NAF base Fluid/100 g wet drill cuttings [12]	Daily [13]	Grab
	Volume (MG)	Report average and maximum daily and monthly total	Monthly	Estimate

Footnotes:

1. As determined by the 96-hour suspended particulate phase (SPP) toxicity test. See 40 CFR 435, Subpart A, Appendix 2.
2. At the end-of-well, a sample must be collected for toxicity testing where no mineral oil is used. This sample can also serve as the monthly monitoring sample
3. As determined by the Static Sheen Test. See 40 CFR Part 435, Subpart A, Appendix 1.
4. See Section 2.2.6.3.
5. Dry weight in the stock barite. Analysis shall be conducted using EPA Methods 245.5 or 7471b for mercury and 200.7 for cadmium. The permittee shall analyze a representative sample of stock barite once prior to drilling each well and submit the results with the DMR for the month in which drilling operations commence for the respective well. If the permittee uses the same supply of stock barite to drill subsequent wells, the permittee may submit the same analysis for those subsequent wells (see Section 2.2.6.6).
6. PAH mass ratio = [mass (g) of PAH (as phenanthrene)] ÷ [mass (g) of stock base fluid] as determined by EPA method 1654, Revision A, entitled "PAH Content of Oil by HPLC/UV," December 1992 (see Section 2.2.3.2).
7. Base fluid sediment toxicity ratio = [10-day LC_{50} of C_{16}-C_{18} internal olefin, C_{12}-C_{14} ester or C_8 ester] ÷ [10-day LC_{50} of stock base fluid] as determined by ASTM E 1367-99 method: "Standard Guide for Conducting 10-day Static Sediment Toxicity Tests with Marine and Estuarine Amphipods,"1992, after preparing the sediment according to the method specified at 40 CFR 435, Subpart A, Appendix 3 (See Section 2.2.4.6). Results of up to 3 tests may be averaged to determine compliance, using 2 samples from the same lot of stock fluids. Equivalent aliquots of one homogenized sample must be split by laboratory (parts 1A and 1B) and tested separately if averaging is used. Permittees may show compliance based on test results from part 1A or from the rounded arithmetic average of the test results from part 1A and 1B. Permittees may also test the second sample for compliance. Where the second sample is analyzed, operators will determine compliance using the arithmetic average of the results from all 3 tests. Permittees shall report the appropriate number on the DMR. With the DMR, the permittee must submit documentation showing how the number was calculated and all applicable test reports (see Section 2.2.3.6).
8. Biodegradation rate ratio = [cumulative gas production (ml) of C_{16}-C_{18} internal olefin, C_{12}-C_{14} ester or C_8 ester] ÷ [cumulative gas production (ml) of stock base fluid], both at 275 days as determined by ISO 11734:1995 method: "Water quality - Evaluation of the 'ultimate' anaerobic biodegradability of organic compounds in digested sludge--Method by measurement of the biogas production (1995 edition)" as modified for the marine environment (see Section 2.2.3.1). Results of up to 3 tests may be averaged to determine compliance, using 2 samples from the same lot of stock fluids. Equivalent aliquots of one homogenized sample must be split by laboratory (parts 1A and 1B) and tested separately if averaging is used. Permittees may show compliance based on test results from part 1A or from the rounded arithmetic average of the test results from part 1A and 1B. Permittees may also test the second sample for compliance. Where the second sample is analyzed, operators will determine compliance using the arithmetic average of the results from all 3 tests. Permittees shall report the appropriate number on the DMR. With the DMR, the permittee must submit documentation showing how the number was calculated and all applicable test reports
9. Drilling fluid sediment toxicity ratio = [4-day LC_{50} of C_{16}-C_{18} internal olefin] ÷ [4-day LC_{50} of drilling fluid removed from drill cuttings at the solids control equipment] as determined by ASTM E 1367-99 method: "Standard Guide for Conducting Static Sediment Toxicity Tests with Marine and Estuarine Amphipods" (1999), after preparing the sediment according to the method specified in Appendix B of this permit. Results of up to 3 tests may be averaged to determine compliance, using 2 grab samples collected no more than 15 minutes apart. Equivalent aliquots of the first, homogenized sample must be split by the laboratory (parts 1A and 1B) and tested separately if averaging is used. Permittees may show compliance based on test results from part 1A or from the rounded arithmetic average of the test results from parts 1A and 1B. Permittees may also test the second sample for compliance with this limit. Where the second sample is analyzed, operators will determine compliance using the arithmetic average of the results from all 3 tests. Permittees shall report the appropriate number on the DMR. With the DMR, the permittee must submit documentation showing how the number was calculated and all applicable test reports.
10. As determined before drilling fluids are shipped offshore by the GC/MS compliance assurance method (see Section 2.2.3.3), and as determined prior to discharge by the Reverse Phase Extraction (RPE) method (see Section 2.2.3.3) applied to drilling fluid removed from drill cuttings. If the operator wishes to confirm the results of the RPE method, the operator may use the GC/MS compliance assurance method (see Section 2.2.3.4). Results from the GC/MS compliance assurance method shall supersede the results of the RPE method.
11. This limitation is applicable only when the NAF base fluid meets the stock limitations defined in this table.
12. As determined by the American Petroleum Institute (API) retort method (see Section 2.2.3.5).
13. Monitoring shall be performed at least once per day when generating new cuttings. Operators conducting fast drilling (*i.e.*, greater than 500 linear feet advancement of the drill bit per day using non-aqueous fluids) shall collect and analyze one set of drill cuttings samples per 500 linear feet drilled, with a maximum of three sets per day. Operators shall collect a single discrete drill cuttings sample for each point of discharge to the ocean. The weighted average of the results of all discharge points for each sampling interval will be used to determine compliance.
14. Averaged over all well sections.
15. Exemptions to the zero discharge of non-aqueous drilling fluids which adhere to drill cuttings based on technical limitations may be granted per 40 CFR Part 435, Appendix A of Subpart D Coastal Subcategory.

2.2.3 Specific Test Requirements

2.2.3.1 Biodegradation Rate.

The approved test method for permit compliance is identified as: modified ISO 11734:1995 method: "Water quality - Evaluation of the 'ultimate' anaerobic biodegradability of organic compounds in digested sludge - Method by measurement of the biogas production (1995 edition)" (Available from the American National Standards Institute, 11 West 42nd Street, 13th Floor, New York, NY 10036) supplemented with modifications in Appendix 4 of 40 CFR 435, Subpart A and detailed in Appendix E. Compliance with the biodegradation limit will be determined using the following ratio:

$$\frac{\text{\% Theoretical gas production of reference fluid}}{\text{\% Theoretical gas production of NAF}} \leq 1.0$$

Where: NAF = stock base fluid being tested for compliance

Reference Fluid = C16-C18 internal olefin or C12-C14 or C8 ester reference fluid

2.2.3.2 Polynuclear Aromatic Hydrocarbons

For analysis of TAH and TAqH all analytical requirements cited in the Alaska Standards, 18 ACC 70.020(b) are applicable.

2.2.3.3 Formation Oil Contaminated Drilling Fluids

The approved test method for permit compliance is identified as GC/MS. The GC/MS method reports results for the GC/MS test as percent crude contamination when calibrated for a specific crude oil. In order to define an applicable pass/fail limit to cover a variety of crude oils, the same crude oil used in calibration of the RPE test shall be used to calibrate the GC/MS test results to a standardized ratio of the target aromatic ION Scan 105. Based on the performance of a range of crude oils against standardized ratio, a value will be selected as a pass/fail standard which will represent detection of crude oil.

2.2.3.4 Formation Oil Contamination of Discharged Drilling Fluids Retained on Cuttings

The approved test method for permit compliance is identified as: Reverse Phase Extraction (RPE) as described in Appendix 6 of 40 CFR Part 435, Subpart A. If the operator wishes to confirm the results of the RPE method (Appendix 6 of 40 CFR Part 435, Subpart A), the operator may use the GC/MS compliance assurance method (Appendix 5 of 40 CFR Part 435, Subpart A). Results from the GC/MS compliance

assurance method shall supercede the results of the RPE method (Appendix 6 of 40 CFR Part 435, Subpart A).

2.2.3.5 Retention of Non-aqueous Based Drilling Fluids on Cuttings

The approved test method for permit compliance is identified as: the Retort Test Method described in Appendix 7 of 40 CFR Part 435, Subpart A. The required sampling, handling, and documentation procedures are listed in Addendum A of 40 CFR Part 435, Subpart A, Appendix 7.

2.2.3.6 Stock Base Fluid Sediment Toxicity.

The approved test method for permit compliance is identified as: ASTM E1367–99 method Standard Guide for Conducting Static Sediment Toxicity Tests with Marine and Estuarine Amphipods (Available from the American Society for Testing and Materials, 100 Barr Harbor Drive, West Conshohocken, PA, 19428) with Leptocheirus plumulosus as the test organism and sediment preparation procedures specified in Appendix 3 of 40 CFR Part 435, Subpart A and the method found in Appendix B of this permit.

2.2.4 Number of Wells

The permittee is limited to drilling discharges from no more than five wells at a single site. Requests to discharge from more than five wells per site will be considered by DEC on a case-by-case basis. The permittee may only discharge from more than five wells upon approval by DEC. The permittee must submit the following information to DEC for consideration for approval of the discharge from additional wells:

2.2.4.1 Number of additional wells;

2.2.4.2 Technical analysis of additional impacts to the receiving waters;

2.2.4.3 Drilling fluid category and group for each well; and

2.2.4.4 Well information for each additional well, including well name, number latitude, longitude, beginning drill date, and hole diameter.

2.2.5 Mineral Oil Pills

2.2.5.1 The discharge of residual amounts of mineral oil pills (mineral oil plus additives) is authorized by this general permit provided that the mineral oil pill and at least a 50 barrels (bbl) buffer of drilling fluid on either side of the pill are removed from the circulating drilling fluid system and not discharged to waters of the US. If more than one pill is applied to a single well, the previous pill and buffer must be removed prior to application of a subsequent pill.

2.2.5.2 Residual mineral oil concentration in the discharged fluid must not exceed 2 percent volume/volume (Appendix 7 to Subpart A of 40 CFR Part 435 (API Rec Prac 13B-2). The permittee must report the following information within 60 days of the discharge if drilling fluid containing residual mineral oil pill (after pill and buffer removal) is discharged:

2.2.5.2.1 Dates of pill application, recovery, and discharge;

2.2.5.2.2 Results of the Drilling Fluids Toxicity Test on samples of the mud before each pill is added and after removal of each pill and buffer (taken when residual mineral oil pill concentration is expected to be greatest);

2.2.5.2.3 Name of spotting compound and mineral oil product used;

2.2.5.2.4 Volumes of spotting compound, mineral oil, water, and barite in the pill;

2.2.5.2.5 Total volume of fluid circulating prior to pill application, volume of pill formulated, and volume of pill circulated;

2.2.5.2.6 Volume of pill recovered, volume of mud buffer recovered, and volume of fluid circulating after pill and buffer recovery;

2.2.5.2.7 Percent recovery of the pill (include calculations);

2.2.5.2.8 Estimated concentrations of residual spotting compound and mineral oil in the sample of mud discharged, as determined from amounts added and total mud volume circulating prior to pill application;

2.2.5.2.9 Measured oil content of the mud samples, as determined by the API retort method; and

2.2.5.2.10 An itemization of other drilling fluid components and specialty additives contained in the discharged fluid concentrations reported in gal/bbl or lbs/bbl.

2.2.6 Monitoring Requirements

2.2.6.1 Chemical Inventory. For each mud system discharged, the permittee must maintain a precise chemical inventory of all constituents added downhole, including all drilling fluid additives used to meet specific drilling requirements. The permittee must maintain these records for <u>each</u> mud system for a period of five years, and must make these records available to DEC upon request. This information is reported as part of the End of Well report described in Section 2.2.6.2.

2.2.6.2 End of Well Reports. The permittee is required to submit an EOW report within 90 days of well completion. The permittee shall report the following for each drilling fluid system in the EOW report:

2.2.6.2.1 Well name, number, latitude, longitude, beginning drill date, and hole diameter at depth, and well completion date;

2.2.6.2.2 A precise chemical inventory of all constituents added downhole, including all drilling fluid additives used to meet specific drilling requirements;

2.2.6.2.3 The base drilling fluid type;

2.2.6.2.4 The name and total amount of each constituent in the discharged drilling fluid;

2.2.6.2.5 The total volumes of drilling fluid create and added downhole;

2.2.6.2.6 The maximum concentration of each constituent in the drilling fluid;

2.2.6.2.7 The total volumes of drilling fluid discharged to surface waters; and

2.2.6.2.8 The estimated amount of each constituent in the drilling fluid discharged to surface waters;

2.2.6.2.9 The use of surfactants, dispersants, and detergents per 2.1.6;

2.2.6.2.10 The name and total amount of each chemical additive per 2.2.6.1, the results of the diesel oil analysis per 2.2.6.3 and metals analysis per 2.2.6.5.1.

2.2.6.3 Diesel Oil

2.2.6.3.1 Compliance with the limitation on diesel oil must be demonstrated by GC analysis of drilling fluids collected from the mud used at the greatest well depth ("end-of-well" sample) and of any drilling fluids or drill cuttings which fail the daily Static Sheen Test. In all cases, the determination of the presence or absence of diesel oil must be based on a comparison of the fingerprint of the sample and of the diesel oil in storage at the facility. The method for analysis must be EPA SW846 Method 8015C (2007). Gas chromatography/mass spectrometry (GC/MS) may be used if an instance should arise where the permittee and DEC determine that greater resolution of the drilling fluid "fingerprint" is needed for a particular drilling fluid sample. If the permittee elects to confirm the results of Method 8015C, the GC/MS methods described in EPA 821-R-92-008 may be used.

2.2.6.3.2 The results and raw data, including the spectra, from the GC analysis must be provided to DEC by written report (1) within 30 days of a positive result with the Static Sheen Test when a discharge has occurred, or (2) for the end-of-well analysis, within 90 days of well completion, per 2.2.6.2.

2.2.6.4 Static Sheen Test

2.2.6.4.1 The permittee must perform the Static Sheen Test on separate samples of drilling fluids and drill cuttings, as required in 40 CFR Part 435, Subpart A, Appendix 1. Samples must be collected on each day of discharge and prior to bulk discharges.

2.2.6.4.2 The test must be conducted in accordance with "Approved Methodology: Laboratory Sheen Tests for the Offshore Subcategory, Oil and Gas Extraction Industry," 40 CFR Part 435, Subpart A, Appendix 1. For discharge below ice or during periods of unstable or broken ice, water temperature for the Static Sheen Test must approximate surface water temperatures at ice breakup.

2.2.6.4.3 Whenever fluids or cuttings fail the Static Sheen Test, and a discharge has occurred in the past 24 hours, the permittee is required to analyze an undiluted sample of the material which failed the test to determine the presence or absence of diesel oil. The determination and reporting results must be performed according to Section 2.2.6.3.

2.2.6.5 Metals Analysis

2.2.6.5.1 The permittee must analyze each discharged fluid system for the following metals: barium, cadmium, chromium, copper, mercury, zinc, and lead. Analyses for total recoverable concentrations must be conducted and reported for each metal utilizing the methods specified in 40 CFR Part 136. The results must be reported in "mg/kg of whole mud (dry weight)" and the moisture content (percent by weight) of the original drilling fluid sample must be included in the EOW report, see 2.2.6.2.

2.2.6.5.2 Samples must be collected when the residual mineral oil concentration is at its maximum value. If no mineral oil is used, the analysis must be done on a drilling fluid sample from the mud system used at the greatest well depth. All samples must be collected prior to any pre-dilution.

2.2.6.6 Mercury and Cadmium Content in Barite

2.2.6.6.1 The permittee must analyze a representative sample of stock barite once prior to drilling each well and submit the results for total mercury and total cadmium in the DMR for the month in which drilling of the well commenced. Analyses must be conducted using EPA Methods 245.5 or 7471b for mercury and 200.7 for cadmium and results expressed as mg/kg (dry weight) of barite.

2.2.6.6.2 If more than one well is drilled at a site, new analyses are not required for subsequent wells if no new supplies of barite have been received since the previous analysis. In this case, the DMR should state that no new barite was received since the last reported analysis. A permittee may provide certification, as documented by the supplier(s), that the barite meets the above limits. The concentration of mercury and cadmium in stock barite must be reported on the DMR as documented by the supplier.

2.2.7 Environmental Monitoring Requirements

2.2.7.1 All Mobile Exploratory Facilities: Monitoring of the fate and effects of drilling fluids and/or cuttings discharges are required for all facilities near the area of discharge.

2.2.7.2 Environmental Monitoring Study. Operators of all mobile exploratory facilities discharging drilling fluids and/or drill cuttings must submit a plan of study for environmental monitoring to DEC for review and comment with, or prior to, submission of an NOI.

2.2.7.3 Objectives. The objectives of the environmental monitoring must be to:

2.2.7.3.1 Monitor for discharge related impacts,

2.2.7.3.2 Determine statistically significant changes in sediment pollution concentrations and potential for sediment toxicity with time and distance from the discharge,

2.2.7.3.3 Monitor for discharge related impacts to the benthic community,

2.2.7.3.4 Assess whether any impacts warrant an adjustment of the monitoring program, and

2.2.7.3.5 Provide information for permit reissuance.

2.2.7.4 Plan of Study. The monitoring must include, but not be limited to, relevant hydrographic, sediment hydrocarbon, and heavy metal data from surveys conducted before and during drilling fluid disposal and up to at least one year after drilling operations cease. The monitoring plan must address:

2.2.7.4.1 The monitoring objectives,

2.2.7.4.2 Appropriate null and alternative test hypotheses,

2.2.7.4.3 A statistically valid sampling design,

2.2.7.4.4 All monitoring procedures and methods,

2.2.7.4.5 A quality assurance/quality (QA/QC) control program,

2.2.7.4.6 A detailed discussion of how data will be used to meet, test, and evaluate the monitoring objectives, and

2.2.7.4.7 A summary of the results of previous environmental monitoring as they apply to the proposed program plan.

2.2.7.5 Reporting Requirements

2.2.7.5.1 The permittee must analyze the data and submit a draft report within 180 days following the completion of sample collection. The report must address the environmental monitoring objectives by using appropriate descriptive and analytical methods to test for and to describe any impacts of the effluent on sediment pollutant concentrations, sediment quality, water quality, and the benthic community. The report must include all relevant QA/QC information, including but not limited to instrumentation, laboratory procedures, detection limits/precision requirements of the applied analyses, and sample collection methodology.

2.2.7.5.2 DEC will review the draft report in accordance with the environmental monitoring objectives and evaluate it for compliance with the requirements of the permit. If revisions to the report are required, the permittee must complete them and submit the final report to DEC within two months of DEC's request. The permittee will be required to correct, repeat, or expand environmental monitoring programs which have not fulfilled the requirements of the permit.

2.2.7.6 Modification of Monitoring Program. The monitoring program may be modified if DEC determines that the modification is appropriate. The modified program may include changes in sampling stations, sampling times, and parameters.

2.2.7.7 Exemption. DEC may grant a written exemption to this requirement if the permittee can satisfactorily demonstrate that information on the fate and effects of the discharge is available or the discharge will not have significant impacts on the receiving environment in the area of discharge. An exemption to post-drilling monitoring will be granted if no impact was indicated during drilling. A site specific exemption request may be submitted to DEC in writing for Department approval.

2.2.8 Drilling Fluid Plan Requirements

2.2.8.1 The applicant must develop and submit a DFP for Department review and comment with, or prior to, submission of an NOI. The applicant must implement the written procedure in the DFP for the formulation and control of drilling fluid/chemical additive systems for each well. The DFP must specify the drilling fluid/chemical additive systems to be used.

The plan must be implemented during drilling operations and a copy of the plan must be available on-site at the exploratory facility at all times.

2.2.8.2 The applicant must submit a copy of the completed drilling fluid plan to DEC with the NOI.

2.2.8.3 At a minimum, the drilling fluid plan must include the following information:

2.2.8.3.1 Types of drilling fluids proposed for discharge, the well name, well number, location, and drilling fluid types as basic plan identification for each well drilled.

2.2.8.3.2 Specific to each well and drilling fluid type, provide a list including commercial product names, descriptions of the products, and the maximum proposed discharge concentrations for each product and chemical additive. Concentrations must be commonly stated in appropriate terms (e.g., lb/bbl, gal/bbl, % (wt), or % v/v (% volume oil per volume drilling fluid)). Each drilling fluid or additive system must be clearly labeled with respect to drilling fluid type (e.g., KCl/polymer drilling fluid, freshwater lignosulfonate drilling fluid). Components of the basic drilling fluid must be listed separately from specialty or contingency chemical additives which may be used.

2.2.8.3.3 A record of the operator's determination of how discharge of drilling fluids and drill cuttings is expected to comply with the 30,000 ppm SPP toxicity limitation. Operator's determination must be based upon but not limited to, the following criteria:

- Estimate of worst-case cumulative discharge toxicity based on additive toxicity estimations or commercially calculated discharge toxicity estimations;
- Estimations of discharge toxicity based on the use of mineral oil pills and subsequent discharge of residual mineral oil concentrations must be estimated separately from the proposed drilling fluid or additive system; and
- Description of how overall toxicity is minimized, where possible.

2.2.8.3.4 A clearly stated procedure for determining whether or not a chemical additive not originally planned for or included in toxicity estimations may be used and discharged.

2.2.8.3.5 An outline of the drilling fluid planning process which must be consistent with other general permit requirements. Names and titles of personnel responsible for the drilling fluid planning process must be included in the drilling fluid plan.

2.3 Requirements for Deck Drainage (Discharge 002)

2.3.1 Effluent Limitations and Monitoring Requirements. In addition to the restrictions set out in Section 2.1, the permittee must comply with the following effluent limitations and monitoring requirements.

Table 3: Effluent Limitations and Monitoring Requirements Deck Drainage (Discharge 002)

Parameter	Units	Effluent Limitations	Monitoring Requirements	
			Sample Frequency[1]	Sample Type
Free Oil	---	No Discharge	Daily	Visual[2]
Free Oil [2]	---	No Discharge	Once/Discharge Event [3]	Grab
Whole Effluent Toxicity (WET)[4, 5]	TU_c	Report	Once during first year of coverage	See Section 2.7
Flow	mgd	Report	Monthly	Estimated

Footnotes:

1. When discharging.
2. If discharge occurs during broken or unstable ice conditions or during stable ice conditions, the Static Sheet Test must be used (see 40 CRF Part 435 Subpart A, Appendix 1) and a grab sample is required.
3. The monitoring frequency is reduced to monthly if the permittee has complied with this requirement for three consecutive months.
4. Contaminated deck drainage must be processed through an oil-water separator prior to discharge (See Section 2.1.7) and samples for that portion of the deck drainage collected from the separator effluent must be sampled for WET testing.
5. Sample must be collected during a significant rainfall or snow melt. If discharge of deck drainage is initiated after the first year of the permit, sampling must occur during the year following the initiation of separate deck drainage discharge.

2.3.2 The permittee must ensure that deck drainage contaminated with oil and grease is processed through an oil-water separator prior to discharge. Once per discharge event, the permittee must sample deck drainage discharges that are processed through the oil-water separator and test for sheen using the Static Sheet Test in 40 CFR Part 435, subpart A.

2.4 Requirements for Domestic Wastewater (Discharge 003)

2.4.1 Effluent Limitations and Monitoring Requirements. In addition to the restrictions set out in Section 2.1, the permittee must comply with the following effluent limitations and monitoring requirements.

Table 4: Effluent Limitations and Monitoring Requirements for Domestic Wastewater (Discharge 003)

Discharge	Effluent Parameter	Effluent Limitations		Monitoring Requirements	
		Avg. Monthly Limit	Max. Daily Limit	Sample Frequency	Sample Type
Domestic Wastewater, All Discharges[1]	Flow Rate (mgd)	Report		1/Month	Estimate
	TRC	-	1.0 mg/L Minimum [2]	1/Month	Grab
	TRC	-	1.0 mg/L[3]	1/Month	Grab
	TRC	-	0.0075 mg/L[4]	1/Month	Grab
	Floating Solids	No Discharge		1/Day	Observation[5]
M10 MSD and MSD/BTUs	BOD	30 mg/l	60 mg/l	1/Month	Grab
	TSS	51 mg/l	67 mg/l	1/Month	Grab
M9IM MSD and MSD/BTUs	BOD	30 mg/l	60 mg/l	1/Month	Grab
	TSS	51 mg/l	67 mg/l	1/Month	Grab
M10 BTUs	BOD	30 mg/l	60 mg/l	1/Month	Grab
	TSS [6]	30 mg/l	60 mg/l	1/Month	Grab
M9IM BTUs	BOD	48 mg/l	90 mg/l	1/Month	Grab
	TSS [6]	56 mg/l	108 mg/l	1/Month	Grab

Footnotes:

1. In cases where domestic wastewater (black water) and graywater are mixed prior to discharge, and sampling of the domestic wastewater stream is infeasible, the discharge may be sampled after mixing. In such cases, the most stringent discharge limits for both discharges shall apply to the mixed stream.
2. Total residual chlorine is a surrogate parameter for fecal coliform and enterococci. For M10 facilities, maintain as close to the minimum limit concentration of 1.0 mg/L as practicable and measure immediately after chlorination. For all other facilities, monitor and report.
3. The 1.0 mg/L maximum daily limit is measured immediately prior to discharge and applies to facilities authorized a 100-meter mixing zone by DEC.
4. The 0.0075 mg/L limit is measured immediately prior to discharge and applies to permittees not authorized a mixing zone by DEC. The analytical detection limit for this parameter is 0.1 mg/L and will be used as the compliance level for this parameter.
5. The permittee must monitor by observing the surface of the receiving water in the vicinity of the outfall(s) during daylight at the time of maximum estimated discharge and during conditions when observation on the surface of the receiving water is possible in the vicinity of the discharge. For domestic wastewater, observations must follow either the morning or midday meal. Observations must be recorded in daily operating logs and made available upon request by DEC.
6. The TSS limit for BTUs is a net value. For those facilities that use filtered seawater for flushing and treat with BTUs, the TSS of the effluent may be reported as the net value by subtracting the TSS value of the intake water from the TSS value of the effluent. Report the TSS value of the intake water on the comment section of the DMR. Samples collected to determine the TSS value of the intake water must be taken on the same day, and during the same time period that the effluent sample is taken. Intake water samples must be taken at the point where the water enters the facility prior to mixing with other flows. Influent samples must be taken with the same frequency that effluent samples are taken.

2.5 Requirements for Graywater (Discharge 004)

2.5.1 Effluent Limitations and Monitoring Requirements. In addition to the restrictions set out in Section 2.1, the permittee must comply with the following effluent limitations and monitoring requirements.

Table 5: Effluent Limitations and Monitoring Requirements for Graywater (Discharge 004)

Effluent Characteristic	Units	Sample Location	Sampling Frequency	Sample Type
Total Flow	Gallons per Day (gpd) (permitted)	Effluent	Daily	Estimate or Measured
Biochemical Oxygen Demand (BOD_5)	mg/L	Influent and Effluent[1]	Monthly	Grab or Composite [2]
Total Suspended Solids (TSS)	mg/L	Influent and Effluent[1]	Monthly	Grab or Composite [2]
Floating Solids	Visual	Effluent	Daily	Observation
Foam	Visual	Effluent	Daily	Observation
Garbage	Visual	Effluent	Daily	Observation
Oily Sheen	Visual	Effluent	Daily	Observation

Footnotes:

1. Influent and effluent samples must be taken over approximately the same time period. Results are used to confirm that graywater meets primary treatment standards prior to discharge. See 18 AAC 72.990(50)(B) for primary treatment standards.
2. Composite samples must consist of at least eight grab samples collected at equally spaced intervals and proportionate to flow so that composite samples reflect influent/effluent quality during the compositing period.

2.5.2 Flow. The permit includes flow monitoring requirements to measure or estimate the effluent discharge flow for each discharge. DEC will use the flow data to determine the amount of contaminants entering the environment and inform future Department decisions during the permit reissuance.

2.5.3 BOD_5. The permit requires monthly influent and effluent monitoring and must be provided to the Department upon request.

2.5.4 TSS. The permit requires monthly influent and effluent monitoring and must be provided to the Department upon request.

2.5.5 Floating Solids, Foam, Garbage, and Oily Sheen. The permit prohibits floating solids, foam, garbage, and oily sheen and requires a visual observation of the receiving water surface at a minimum frequency of once per day. Monitoring of the effluent for floating solids, foam, garbage, and oily sheen is to determine compliance with narrative effluent limits. Observations must be recorded in daily operating logs and made available upon request by DEC.

2.6 Requirements for Miscellaneous Discharges (Discharges 005-013)

2.6.1 Effluent Limitations and Monitoring Requirements. In addition to the restrictions set out in Sections 2.1, the discharge of desalination unit wastes (005); blowout preventer fluid (006); boiler blowdown (007): fire control system test water (008); non-contact cooling water (009); uncontaminated ballast water (010); bilge water (011); excess cement slurry (012); and mud, cuttings, and cement at the seafloor (013) must comply with the following effluent limitations and monitoring requirements:

Table 6: Effluent Limitations and Monitoring Requirements for Miscellaneous Discharges 005-013

Parameter	Effluent Limitations		Monitoring Requirements	
	Average Monthly Limit	Maximum Daily Limit	Sample Frequency [1]	Sample Type
Flow (mgd)	Report		Monthly	Estimate
Free Oil [2]	No discharge	No discharge	Once/Week	Visual
Free Oil [3]	No discharge	No discharge	Once/Discharge Event	Grab
Chemical Additives	See Sections 2.6.3		Monthly	Calculation
WET [4]	See Section 2.6.4		Once/Quarter [5]	Grab

Footnotes:

1. When Discharging.
2. Miscellaneous discharge is limited to those times that a visible sheen observation is possible unless the operator can obtain a grab sample to use the Static Sheen Test. For discharges during stable ice, below ice, to unstable ice or broken ice conditions, the Static Sheen Test must be used with a water temperature that approximates surface water temperatures after breakup. The number of days a sheen is observed must be recorded. Observations must be recorded in daily operating logs and made available upon request by DEC.
3. Applicable to any discharge of Contaminated ballast water (010) and Bilge Water (011). Contaminated ballast water (010) and Bilge water (011) must be treated prior to discharge and must be sampled by static sheen methods at least once per discharge event (see Section 2.6.2.2 and 2.6.2.3).
4. Applicable to all discharges greater than 10,000 gpd to which chemical additives have been added, except Discharges 012 (excess cement slurry) and 013 (mud, cuttings, and cement at the seafloor).
5. The required monitoring frequency for WET may be reduced to once per six months if the permittee has not exceeded the triggers for a period of one year (4 consecutive quarters). The permittee must submit a request for Department approval. If the permittee subsequently exceeds the triggers, the increased monitoring provisions of Section 2.7.8 shall apply. Permittees meeting the requirements for reduced monitoring must report the monitoring frequency on the DMR.

2.6.2 Discharge Specific Limitations

2.6.2.1 Desalination Unit Waste Water (Discharge 005). In addition to the limitations and monitoring requirements in Section 2.6.1, the permittee must maintain a chemical inventory with the quantities and rates of chemicals and biocides that are added to desalination unit waste water. Each annual inventory must be assembled for the calendar year and submitted to the DEC Compliance and Enforcement Program by April 1 for the previous calendar year.

2.6.2.2 Contaminated Ballast Water (Discharge 009). The permittee shall process all contaminated ballast water through an oil-water separator prior to discharge

2.6.2.3 Bilge Water (Discharge 011). The permittee shall process all bilge water through an oil-water separator prior to discharge.

2.6.3 Chemical Additives. The concentration of treatment chemicals in discharged seawater or freshwater shall not exceed the most stringent of the following three constraints. Compliance with these limitations shall be calculated based on the amount of treatment chemical added to the volume of water discharged.

2.6.3.1 The maximum concentrations and any other conditions specified in the EPA product registration labeling if the chemical is an EPA registered product.

2.6.3.2 The maximum manufacturers recommended concentration.

2.6.3.3 The maximum concentration of 500 mg/L

2.6.4 WET Monitoring Requirements. WET testing shall be accomplished in accordance with the monitoring requirements in Sections 2.6.4 and 2.8 of this permit and the WET trigger values (expressed as Chronic Toxic Units (TU_c)) shown in Tables 7 and 8. This requirement applies to any individual, or commingled, miscellaneous discharges greater than 10,000 gallons per day.

Table 7: WET Trigger Levels for Surface Discharges

Discharge Rate (permitted)	Critical Dilution	Trigger Values (TU_c)
10,000 – 17,000	0.24 %	417
17,001 – 22,000	0.27 %	370
22,001 – 27,000	0.29 %	345
27,001 – 55,000	0.36 %	278
55,001 – 150,000	0.46 %	217
Greater than 150,000	0.62 %	161

Table 8: WET Trigger Levels for Submerged Pipe Discharges

Discharge Rate (permitted)	Critical Dilution	Trigger Values in TUc
10,000 – 17,000	0.33%	303
17,001 – 22,000	0.36%	278
22,001 – 27,000	0.37%	270
27,001 – 55,000	0.49%	204
55,001 – 150,000	0.62%	161
Greater than 150,000	0.99%	101

2.7 Requirements for Test Fluid Discharges (019)

2.7.1 Effluent Limitations and Monitoring Requirements. In addition to the restrictions set out in Section 2.1, the permittee must comply with the following effluent limitations and monitoring requirements

Table 9: Effluent Limitations and Monitoring Requirements for Test Fluids (019)

Parameter	Effluent Limitations		Monitoring Requirements	
	Average Monthly Limit	Maximum Daily Limit	Sample Frequency	Average Monthly Limit
Flow (mgd)	Report		Once/Day	Estimate
Oil and Grease	29 mg/L	42 mg/L	Once/Discharge	Grab [1]
Free Oil [2]	No discharge		Once/Discharge	Grab [1]
Oil-based Fluids	No discharge		-	-
pH	6.5 – 8.5		Once/Discharge	Grab
Chemical Inventory [3]	See Section 2.2.6.1		Monthly	Calculation
WET [4]	See Section 2.6.4 and 2.8 [5]		Once/Quarter	Grab

Footnotes:

1. Samples for free oil and oil and grease must be collected after the final step of treatment.
2. Monitoring for compliance with the free oil prohibition shall be accomplished using the Static Sheen Test method. The number of days sheen is observed must be reported.
3. The permittee must maintain an inventory of the type and quantity of chemicals (other than fresh or seawater) added to test fluids.
4. Conduct WET testing per Sections 2.6.4 and 2.8. except testing must also be done for Test Fluid discharges equal to or less than 10,000 gpd.
5. WET triggers and TRE/TRI requirements only apply to discharge of Test Fluids greater than 10,000 gpd. WET testing for discharges equal to or less than 10,000 gpd are reported for information purposes only.

2.8 WET Testing Requirements

This requirement applies to Deck Drainage (002), Desalination Units (005), Blowout Preventer Fluid (006), Boiler Blowdown (007), Fire Control System Test Water (008), Non-contact Cooling Water (009), Uncontaminated Ballast Water (010), Bilge Water (011), and Test Fluids (019).

2.8.1 The permittee must conduct tests on grab effluent samples with one vertebrate and two invertebrate species, as follows.

2.8.1.1 Vertebrate (survival and growth): *Atherinops affinis* (topsmelt). In the event that topsmelt is not available, *Menidia beryllina* (inland silverside) may be used as a substitute. The permittee shall document the substitute species in the next DMR.

2.8.1.2 Invertebrate: For larval development tests, the permittee must conduct tests with a bivalve species, *Crassostrea gigas*, (Pacific Oyster) or Mytilus *sp*. (mussel). For fertilization tests, the permittee must use an echinoderm, *Strongylocentrotus purpuratus* (purple sea urchin) *or Dendraster excentricus* (sand dollar). Due to seasonal variability, testing may be performed during reliable spawning periods.

2.8.2 The permittee must monitor for toxicity once per quarter during discharge activities. If the effluent complies with the toxicity triggers for four consecutive quarters, the permit allows a reduction in toxicity monitoring to once every six months during discharge activities upon written Department approval.

2.8.3 Each year, the permittee must rescreen with the three species listed in 2.7.1.1 and 2.7.1.2 and continue to monitor with the most sensitive species. Rescreening must consist of one test conducted at a different time of year from the previous year's test. After screening is completed, monitoring shall be continued at the frequency required in Table 6 or 2.7.2 of this permit.

2.8.4 The presence of chronic toxicity must be estimated as specified in *USEPA Short-Term Methods for Estimating the Chronic Toxicity of Effluents and Receiving Waters to Marine and Estuarine Organisms*, Third Edition (EPA-821-R-02-014). For the bivalve species, chronic toxicity must be estimated as specified in *Short-Term Methods for Estimating the Chronic Toxicity of Effluents and Receiving Water to West Coast Marine and Estuarine Organisms* (EPA/600/R-95/136).

2.8.5 Results must be reported in TUc, where TUc = $100/IC_{25}$. The reported IC_{25} must be the lowest IC_{25} calculated for the applicable survival, growth or fertilization endpoints.

2.8.6 A series of at least five dilutions and a control must be tested. The series must include the critical dilution and two dilutions both above and two below the critical dilution. Test series should also be designed to bracket toxicity end points from previous tests to provide meaningful toxicity information for review during the next permit reissuance.

2.8.7 In addition to those quality assurance measures specified in the methodology, the following quality assurance procedures must be followed:

2.8.7.1 If organisms are not cultured by the testing laboratory, concurrent testing with reference toxicants must be conducted, unless the test organism supplier provides control chart data from at least the previous five months of reference toxicant testing. Where organisms are cultured by the testing laboratory, monthly reference toxicant testing is sufficient.

2.8.7.2 If either of the reference toxicant tests or the effluent tests does not meet all test acceptability criteria as specified in the test methods manual, then the permittee must re-sample and re-test as soon as possible.

2.8.7.3 Control and dilution water should be receiving water, or salinity adjusted lab water. If the dilution water used is different from the culture water, a second control, using culture water must also be used.

2.8.8 Accelerated Testing

2.8.8.1 If chronic toxicity is detected above the permit limits or trigger values set forth in Sections 2.6.4, collection and analysis of one additional sample is required within two weeks of receipt of the test results.

2.8.8.2 If chronic toxicity is not detected in the sample required by Sections 2.8.8.1, the permittee must notify DEC in writing of the results within fifteen (15) days of receipt of the results, and must discuss the cause of the exceedance, and the corrective actions that were taken to reduce the toxicity.

2.8.8.3 If chronic toxicity is detected in the sample required by Sections 2.7.8.1 then the permittee must conduct four bi-weekly tests over an eight week period. Accelerated testing must be initiated within fifteen (15) days of receiving the sample results required by Sections 2.7.8.1.

2.8.9 Toxicity Reduction Evaluation (TRE) and Toxicity Identification Evaluation (TIE):

2.8.9.1 If chronic toxicity limits or triggers are exceeded during accelerated testing, the pemittee must initiate a toxicity reduction evaluation (TRE) in accordance with *Generalized Methodology for Conducting Industrial Toxicity Reduction Evaluations* (EPA/600/2-88/070) within two weeks of the receipt of the test results showing an exceedence. At a minimum, the TRE must include:

2.8.9.1.1 Further actions to investigate and identify the cause of toxicity;

2.8.9.1.2 Actions the permittee will take to mitigate the impact of the discharge and to prevent the recurrence of toxicity; and

2.8.9.1.3 A schedule for these actions.

2.8.9.2 If a TRE is initiated prior to completion of the accelerated testing, the accelerated testing schedule may be terminated, or used as necessary in performing the TRE.

2.8.9.3 The permittee may initiate a Toxicity Identification Evaluation (TIE) as part of the TRE process. Any TIE must be performed in accordance with EPA guidance manuals, Toxicity Identification Evaluation; Characterization of Chronically Toxic Effluents, Phase I (EPA/600/6-91/005F), Methods for Aquatic Toxicity Identification Evaluations, Phase II: Toxicity Identification Procedures for Samples Exhibiting Acute and Chronic Toxicity (EPA/600/R-92/080), and Methods for Aquatic Toxicity Identification Evaluations, Phase III: Toxicity Confirmation Procedures for Samples Exhibiting Acute and Chronic Toxicity (EPA-600/R-92/081).

2.8.9.4 If chronic toxicity limits or triggers are not exceeded during accelerated testing, WET testing resumes at the normal frequency.

2.8.10 Reporting

2.8.10.1 The permittee must report the results of toxicity testing on the DMR for the month in which the tests are conducted.

2.8.10.2 The permittee must submit the full report by the end of the month following the month in which the DMR is submitted.

2.8.10.3 The full report must consist of,

2.8.10.3.1 The toxicity test results,

2.8.10.3.2 The dates of sample collection and initiation of each toxicity test,

2.8.10.3.3 The flow rate at the time of sample collection, and

2.8.10.3.4 The results of the effluent sampling for chemical parameters required for the outfalls.

2.8.11 Test results for chronic tests must be reported according to the procedures described in the most recent edition of EPA *Short-term Methods for Estimating the Chronic Toxicity of Effluents and Receiving Waters to Marine and Estuarine Organisms*.

2.9 Reporting of Monitoring Requirements

2.9.1 Monitoring required in Section 2 shall be summarized each month on the DMR to be provided by DEC with the permittee's authorization or a Department-approved equivalent that provides the same information in a similar format.

2.9.2 The submitted DMR must be postmarked, faxed, or submitted electronically via email by the 20th day of the following calendar month to DEC at the address in Appendix A – Standard Conditions, Section 1.1.2.

2.9.3 DMRs are required to be submitted monthly even if no discharge occurs. The permittee shall mark the DMR as "no discharge" during periods of no discharge. The permittee must sign and certify all DMRs, reports, and other submittals in accordance with signatory requirements Appendix A – Standard Conditions in Section 1.12.

2.9.4 With the exception of TRC, the permittee must use EPA-approved methods under 40 CFR Part 136, adopted by reference at 18 AAC 83.010(f), that can achieve a method detection limit (MDL) less than the effluent limit for all effluent monitoring. For a parameter without an effluent limit in this permit, the permittee must use the most sensitive MDL from an EPA-approved analytical test method necessary for compliance monitoring. The permittee must use an EPA-approved test method for TRC monitoring, but in this permit, sample concentrations below the MDL of the EPA-approved method used or 0.1 mg/L, whichever is lower, will be considered the compliance limit.

2.9.5 When reporting for a single sample on the DMR, if a value is less than the MDL, the permittee must report "less than [numeric value of MDL]," and if a value is less than a minimum level (ML), the permittee must report "less than [numeric value of ML]."

2.9.6 When calculating a monthly average, zero (0) may be assigned for a value less than the MDL, and the numeric value of MDL may be assigned for a value between the MDL and the ML. If the average value is less than the MDL, the permittee must report "less than [numeric value of MDL]," and if the average value is less than the ML, the permittee must report "less than [numeric value of ML]." If a value is equal to or greater than the ML, the permittee must report and use the actual value. The resulting average value must be compared to the compliance level, ML, in assessing compliance.

2.10 Mixing Zone and Modification of Effluent Limits

2.10.1 In accordance with State regulations at 18 AAC 70.240, as amended through June 23, 2003, a mixing zone may be authorized as follows:

2.10.1.1 Discharge 001 – Drilling Fluids and Drill Cuttings for Aluminum, Antimony, Arsenic, Barium, Beryllium, Cadmium, Chromium, Copper, Iron, Lead, Mercury, Nickel, Selenium, Silver, Thallium, and Zinc,

2.10.1.2 Discharge 003 – Domestic Wastewater for TRC,

2.10.1.3 Discharge 004 – Graywater for TRC,

2.10.1.4 Discharge 005 – Desalination Unit Wastes for chronic WET,

2.10.1.5 Discharge 006 - Blowout Preventer Fluid for chronic WET,

2.10.1.6 Discharge 007 – Boiler Blowdown for chronic WET,

2.10.1.7 Discharge 008 – Fire Control System Test Water for chronic WET,

2.10.1.8 Discharge 009 – Non-contact Cooling Water for chronic WET,

2.10.1.9 Discharge 010 – Uncontaminated Ballast Water for chronic WET,

2.10.1.10 Discharge 011 - Bilge Water for chronic WET, and

2.10.1.11 Discharge 013 – Muds, Cuttings, and Cement at the Seafloor for Aluminum, Antimony, Arsenic, Barium, Beryllium, Cadmium, Chromium, Copper, Iron, Lead, Mercury, Nickel, Selenium, Silver, Thallium, and Zinc

2.10.1.12 Discharge 019 – Test Fluids for TAH, TAqH, metals, ammonia, dissolved inorganic substances, and WET.

2.10.2 The Department will review the NOI information to ensure the applicant meets the general requirements for coverage under the permit and specifically for site conditions pertaining to mixing zone authorization. If the Department finds sufficient supporting information justifies, the Department will authorize a standard size cylindrically shaped 100 meter radii chronic mixing zone for all applicable discharges and parameters listed in 2.10.1.

2.10.3 The Department will review the NOI information to ensure the applicant meets the general requirements for coverage under the permit and specifically for site conditions pertaining to mixing zone authorization. If the Department finds sufficient supporting information justifies, the Department will authorize a standard size cylindrically shaped 10-meter radii acute mixing zone for discharges 2.10.1.2 and 2.10.1.3, if applicable.

2.10.4 The written authorization from the Department will specify authorized discharges and the parameters for which water quality criteria may be exceeded within an authorized mixing zone.

2.10.4.1 The Department will authorize a mixing zone if the proposed discharges listed in the NOI are consistent with permit conditions.

2.10.4.2 Within an authorized mixing zone, the Department may authorize exceedences of the water quality criteria of 18 AAC 70.020 for Aluminum, Antimony, Arsenic, Barium, Beryllium, Cadmium, Chromium, Copper, Iron, Lead, Mercury, Nickel, Selenium, Silver, Thallium, Zinc, TRC, ammonia, dissolved inorganic substances, TAH, TAqH, and chronic WET per Section 2.9.1. All water quality criteria must be met at the boundary of the mixing zone.

2.10.4.3 If the Department determines that a mixing zone is not appropriate to protect and maintain existing uses of the water body outside of an authorized mixing zone, a permittee may submit additional information to supplement the NOI to provide adequate justification or may submit an individual permit application Form 1, Form 2C, and Form 2M.

2.11 Best Management Practices Plan

The following BMP Plan applies to all permittees:

2.11.1 Through implementation of the BMP plan, the permittee must prevent or minimize the generation and potential for the release of pollutants from the facility to the waters of the US through normal and ancillary activities.

2.11.2 The permittee must develop and implement a BMP Plan which achieves the objectives and the specific requirements listed in Part 2.11.3. Any existing BMP plans may be modified under this section. The BMP Plan shall be ready to implement at the time of submittal of an NOI. The applicant will certify in a cover letter provided with the NOI stating that the BMP Plan is ready to implement when the NOI is submitted.

2.11.3 Objectives: The BMP Plan should be consistent with the general guidance contained in *Guidance Manual for Developing Best Management Practices* (EPA 833-B-93-004, October 1993) or any subsequent revision. The BMP Plan must include, at a minimum, the following items:

2.11.3.1 Documentation in narrative form including any necessary plot plans, drawings or maps, and must be developed in accordance with good engineering practices. The BMP Plan must contain the planning, development and implementation, and evaluation/reevaluation components discussed in *Guidance Manual for Developing Best Management Practices* (USEPA, 1993) or any subsequent revisions to the guidance document.

2.11.3.2 A description of the number and quantity of pollutants and the toxicity of effluent generated, discharged or potentially discharged at the facility that shall be minimized by the permittee to the extent feasible by managing each waste stream in the most appropriate manner..

2.11.3.3 The permittee must establish specific objectives for the control of pollutants by conducting the following evaluations.

2.11.3.3.1 Each facility component or system shall be examined for its waste minimization opportunities and its potential for causing a release of significant amounts of pollutants to waters of the US due to equipment failure, improper operation, and natural phenomena such as rain or snowfall, etc. The examination shall include all normal operations and ancillary activities including loading or unloading operations or spillage or leaks.

2.11.3.3.2 Where experience indicates a reasonable potential for equipment failure, natural condition (e.g., precipitation), or other circumstances to result in significant amounts of pollutants reaching surface waters, the program should include a prediction of the direction, rate of flow and total quantity of pollutants which could be discharged from the facility as a result of each condition or circumstance.

2.11.4 Requirements: The BMP Plan must be consistent with the objectives listed above and the general guidance contained in the publication entitled *Guidance Manual for Developing Best Management Practices* (USEPA, 1993) or any subsequent revisions to the guidance document. The BMP Plan must:

2.11.4.1 Include the following provisions concerning BMP Plan review:

- An annual review by facility engineering representativeand the facility manager.
- Be reviewed and endorsed by the permittee’s BMP Committee annually.
- Include a statement that the above annual reviews have been completed and that the BMP Plan fulfills the requirements set forth in this permit. The statement shall be signed and dated by each BMP Committee member as certification of the annual reviews.

- The permittee must submit a copy of the annual certification statement to the DEC with the December DMR due in January of each year

Establish specific BMPs to meet the objectives identified above, addressing each component or system capable of generating or causing a release of significant amounts of pollutants, and identifying specific preventative or remedial measures to be implemented. The specific BMPs must include the identification of the chemical additive inventory procedures (i.e. implementation procedures, calculation methods, record-keeping and reporting procedures) to ensure compliance with Permit Sections 2.2.8, 2.6.3, and 2.7.

2.11.5 Documentation. The permittee must maintain a copy of the BMP Plan at the facility and make it available to DEC or an authorized representative upon request.

2.11.6 BMP Plan Modification

2.11.6.1 The permittee must modify the BMP Plan whenever there is a change in the facility or in the operation of the facility, which materially increases the generation of pollutants or their release or potential release to waters of the US.

2.11.6.2 The permittee must modify the BMP Plan whenever it is found to be ineffective in achieving the general objective of preventing and minimizing the generation and the potential for the release of pollutants from the facility to waters of the US and/or the specific requirements of Part 2.11.4.

2.11.6.3 Any modifications to the BMP Plan must be consistent with the objectives and specific requirements listed in Part 2.11.3. All changes in the BMP Plan must be reported to DEC with the annual certification required under Permit Part 2.11.4.1.

2.12 Cooling Water Intake Structure Requirements

2.12.1 Applicability: These requirements apply to new offshore oil and gas extraction facilities for which construction was commenced after July 17, 2006, that meet the following criteria: (1) it is a point source that uses or proposes to use a cooling water intake structure; (2) it has at least one cooling water intake structure that uses at least 25 percent of the water it withdraws for cooling purposes as specified Section 2.12.2; and (3) it has a design intake flow greater than 2 million gallons of water per day. The applicant must indicate in the NOI submittal whether its facility meets the three criteria and the approach to comply with Track II requirements.

2.12.2 Threshold Design Intake Flow Capacity: The threshold requirement that at least 25 percent of water withdrawn be used for cooling purposes must be measured on an average monthly basis. A new facility meets the 25 percent cooling water threshold if, based on the new facility's design, any monthly average over a year for the percentage of cooling water withdrawn is expected to equal or exceed 25 percent of the total water withdrawn.

2.12.3 Best Management Practices for All Facilities. New facilities that do not meet the threshold requirements regarding the amount of water withdrawn or percentage of water withdrawn for cooling water purposes in Section 2.12.1 and existing facilities are required to implement BMPs to minimize the impingement mortality and entrainment of all life stages of fish and shellfish in accordance with the BMP Plan requirements. New facilities that meet the threshold requirements are also are required to implement the BMP Plan requirements in addition to the other CWIS Requirements in Appendix H of this general permit.

2.12.4 Appendix H, Cooling Water Intake Structure Requirements for New Facilities: The applicant of a new facility meeting the applicability provisions of Section 2.12.1 must comply with the provisions of Appendix H of this general permit. Appendix H is an integral and enforceable part of this general permit.

2.12.5 More Stringent Requirements: The applicant must comply with any more stringent requirements relating to location, design, construction, and capacity of a CWIS's or monitoring requirements at a new offshore oil and gas extraction facility that DEC deems are reasonably necessary to comply with any provision of federal or state law, including compliance with applicable state water quality standards, including designated uses, criteria, and antidegradation requirements.

2.13 Removed Substances

Collected screenings, grit, solids, scum, and other facility residuals, or other pollutants removed in the course of treatment or control of water and wastewaters shall be disposed of in a Department-approved manner and method in accordance with 18 AAC 60, such as to prevent any pollution from such materials from entering waters of the US.

3.0 SPECIAL CONDITIONS

3.1 Quality Assurance Project Plan

3.1.1 The permittee must develop a QAPP for all monitoring required by this permit. The QAPP must be implemented within 45 days prior to discharge.

3.1.2 The QAPP must be designed to assist in planning for the collection and analysis of effluent and receiving water samples in support of the permit and in explaining data anomalies when they occur.

3.1.3 Throughout all sample collection and analysis activities, the permittee must use the EPA-approved quality assurance/quality control and chain-of-custody procedures described in *Requirements for Quality Assurance Project Plans* (EPA/QA/R-5) and *Guidance for Quality Assurance Project Plans* (EPA/QA/G-5). The QAPP must be prepared in the format which is specified in these documents.

3.1.4 The permittee must amend the QAPP as soon as practicable whenever there is a modification in sample collection, sample analysis, or other procedure addressed by the QAPP.

3.1.5 Copies of the QAPP must be kept on site and made available to DEC or an authorized representative upon request.

Appendix A

Standard Conditions

APPENDIX A

STANDARD CONDITIONS

APDES PERMIT

NONDOMESTIC DISCHARGES

September 2011

TABLE OF CONTENTS

1.0 Standard Conditions Applicable to All Permits A-1

1.1 Contact Information and Addresses A-1
1.2 Duty to Comply A-1
1.3 Duty to Reapply A-2
1.4 Need to Halt or Reduce Activity Not a Defense A-2
1.5 Duty to Mitigate A-2
1.6 Proper Operation and Maintenance A-2
1.7 Permit Actions A-2
1.8 Property Rights A-2
1.9 Duty to Provide Information A-2
1.10 Inspection and Entry A-3
1.11 Monitoring and Records A-3
1.12 Signature Requirement and Penalties A-4
1.13 Proprietary or Confidential Information A-5
1.14 Oil and Hazardous Substance Liability A-5
1.15 Cultural and Paleontological Resources A-6
1.16 Fee A-6
1.17 Other Legal Obligations A-6

2.0 Special Reporting Obligations A-6

2.1 Planned Changes A-6
2.2 Anticipated Noncompliance A-6
2.3 Transfers A-7
2.4 Compliance Schedules A-7
2.5 Corrective Information A-7
2.6 Bypass of Treatment Facilities A-7
2.7 Upset Conditions A-8
2.8 Existing Manufacturing, Commercial, Mining, and Silvicultural Discharges A-8

3.0 Monitoring, Recording, and Reporting Requirements A-9

3.1 Representative Sampling A-9
3.2 Reporting of Monitoring Results A-9
3.3 Additional Monitoring by Permittee A-9
3.4 Twenty-four Hour Reporting A-9
3.5 Other Noncompliance Reporting A-10

4.0 Penalties for Violations of Permit Conditions A-11

4.1 Civil Action A-11
4.2 Injunctive Relief A-11
4.3 Criminal Action A-11
4.4 Other Fines A-12

Appendix A of the permit contains standard regulatory language that must be included in all APDES permits. These requirements are based on the regulations and cannot be challenged in the context of an individual APDES permit action. The standard regulatory language covers requirements such as monitoring, recording, reporting requirements, compliance responsibilities, and other general requirements. Appendix A, Standard Conditions is an integral and enforceable part of the permit. Failure to comply with a Standard Condition in this Appendix constitutes a violation of the permit and is subject to enforcement.

1.0 Standard Conditions Applicable to All Permits

1.1 Contact Information and Addresses

1.1.1 Permitting Program

Documents, reports, and plans required under the permit and Appendix A are to be sent to the following address:

State of Alaska
Department of Environmental Conservation
Division of Water
Wastewater Discharge Authorization Program
555 Cordova Street
Anchorage, Alaska 99501
Telephone (907) 269-6285
Fax (907) 269-3487
Email: DEC.Water.WQPermit@alaska.gov

1.1.2 Compliance and Enforcement Program

Documents and reports required under the permit and Appendix A relating to compliance are to be sent to the following address:

State of Alaska
Department of Environmental Conservation
Division of Water
Compliance and Enforcement Program
555 Cordova Street
Anchorage, Alaska 99501
Telephone Nationwide (877) 569-4114
Anchorage Area / International (907) 269-4114
Fax (907) 269-4604
Email: dec-wqreporting@alaska.gov

1.2 Duty to Comply

A permittee shall comply with all conditions of the permittee's APDES permit. Any permit noncompliance constitutes a violation of 33 U.S.C 1251-1387 (Clean Water Act) and state law and is grounds for enforcement action including termination, revocation and reissuance, or modification of a permit, or denial of a permit renewal application. A permittee shall comply with effluent standards or prohibitions established under 33 U.S.C. 1317(a) for toxic pollutants within the time provided in the regulations that establish those effluent standards or prohibitions even if the permit has not yet been modified to incorporate the requirement.

1.3 Duty to Reapply

If a permittee wishes to continue an activity regulated by this permit after its expiration date, the permittee must apply for and obtain a new permit. In accordance with 18 AAC 83.105(b), a permittee with a currently effective permit shall reapply by submitting a new application at least 180 days before the existing permit expires, unless the Department has granted the permittee permission to submit an application on a later date. However, the Department will not grant permission for an application to be submitted after the expiration date of the existing permit.

1.4 Need to Halt or Reduce Activity Not a Defense

In an enforcement action, a permittee may not assert as a defense that compliance with the conditions of the permit would have made it necessary for the permittee to halt or reduce the permitted activity.

1.5 Duty to Mitigate

A permittee shall take all reasonable steps to minimize or prevent any discharge in violation of this permit that has a reasonable likelihood of adversely affecting human health or the environment.

1.6 Proper Operation and Maintenance

1.6.1 A permittee shall at all times properly operate and maintain all facilities and systems of treatment and control and related appurtenances that the permittee installs or uses to achieve compliance with the conditions of the permit. The permittee's duty to operate and maintain properly includes using adequate laboratory controls and appropriate quality assurance procedures. However, a permittee is not required to operate back-up or auxiliary facilities or similar systems that a permittee installs unless operation of those facilities is necessary to achieve compliance with the conditions of the permit.

1.6.2 Operation and maintenance records shall be retained and made available at the site.

1.7 Permit Actions

A permit may be modified, revoked and reissued, or terminated for cause as provided in 18 AAC 83.130. If a permittee files a request to modify, revoke and reissue, or terminate a permit, or gives notice of planned changes or anticipated noncompliance, the filing or notice does not stay any permit condition.

1.8 Property Rights

A permit does not convey any property rights or exclusive privilege.

1.9 Duty to Provide Information

A permittee shall, within a reasonable time, provide to the Department any information that the Department requests to determine whether a permittee is in compliance with the permit, or whether cause exists to modify, revoke and reissue, or terminate the permit. A permittee shall also provide to the Department, upon request, copies of any records the permittee is required to keep under the permit.

1.10 Inspection and Entry

A permittee shall allow the Department, or an authorized representative, including a contractor acting as a representative of the Department, at reasonable times and on presentation of credentials establishing authority and any other documents required by law, to:

1.10.1 Enter the premises where a permittee's regulated facility or activity is located or conducted, or where permit conditions require records to be kept;

1.10.2 Have access to and copy any records that permit conditions require the permittee to keep;

1.10.3 Inspect any facilities, equipment, including monitoring and control equipment, practices, or operations regulated or required under a permit; and

1.10.4 Sample or monitor any substances or parameters at any location for the purpose of assuring permit compliance or as otherwise authorized by 33 U.S.C. 1251-1387 (Clean Water Act).

1.11 Monitoring and Records

A permittee must comply with the following monitoring and recordkeeping conditions:

1.11.1 Samples and measurements taken for the purpose of monitoring must be representative of the monitored activity.

1.11.2 The permittee shall retain records in Alaska of all monitoring information for at least three years, or longer at the Department's request at any time, from the date of the sample, measurement, report, or application. Monitoring records required to be kept include:

1.11.2.1 All calibration and maintenance records,

1.11.2.2 All original strip chart recordings or other forms of data approved by the Department for continuous monitoring instrumentation,

1.11.2.3 All reports required by a permit,

1.11.2.4 Records of all data used to complete the application for a permit,

1.11.2.5 Field logbooks or visual monitoring logbooks,

1.11.2.6 Quality assurance chain of custody forms,

1.11.2.7 Copies of discharge monitoring reports, and

1.11.2.8 A copy of this APDES permit.

1.11.3 Records of monitoring information must include:

1.11.3.1 The date, exact place, and time of any sampling or measurement;

1.11.3.2 The name(s) of any individual(s) who performed the sampling or measurement(s);

1.11.3.3 The date(s) and time any analysis was performed;

1.11.3.4 The name(s) of any individual(s) who performed any analysis;

1.11.3.5 Any analytical technique or method used; and

1.11.3.6 The results of the analysis.

1.11.4 Monitoring Procedures

Analyses of pollutants must be conducted using test procedures approved under 40 CFR Part 136, adopted by reference at 18 AAC 83.010, for pollutants with approved test procedures, and using test procedures specified in the permit for pollutants without approved methods.

1.12 Signature Requirement and Penalties

1.12.1 Any application, report, or information submitted to the Department in compliance with a permit requirement must be signed and certified in accordance with 18 AAC 83.385. Any person who knowingly makes any false material statement, representation, or certification in any application, record, report, or other document filed or required to be maintained under a permit, or who knowingly falsifies, tampers with, or renders inaccurate any monitoring device or method required to be maintained under this permit shall, upon conviction, be subject to penalties under 33 U.S.C. 1319(c)(4), AS 12.55.035(c)(1)(B), (c)(2) and (c)(3), and AS 46.03.790(g).

1.12.2 In accordance with 18 AAC 83.385, an APDES permit application must be signed as follows:

1.12.2.1 For a corporation, a responsible corporate officer shall sign the application; in this subsection, a responsible corporate officer means:

1.12.2.1.1 A president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy- or decision-making functions for the corporation; or

1.12.2.1.2 The manager of one of more manufacturing, production, or operating facilities, if

1.12.2.1.2.1 The manager is authorized to make management decisions that govern the operation of the regulated facility, including having the explicit or implicit duty of making major capital investment recommendations, and initiating and directing other comprehensive measures to assure long term environmental compliance with environmental statutes and regulations;

1.12.2.1.2.2 The manager can ensure that the necessary systems are established or actions taken to gather complete and accurate information for permit application requirements; and

1.12.2.1.2.3 Authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures.

1.12.2.2 For a partnership or sole proprietorship, by the general partner or the proprietor, respectively, shall sign the application

1.12.2.3 For a municipality, state, federal, or other public agency, either a principal executive officer or ranking elected official shall sign the application; in this subsection, a principal executive officer of an agency means:

1.12.2.3.1 The chief executive officer of the agency; or

1.12.2.3.2 A senior executive officer having responsibility for the overall operations of a principal geographic unit or division of the agency.

1.12.3 Any report required by an APDES permit, and a submittal with any other information requested by the Department, must be signed by a person described in Appendix A, Part 1.12.2, or by a duly authorized representative of that person. A person is a duly authorized representative only if:

1.12.3.1 The authorization is made in writing by a person described in Appendix A, Part 1.12.2;

1.12.3.2 The authorization specifies either an individual or a position having responsibility for the overall operation of the regulated facility or activity, including the position of plant manager, operator of a well or a well field, superintendent, or position of equivalent responsibility; or an individual or position having overall responsibility for environmental matters for the company; and

1.12.3.3 The written authorization is submitted to the Department to the Permitting Program address in Appendix A, Part 1.1.1.

1.12.4 If an authorization under Appendix A, Part 1.12.3 is no longer effective because a different individual or position has responsibility for the overall operation of the facility, a new authorization satisfying the requirements of Appendix A, Part 1.12.3 must be submitted to the Department before or together with any report, information, or application to be signed by an authorized representative.

1.12.5 Any person signing a document under Appendix A, Part 1.12.2 or Part 1.12.3 shall certify as follows:

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."

1.13 Proprietary or Confidential Information

1.13.1 A permit applicant or permittee may assert a claim of confidentiality for proprietary or confidential business information by stamping the words “confidential business information” on each page of a submission containing proprietary or confidential business information. The Department will treat the stamped submissions as confidential if the information satisfies the test in 40 CFR §2.208, adopted by reference at 18 AAC 83.010, and is not otherwise required to be made public by state law.

1.13.2 A claim of confidentiality under Appendix A, Part 1.13.1 may not be asserted for the name and address of any permit applicant or permittee, a permit application, a permit, effluent data, sewage sludge data, and information required by APDES or NPDES application forms provided by the Department, whether submitted on the forms themselves or in any attachments used to supply information required by the forms.

1.13.3 A permittee’s claim of confidentiality authorized under Appendix A, Part 1.13.1 is not waived if the Department provides the proprietary or confidential business information to the EPA or to other agencies participating in the permitting process. The Department will supply any information obtained or used in the administration of the state APDES program to the EPA upon request under 40 CFR §123.41, as revised as of July 1, 2005. When providing information submitted to the Department with a claim of confidentiality to the EPA, the Department will notify the EPA of the confidentiality claim. If the Department provides the EPA information that is not claimed to be confidential, the EPA may make the information available to the public without further notice.

1.14 Oil and Hazardous Substance Liability

Nothing in this permit shall be construed to preclude the institution of any action or relieve a permittee

from any responsibilities, liabilities, or penalties to which the permittee is or may be subject to under state laws addressing oil and hazardous substances.

1.15 Cultural and Paleontological Resources

If cultural or paleontological resources are discovered because of this disposal activity, work that would disturb such resources is to be stopped, and the Office of History and Archaeology, a Division of Parks and Outdoor Recreation of the Alaska Department of Natural Resources (http://www.dnr.state.ak.us/parks/oha/), is to be notified immediately at (907) 269-8721.

1.16 Fee

A permittee must pay the appropriate permit fee described in 18 AAC 72.

1.17 Other Legal Obligations

This permit does not relieve the permittee from the duty to obtain any other necessary permits from the Department or from other local, state, or federal agencies and to comply with the requirements contained in any such permits. All activities conducted and all plan approvals implemented by the permittee pursuant to the terms of this permit shall comply with all applicable local, state, and federal laws and regulations.

2.0 Special Reporting Obligations

2.1 Planned Changes

2.1.1 The permittee shall give notice to the Department as soon as possible of any planned physical alteration or addition to the permitted facility if:

2.1.1.1 The alteration or addition may make the facility a “new source” under one or more of the criteria in 18 AAC 83.990(44); or

2.1.1.2 The alteration or addition could significantly change the nature or increase the quantity of pollutants discharged if those pollutants are not subject to effluent limitations in the permit or to notification requirements under 18 AAC 83.610.

2.1.2 If the proposed changes are subject to plan review, then the plans must be submitted at least 30 days before implementation of changes (see 18 AAC 15.020 and 18 AAC 72 for plan review requirements). Written approval is not required for an emergency repair or routine maintenance.

2.1.3 Written notice must be sent to the Permitting Program address in Appendix A, Part 1.1.1.

2.2 Anticipated Noncompliance

2.2.1 A permittee shall give seven days’ notice to the Department before commencing any planned change in the permitted facility or activity that may result in noncompliance with permit requirements.

2.2.2 Written notice must be sent to the Compliance and Enforcement Program address in Appendix A, Part 1.1.2.

2.3 Transfers

2.3.1 A permittee may not transfer a permit for a facility or activity to any person except after notice to the Department in accordance with 18 AAC 83.150. The Department may modify or revoke and reissue the permit to change the name of the permittee and incorporate such other requirements under 33 U.S.C. 1251-1387 (Clean Water Act) or state law.

2.3.2 Written notice must be sent to the Permitting Program address in Appendix A, Part 1.1.1.

2.4 Compliance Schedules

2.4.1 A permittee must submit progress or compliance reports on interim and final requirements in any compliance schedule of a permit no later than 14 days following the scheduled date of each requirement.

2.4.2 Written notice must be sent to the Compliance and Enforcement Program address in Appendix A, Part 1.1.2.

2.5 Corrective Information

2.5.1 If a permittee becomes aware that it failed to submit a relevant fact in a permit application or submitted incorrect information in a permit application or in any report to the Department, the permittee shall promptly submit the relevant fact or the correct information.

2.5.2 Information must be sent to the Permitting Program address in Appendix A, Part 1.1.1.

2.6 Bypass of Treatment Facilities

2.6.1 Prohibition of Bypass

Bypass is prohibited. The Department may take enforcement action against a permittee for any bypass, unless:

2.6.1.1 The bypass was unavoidable to prevent loss of life, personal injury, or severe property damage;

2.6.1.2 There were no feasible alternatives to the bypass, including use of auxiliary treatment facilities, retention of untreated wastes, or maintenance during normal periods of equipment downtime. However, this condition is not satisfied if the permittee, in the exercise of reasonable engineering judgment, should have installed adequate back-up equipment to prevent a bypass that occurred during normal periods of equipment downtime or preventive maintenance; and

2.6.1.3 The permittee provides notice to the Department of a bypass event in the manner, as appropriate, under Appendix A, Part 2.6.2.

2.6.2 Notice of bypass

2.6.2.1 For an anticipated bypass, the permittee submits notice at least 10 days before the date of the bypass. The Department may approve an anticipated bypass, after considering its adverse effects, if the Department determines that it will meet the conditions of Appendix A, Parts 2.6.1.1 and 2.6.1.2.

2.6.2.2 For an unanticipated bypass, the permittee submits 24-hour notice, as required in 18 AAC 83.410(f) and Appendix A, Part 3.4, Twenty-four Hour Reporting.

2.6.2.3 Written notice must be sent to the Compliance and Enforcement Program address in Appendix A, Part 1.1.2.

2.6.3 Notwithstanding Appendix A, Part 2.6.1, a permittee may allow a bypass that:

2.6.3.1 Does not cause an effluent limitation to be exceeded, and

2.6.3.2 Is for essential maintenance to assure efficient operation.

2.7 Upset Conditions

2.7.1 In any enforcement action for noncompliance with technology-based permit effluent limitations, a permittee may claim upset as an affirmative defense. A permittee seeking to establish the occurrence of an upset has the burden of proof to show that the requirements of Appendix A, Part 2.7.2 are met.

2.7.2 To establish the affirmative defense of upset, the permittee must demonstrate, through properly signed, contemporaneous operating logs or other relevant evidence that:

2.7.2.1 An upset occurred and the permittee can identify the cause or causes of the upset;

2.7.2.2 The permitted facility was at the time being properly operated;

2.7.2.3 The permittee submitted 24-hour notice of the upset, as required in 18 AAC 83.410(f) and Appendix A, Part 3.4, Twenty-four Hour Reporting; and

2.7.2.4 The permittee complied with any mitigation measures required under 18 AAC 83.405(e) and Appendix A, Part 1.5, Duty to Mitigate.

2.7.3 Any determination made in administrative review of a claim that noncompliance was caused by upset, before an action for noncompliance is commenced, is not final administrative action subject to judicial review.

2.8 Existing Manufacturing, Commercial, Mining, and Silvicultural Discharges

2.8.1 In addition to the reporting requirements under 18 AAC 83.410, an existing manufacturing, commercial, mining, and silvicultural discharger shall notify the Department as soon as that discharger knows or has reason to believe that any activity has occurred or will occur that would result in:

2.8.1.1 The discharge, on a routine or frequent basis, of any toxic pollutant that is not limited in the permit, if that discharge will exceed the highest of the following notification levels:

2.8.1.1.1 One hundred micrograms per liter (100 µg/L);

2.8.1.1.2 Two hundred micrograms per liter (200 µg/L) for acrolein and acrylonitrile, 500 micrograms per liter (500 µg/L) for 2,4-dinitrophenol and for 2-methyl-4,6-dinitrophenol, and one milligram per liter (1 mg/L) for antimony;

2.8.1.1.3 Five times the maximum concentration value reported for that pollutant in the permit application in accordance with 18 AAC 83.310(c)-(g); or

2.8.1.1.4 The level established by the Department in accordance with 18 AAC 83.445.

2.8.1.2 Any discharge, on a non-routine or infrequent basis, of a toxic pollutant that is not limited in the permit, if that discharge will exceed the highest of the following notification levels:

2.8.1.2.1 Five hundred micrograms per liter (500 µg/L);

2.8.1.2.2 One milligram per liter (1 mg/L) for antimony;

2.8.1.2.3 Ten times the maximum concentration value reported for that pollutant in the permit application in accordance with 18 AAC 83.310(c)-(g); or

2.8.1.2.4 The level established by the Department in accordance with 18 AAC 83.445.

3.0 Monitoring, Recording, and Reporting Requirements

3.1 Representative Sampling

A permittee must collect effluent samples from the effluent stream after the last treatment unit before discharge into the receiving waters. Samples and measurements must be representative of the volume and nature of the monitored activity or discharge.

3.2 Reporting of Monitoring Results

At intervals specified in the permit, monitoring results must be reported on the EPA discharge monitoring report (DMR) form, as revised as of March 1999, adopted by reference.

3.2.1 Monitoring results shall be summarized each month on the DMR or an approved equivalent report. The permittee must submit reports monthly postmarked by the 15th day of the following month.

3.2.2 The permittee must sign and certify all DMRs and all other reports in accordance with the requirements of Appendix A, Part 1.12, Signatory Requirements and Penalties. All signed and certified legible original DMRs and all other documents and reports must be submitted to the Department at the Compliance and Enforcement Program address in Appendix A, Part 1.1.2.

3.2.3 If, during the period when this permit is effective, the Department makes available electronic reporting, the permittee may, as an alternative to the requirements of Appendix A, Part 3.2.2, submit monthly DMRs electronically by the 15th day of the following month in accordance with guidance provided by the Department. The permittee must certify all DMRs and other reports, in accordance with the requirements of Appendix A, Part 1.12, Signatory Requirements and Penalties. The permittee must retain the legible originals of these documents and make them available to the Department upon request.

3.3 Additional Monitoring by Permittee

If the permittee monitors any pollutant more frequently than the permit requires using test procedures approved in 40 CFR Part 136, adopted by reference at 18 AAC 83.010, or as specified in this permit, the results of that additional monitoring must be included in the calculation and reporting of the data submitted in the DMR required by Appendix A, Part 3.2. All limitations that require averaging of measurements must be calculated using an arithmetic means unless the Department specifies another method in the permit. Upon request by the Department, the permittee must submit the results of any other sampling and monitoring regardless of the test method used.

3.4 Twenty-four Hour Reporting

A permittee shall report any noncompliance event that may endanger health or the environment as follows:

3.4.1 A report must be made:

3.4.1.1 Orally within 24 hours after the permittee becomes aware of the circumstances, and

3.4.1.2 In writing within five days after the permittee becomes aware of the circumstances.

3.4.2 A report must include the following information:

3.4.2.1 A description of the noncompliance and its causes, including the estimated volume or weight and specific details of the noncompliance;

3.4.2.2 The period of noncompliance, including exact dates and times;

3.4.2.3 If the noncompliance has not been corrected, a statement regarding the anticipated time the noncompliance is expected to continue; and

3.4.2.4 Steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance.

3.4.3 An event that must be reported within 24 hours includes:

3.4.3.1 An unanticipated bypass that exceeds any effluent limitation in the permit (see Appendix A, Part 2.6, Bypass of Treatment Facilities).

3.4.3.2 An upset that exceeds any effluent limitation in the permit (see Appendix A, Part 2.7, Upset Conditions).

3.4.3.3 A violation of a maximum daily discharge limitation for any of the pollutants listed in the permit as requiring 24-hour reporting.

3.4.4 The Department may waive the written report on a case-by-case basis for reports under Appendix A, Part 3.4 if the oral report has been received within 24 hours of the permittee becoming aware of the noncompliance event.

3.4.5 The permittee may satisfy the written reporting submission requirements of Appendix A, Part 3.4 by submitting the written report via e-mail, if the following conditions are met:

3.4.5.1 The Noncompliance Notification Form or equivalent form is used to report the noncompliance;

3.4.5.2 The written report includes all the information required under Appendix A, Part 3.4.2;

3.4.5.3 The written report is properly certified and signed in accordance with Appendix A, Parts 1.12.3 and 1.12.5.;

3.4.5.4 The written report is scanned as a PDF (portable document format) document and transmitted to the Department as an attachment to the e-mail; and

3.4.5.5 The permittee retains in the facility file the original signed and certified written report and a printed copy of the conveying email.

3.4.6 The e-mail and PDF written report will satisfy the written report submission requirements of this permit provided the e-mail is received by the Department within five days after the time the permittee becomes aware of the noncompliance event and the e-mail and written report satisfy the criteria of Part 3.4.5. The e-mail address to report noncompliance is: dec-wqreporting@alaska.gov

3.5 Other Noncompliance Reporting

A permittee shall report all instances of noncompliance not required to be reported under Appendix A, Parts 2.4 (Compliance Schedules), 3.3 (Additional Monitoring by Permittee), and 3.4 (Twenty-four Hour Reporting) at the time the permittee submits monitoring reports under Appendix A, Part 3.2 (Reporting of Monitoring Results). A report of noncompliance under this part must contain the information listed in Appendix A, Part 3.4.2 and be sent to the Compliance and Enforcement Program address in Appendix A, Part 1.1.2.

4.0 Penalties for Violations of Permit Conditions

Alaska laws allow the State to pursue both civil and criminal actions concurrently. The following is a summary of Alaska law. Permittees should read the applicable statutes for further substantive and procedural details.

4.1 Civil Action

Under AS 46.03.760(e), a person who violates or causes or permits to be violated a regulation, a lawful order of the Department, or a permit, approval, or acceptance, or term or condition of a permit, approval or acceptance issued under the program authorized by AS 46.03.020 (12) is liable, in a civil action, to the State for a sum to be assessed by the court of not less than $500 nor more than $100,000 for the initial violation, nor more than $10,000 for each day after that on which the violation continues, and that shall reflect, when applicable:

4.1.1 Reasonable compensation in the nature of liquated damages for any adverse environmental effects caused by the violation, that shall be determined by the court according to the toxicity, degradability, and dispersal characteristics of the substance discharged, the sensitivity of the receiving environment, and the degree to which the discharge degrades existing environmental quality;

4.1.2 Reasonable costs incurred by the State in detection, investigation, and attempted correction of the violation;

4.1.3 The economic savings realized by the person in not complying with the requirements for which a violation is charged; and

4.1.4 The need for an enhanced civil penalty to deter future noncompliance.

4.2 Injunctive Relief

4.2.1 Under AS 46.03.820, the Department can order an activity presenting an imminent or present danger to public health or that would be likely to result in irreversible damage to the environment be discontinued. Upon receipt of such an order, the activity must be immediately discontinued.

4.2.2 Under AS 46.03.765, the Department can bring an action in Alaska Superior Court seeking to enjoin ongoing or threatened violations for Department-issued permits and Department statutes and regulations.

4.3 Criminal Action

Under AS 46.03.790(h), a person is guilty of a Class A misdemeanor if the person negligently:

4.3.1 Violates a regulation adopted by the Department under AS 46.03.020(12);

4.3.2 Violates a permit issued under the program authorized by AS 46.03.020(12);

4.3.3 Fails to provide information or provides false information required by a regulation adopted under AS 46.03.020(12);

4.3.4 Makes a false statement, representation, or certification in an application, notice, record, report, permit, or other document filed, maintained, or used for purposes of compliance with a permit issued under or a regulation adopted under AS 46.03.020(12); or

4.3.5 Renders inaccurate a monitoring device or method required to be maintained by a permit issued or under a regulation adopted under AS 46.03.020(12).

4.4 Other Fines

Upon conviction of a violation of a regulation adopted under AS 46.03.020(12), a defendant who is not an organization may be sentenced to pay a fine of not more than $10,000 for each separate violation (AS 46.03.790(g)). A defendant that is an organization may be sentenced to pay a fine not exceeding the greater of: (1) $200,00; (2) three times the pecuniary gain realized by the defendant as a result of the offense; or (3) three times the pecuniary damage or loss caused by the defendant to another, or the property of another, as a result of the offense (AS 12.55.035(c)(B), (c)(2), and (c)(3)).

APPENDIX B **ACRONYMS**

Appendix B

Acronyms

The following acronyms are common terms that may be found in an Alaska Pollutant Discharge Elimination System (APDES) permit.

18 AAC 15	Alaska Administrative Code. Title 18 Environmental Conservation, Chapter 15: Administrative Procedures
18 AAC 60	Alaska Administrative Code. Title 18 Environmental Conservation, Chapter 60: Solid Waste Management
18 AAC 70	Alaska Administrative Code. Title 18 Environmental Conservation, Chapter 70: Water Quality Standards
18 AAC 72	Alaska Administrative Code. Title 18 Environmental Conservation, Chapter 72: Wastewater Disposal
18 AAC 83	Alaska Administrative Code. Title 18 Environmental Conservation, Chapter 83: Alaska Pollutant Discharge Elimination System

All chapters of Alaska Administrative Code, Title 18 are available at the Alaska Administrative Code database http://www.legis.state.ak.us/cgi-bin/folioisa.dll/aac

40 CFR	Code of Federal Regulations Title 40: Protection of Environment
AAC	Alaska Administrative Code
ADNR	Alaska Department of Natural Resources
APDES	Alaska Pollutant Discharge Elimination System
AS	Alaska Statutes
AS 46.03	Alaska Statutes Title 46, Chapter 03: Environmental Conservation. Available at http://www.legis.state.ak.us/default.htm
ASMA	Area Meriting Special Attention
BOD_5	Biochemical Oxygen Demand, 5-day
BMP	Best Management Practice
BPJ	Best Professional Judgment
BPT	Best Practicable Control Technology (currently available)
BTUs	British Thermal Units

CFR	Code of Federal Regulations
CWA	Clean Water Act
CWIS	Cooling water intake structures
DEC	Alaska Department of Environmental Conservation
DFP	Drilling Fluid Plan
DMR	Discharge Monitoring Report
DNR	Alaska Department of Natural Resources
EFH	Essential Fish Habitat
ELGs	Effluent Limitation Guidelines
EOW	End-of-well
EPA	U.S. Environmental Protection Agency
ESA	Endangered Species Act
FC	Fecal Coliform Bacteria
M9IM	Facilities that are intermittently staffed or have a regular staff of nine or fewer people
mg/L	Milligrams per Liter
MZ	Mixing Zone
NMFS	National Marine Fisheries Service
NOI	Notice of Intent
NPDES	National Pollutant Discharge Elimination System
ODCE	Ocean Discharge Criteria Evaluation
RCRA	Resource Conservation and Recovery Act
SU	Standard Units
TBELs	Technology Based Effluent Limits
TMDL	Total Maximum Daily Load
TRC	Total Residual Chlorine

TSS	Total Suspended Solids
U.S.C.	United States Code
USFWS	United States Fish & Wildlife Service
WET	Whole Effluent Toxicity
WQS	Water Quality Standards

APPENDIX C **DEFINITIONS**

Appendix C

Definitions

The following are common definitions of terms associated with APDES permits. Not all the terms listed may appear in a permit. Consult the footnote references for a complete list of terms and definitions.

Alaska Pollutant Discharge Elimination System (APDES)[a]	Means the state's program, approved by EPA under 33 U.S.C. 1342(b), for issuing, modifying, revoking and reissuing, terminating, monitoring and enforcing permits and imposing and enforcing pretreatment requirements under 33 U.S.C. 1317, 1328, 1342, and 1345
Annual	Means once per calendar year
Average	Means an arithmetic mean obtained by adding quantities and dividing the sum by the number of quantities
Average Monthly Discharge Limitation[a]	Means the highest allowable average of "daily discharges" over a calendar month calculated as the sum of all "daily discharges" measured during a calendar month divided by the number of "daily discharges" measured for that month.
Best Management Practices (BMPs)[a]	Means schedules of activities, prohibitions of practices, maintenance procedures, and other management practices to prevent or reduce the pollution of waters of the United States. BMPs also include treatment requirements, operating procedures, and practices to control plant site runoff, spillage or leaks, sludge or waste disposal, or drainage from raw material storage areas.
Biochemical Oxygen Demand (BOD)[c]	Means the amount, in milligrams per liter, of oxygen used in the biochemical oxidation of organic matter in five days at 20º C
Bypass[a]	Means the intentional diversion of waste streams from any portion of a treatment facility
Clean Water Act (CWA)[a]	Means the federal law codified at 33 U.S.C. 1251-1387, also referred to as the Federal Water Pollution Control Act or Federal Water Pollution Control Act Amendments of 1972
Coastal	Means any location in or on a water of the United States landward of the inner boundary of the territorial seas.

a) See 18 AAC 83
b) See 18 AAC 70.990
c) See 18 AAC 72.990
d) See 40 CFR Part 136
e) See EPA Technical Support Document
f) See Standard Methods for the Examination of Water and Wastewater 18th Edition
g) See EPA Permit Writers Manual

Color[b]	Means the condition that results in the visual sensations of hue and intensity as measured after turbidity is removed
Commissioner[a]	Means the commissioner of the Alaska Department of Environmental Conservation or the commissioner's designee
Composite Samples	Composite samples must consist of at least eight equal volume grab samples. 24 hour composite sample means a combination of at least eight discrete samples of equal volume collected at equal time intervals over a 24-hour period at the same location. A "flow proportional composite" sample means a combination of at least eight discrete samples collected at equal time intervals over a 24-hour period with each sample volume proportioned according to the flow volume. The sample aliquots must be collected and stored in accordance with procedures prescribed in the most recent edition of *Standard Methods for the Examination of Water and Wastewater*.
Contact Recreation[b]	Means activities in which there is direct and intimate contact with water. Contact recreation includes swimming, diving, and water skiing. Contact recreation does not include wading.
Criterion[b]	Means a set concentration or limit of a water quality parameter that, when not exceeded, will protect an organism, a population of organisms, a community of organisms, or a prescribed water use with a reasonable degree of safety. A criterion might be a narrative statement instead of a numerical concentration or limit.
Daily Discharge[a]	Means the discharge of a pollutant measured during a calendar day or any 24-hour period that reasonably represents the calendar day for the purposes of sampling. For pollutants measured in units of mass, the "daily discharge" is calculated as the total mass of the pollutant discharged over the day. For pollutants with a limitation expressed in other units of measurement, the "daily discharge" is calculated as the average measurement of the pollutant over the day.
Department[a]	Means the Alaska Department of Environmental Conservation
Design Flow[a]	Means the wastewater flow rate that the plant was designed to handle

a) See 18 AAC 83
b) See 18 AAC 70.990
c) See 18 AAC 72.990
d) See 40 CFR Part 136
e) See EPA Technical Support Document
f) See Standard Methods for the Examination of Water and Wastewater 18th Edition
g) See EPA Permit Writers Manual

Director[a]	Means the commissioner or the commissioner's designee assigned to administer the APDES program or a portion of it, unless the context identifies an EPA director
Discharge[a]	When used without qualification, discharge means the discharge of a pollutant
Discharge of a Pollutant[a]	Means any addition of any pollutant or combination of pollutants to waters of the United States from any point source or to waters of the contiguous zone or the ocean from any point source other than a vessel or other floating craft that is being used as a means of transportation. Discharge includes any addition of pollutants into waters of the United States from surface runoff that is collected or channeled by humans; discharges through pipes, sewers, or other conveyances owned by a state, municipality, or other person that do not lead to a treatment works; discharges through pipes, sewers, or other conveyances leading into privately owned treatment works; and does not include an addition of pollutants by any indirect discharger.
Domestic Wastewater[c]	Means waterborne human wastes or graywater derived from dwellings, commercial buildings, institutions, or similar structures. "Domestic wastewater" includes the contents of individual removable containers used to collect and temporarily store human wastes.
Effluent[b]	Means the segment of a wastewater stream that follows the final step in a treatment process and precedes discharge of the wastewater stream to the receiving environment
Estimated	Means a way to estimate the discharge volume. Approvable estimations include, but are not limited to, the number of persons per day at the facility, volume of potable water produced per day, lift station run time, etc.
Excluded area	Means an area not authorized as a receiving water under a permit
Fecal Coliform Bacteria (FC)[b]	Bacteria that can ferment lactose at 44.5° + 0.2°C to produce gas in a multiple tube procedure. Fecal coliform bacteria also means all bacteria that produce blue colonies in a membrane filtration procedure within 24 ± 2 hours of incubation at 44.5° + 0.2°C in an M-FC broth.
Fish[b]	Means any of the group of cold-blooded vertebrates that live in water and have permanent gills for breathing and fins for locomotion

a) See 18 AAC 83
b) See 18 AAC 70.990
c) See 18 AAC 72.990
d) See 40 CFR Part 136
e) See EPA Technical Support Document
f) See Standard Methods for the Examination of Water and Wastewater 18th Edition
g) See EPA Permit Writers Manual

Geometric Mean	The geometric mean is the Nth root of the product of N. All sample results of zero will use a value of 1 for calculation of the geometric mean. Example geometric mean calculation: $\sqrt[4]{12x23x34x990} = 55$.
Grab Sample	Means a single instantaneous sample collected at a particular place and time that represents the composition of wastewater only at that time and place
Graywater[b]	Means wastewater from a laundry, kitchen, sink, shower, bath, or other domestic source that does not contain excrement, urine, or combined storm water
Influent	Means untreated wastewater before it enters the first treatment process of a wastewater treatment works
Maximum Daily Discharge Limitation[a]	Means the highest allowable "daily discharge"
Mean[b]	Means the average of values obtained over a specified period and, for fecal coliform analysis, is computed as a geometric mean
Measured	Means the actual volume of wastewater discharged using appropriate mechanical or electronic equipment to provide a totalized reading. Measure does not provide a recorded measurement of instantaneous rates.
Milligrams per Liter (mg/L)[b]	Means the concentration at which one thousandth of a gram (10^{-3} g) is found in a volume of one liter. It is approximately equal to the unit "parts per million (ppm)," formerly of common use.
Mixing Zone[b]	Means a volume of water adjacent to a discharge in which wastes discharged mix with the receiving water
Month	Means the time period from the 1st of a calendar month to the last day in the month

a) See 18 AAC 83
b) See 18 AAC 70.990
c) See 18 AAC 72.990
d) See 40 CFR Part 136
e) See EPA Technical Support Document
f) See Standard Methods for the Examination of Water and Wastewater 18th Edition
g) See EPA Permit Writers Manual

Monthly Average	Means the average of daily discharges over a monitoring month calculated as the sum of all daily discharges measured during a monitoring month divided by the number of daily discharges measured during that month
New Facility	Means a facility that has not operated in the area specified in the Notice of intent (NOI) prior to the submission of the NOI.
Offshore	Means offshore of the inner boundary of the territorial seas.
Open waters	Means ponds, lakes, streams, rivers, and marine waters not covered by ice.
Permittee	Means a company, organization, association, entity, or person who is issued a wastewater permit and is responsible for ensuring compliance, monitoring, and reporting as required by the permit
pH[g]	Means a measure of the hydrogen ion concentration of water or wastewater; expressed as the negative log of the hydrogen ion concentration in mg/L. A pH of 7 is neutral. A pH less than 7 is acidic, and a pH greater than 7 is basic.
Primary Treatment [c]	Means wastewater treatment that: (a) will subsequently discharge wastewater to land or waters that are not waters of the United States and substantially removes all floating and settleable solids; or uses fine screens with 0.04-inch or smaller openings; or (b) will subsequently discharge wastewater to waters of the United States and uses screening, sedimentation, and skimming adequate to remove at least 30 percent of the biochemical oxygen demanding material and of the suspended solids in the treatment works influent; and disinfection, where appropriate.
Principal Executive Officer[a]	Means the chief executive officer of the agency or a senior executive officer having responsibility for the overall operations of a principal geographic unit of division of the agency
Pollutant[a]	Means dredged spoil, solid waste, incinerator residue, filter backwash, sewage, garbage, sewage sludge, munitions, chemical wastes, biological materials, radioactive materials (except those regulated under 42 U.S.C. 2011), heat, wrecked or discarded equipment, rock, sand, cellar dirt, and industrial, municipal, or agricultural waste discharged into water

a) See 18 AAC 83
b) See 18 AAC 70.990
c) See 18 AAC 72.990
d) See 40 CFR Part 136
e) See EPA Technical Support Document
f) See Standard Methods for the Examination of Water and Wastewater 18th Edition
g) See EPA Permit Writers Manual

Receiving WaterBody	Means lakes, bays, sounds, ponds, impounding reservoirs, springs, wells, rivers, streams, creeks, estuaries, marshes, inlets, straits, passages, canals, the Pacific Ocean, Gulf of Alaska, Bering Sea, and Arctic Ocean, in the territorial limits of the state, and all other bodies of surface water, natural or artificial, public or private, inland or coastal, fresh or salt, which are wholly or partially in or bordering the state or under the jurisdiction of the state. (See "Waters of the U.S." at 18 AAC 83.990(77))
Recommencing Facilities	Those facilities that may have let permit coverage lapse but still meet the coverage requirements of the PERMIT.
Report	Report results of analysis.
Residual Chlorine	Means chlorine remaining in water or wastewater at the end of a specified contact period as combined or free chlorine.
Responsible Corporate Officer[a]	Means a president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function or any other person who performs similar policy or decision making functions for the corporation The Responsible Corporate Officer can also be the manager of one or more manufacturing, production, or operating facilities if the requirements of 18 AAC 83.385(a)(1)(B)(i)-(iii) are met.
Secondary Recreation[b]	Means activities in which incidental water use can occur. Secondary recreation includes boating, camping, hunting, hiking, wading, and recreational fishing. Secondary contact recreation does not include fish consumption.
Severe Property Damage[a]	Means substantial physical damage to property, damage to the treatment facilities which causes them to become inoperable, or substantial and permanent loss of natural resources which can reasonably be expected to occur in the absence of a bypass. Severe property damage does not mean economic loss caused by delays in production.
Sheen[b]	Means an iridescent appearance on the water surface
Shellfish[b]	Means a species of crustacean, mollusk, or other aquatic invertebrate with a shell or shell-like exoskeleton in any stage of its life cycle

a) See 18 AAC 83
b) See 18 AAC 70.990
c) See 18 AAC 72.990
d) See 40 CFR Part 136
e) See EPA Technical Support Document
f) See Standard Methods for the Examination of Water and Wastewater 18th Edition
g) See EPA Permit Writers Manual

Territorial Seas	Means the belt of the seas measured from the line of ordinary low water along that portion of the coast which is in direct contact with the open sea and the line marking the off shore limit of inland waters, and extending off shore a distance of three miles.
Total Suspended Solids (TSS)[g]	Means a measure of the filterable solids present in a sample, as determined by the method specified in 40 CFR Part 136
Twice per year	Means two time periods during the calendar year: October through April and May through September
Upset[a]	Means an exceptional incident in which there is unintentional and temporary noncompliance with technology-based effluent limitations because of factors beyond the reasonable control of the permittee. An upset does not include noncompliance to the extent caused by operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation.
Wastewater Treatment	Means any process to which wastewater is subjected in order to remove or alter its objectionable constituents and make it suitable for subsequent use or acceptable for discharge to the environment
Waters of the United States or Waters of the U.S.	Has the meaning given in 18 AAC 83.990(77)
Water Recreation[b]	See contact recreation or secondary recreation
Water Supply[b]	Means any of the waters of the United States that are designated in 18 AAC 70 to be protected for fresh water or marine water uses. Water supply includes waters used for drinking, culinary, food processing, agricultural, aquacultural, seafood processing, and industrial purposes. Water supply does not necessarily mean that water in a waterbody that is protected as a supply for the uses listed in this paragraph is safe to drink in its natural state.
Week	Means the time period of Sunday through Saturday

a) See 18 AAC 83
b) See 18 AAC 70.990
c) See 18 AAC 72.990
d) See 40 CFR Part 136
e) See EPA Technical Support Document
f) See Standard Methods for the Examination of Water and Wastewater 18th Edition
g) See EPA Permit Writers Manual

APPENDIX D **COOK INLET COVERAGE AREA**

Appendix D

Cook Inlet Coverage Area


RUSSIA
Chukchi Sea
CANADA
Bering Sea
MAP LOCATION
Gulf of Alaska
Legend
Baseline
State Permit Coverage Area
N
Wasilla
Knik Arm
Anchorage
Beluga
Tyonek
Fire Island
Point Possession
Chickaloon Bay
Turnagain Arm
Girdwood
Trading Bay
Kustatan
Nikiski
Salamatof
Kenai
Redoubt Bay
Soldotna
Kalgin Island
Skilak Lake
Kasilof
Clam Gulch
Tustumena Lake
Tuxedni Bay
Chisik Island
Ninilchik
Seward
Day Harbor
Cook Inlet
Iniskin
Chinitna Bay
Chinitna Point
Dutton
Homer
Kachemak Bay
Halibut Cove
Jakolof Bay
Seldovia
Augustine Island
Kamishak Bay
Gulf of Alaska
0 15 30 45 60 75 90 Miles
Barren Islands
Sugarloaf Island
Shuyak Island
Shelikof Strait
COOK INLET APDES
ALASKA DEPARTMENT OF ENVIRONMENTAL CONSERVATION
PERMIT COVERAGE AREA
APDES 315100
COOK INLET, ALASKA
JOB NO: 26221222 DRAWN: CMS
DATE: MAY 2014 FILE: SEE PATH
FIGURE 1
The Department of Environmental Conservation (DEC) has compiled the computer representation from data or information sources that may not have been verified by the DEC. This general representation should not be re-used without verification of sources by an independent professional qualified to verify such data or information. DEC does not guarantee the accuracy, completeness or timeliness of the information shown and shal not be liable for any loss or injury resulting from reference upon the information shown. Sources: Alaska Department of Natural Resources, Land Records GIS.

APPENDIX E **SPP METHOD**

Appendix E

Method for Conducting a Sediment Toxicity Test with *Leptocherius plumulosus* and Non-aqueous Fluids or Synthetic Based Drilling Muds

Introduction

This test method describes procedures for obtaining data regarding the effects of non-aqueous fluids (NAF) or synthetic based drilling muds (SBMs) on the marine amphipod, *Leptocheirus plumulosus*. The tests are conducted in a similar manner; differences are noted in the text and tables below. USEPA is regulating the sediment toxicity of NAFs and SBMs discharged by oil and gas extraction facilities in coastal and offshore waters as an indication of the toxicity of the drilling muds (USEPA 2000). This test method conforms to the Effluent Limitations Guidelines specified in 40 CFR part 435 (see 66 FR 6849, January 22, 2001). As specified in the Effluent Limitations Guidelines, this test method is consistent with ASTM Standard Guide E 1367-92 (ASTM 1997). Since ASTM E 1367-92 was outdated at the time 40 CFR part 435 (see 66 FR 6849, January 22, 2001) was published in the Federal Register, this test method is also consistent with ASTM E 1367-99 (ASTM 2000), which is the latest version published by ASTM.

Test Species

L. plumulosus is an infaunal amphipod that is indigenous to subtidal regions along the east coast of the U.S. This amphipod constructs U-shaped burrows in the top 5 cm of fine sand to silty clay sediments (ASTM E1367-99). As a result of its broad salinity and particle size tolerances, it is a desirable test species for a variety of toxicity testing programs.

Collection and Handling

In the field, amphipods can be collected using sediment grab samplers such as Peterson and Ponar dredges. This species has been collected in various tributaries of the Chesapeake Bay for various toxicity testing programs (ASTM E 1367-99). The contents of each grab should be sieved through a 500 □m mesh screen. The sediment and organisms retained on the screen are gently rinsed into plastic buckets containing sediment and water from the collection site. These buckets are quickly transported back to the laboratory and aerated. See ASTM E 1367-99 for more details on collection and handling.

Holding and Acclimation

Amphipods can be placed in aquaria containing a 1-2 cm deep layer of collection site sediment that has been sieved through a 500 μ m mesh screen. Amphipod density should be about 200-300 per 40 L aquarium with vigorous aeration. Two to three days are sufficient for acclimation to test conditions, and during this period a gradual change over from site water to test water is recommended (ASTM E 1367-99).

Environmental Tolerances

L. plumulosus is tolerant of a broad salinity range, from near 0 to 33 g/kg (‰) (ASTM E 1367-99). This species has demonstrated up to 100% survival in >90% silt-clay sediment and an average of 85% survival in >95% sand/gravel sediment (ASTM E 1367-99). The ASTM data are consistent with data published from other studies indicating that *L. plumulosus* is tolerant of sandy and silty sediments. For example, Schlekat et al. (1992) noted a mean survival of 97.5% when *L. plumulosus* was exposed for 10 days to field collected sediments ranging from 98.1% sand to 96.5% fines. Further, this species was collected in

the field in sediments consisting of 99.9% sand and 92.1% fines, indicating that *L. plumulosus* is a generalist and can thrive in a variety of sediment types (Schlekat et al. 1992).

However, the fine fraction of sediments in the Schlekat et al. study did not exceed 55% clay, indicating that the fine fraction was a mixture of silt and clay sized particles. Data from other studies indicated that this species is intolerant of sediments high in clay content. McGee et al. (1999) noted acceptable survival when this species was exposed to Baltimore Harbor sediments containing up to 72% clay. However, Emery et al. (1997) noted significantly reduced amphipod survival when *L. plumulosus* was exposed for 10 days to Magothy River, Maryland sediment (amended with beach sand and kaolinite clay) containing 84%, 90%, and 100% clay.

These data indicated that the tolerance range of this amphipod to clay content is between about 72 to 84%. As such, caution should be used when conducting *L. plumulosus* toxicity tests with sediments with clay content greater than about 70%. This should not have a significant impact on using this species in the NAF and SBM toxicity testing program, since field sediments seldom exceed 70% clay content (Suedel and Rodgers 1991).

Control Sediments

Control sediment must meet certain minimum requirements to be used in the SBM testing program. The primary requirement is that the sediment should be able to support *L. plumulosus* in cultures for extended periods of time. This will ensure that the sediment is chemically nontoxic and that the physical and chemical characteristics of the sediment (e.g., total organic carbon, particle size distribution, and moisture content) are within the tolerance range of the test species. It is expected that separate aliquots of the culture sediment will also be used as a control sediment to be amended by NAFs or SBMs in the NAF/SBM testing program. Any modifications made to the control sediments should be noted in the report.

Characterization

Sediments used in testing should be characterized for total organic carbon (TOC), particle size distribution (sand, silt, and clay), and percent water content. These parameters have been shown to influence the results of NAF/SBM toxicity to *L. plumulosus* in initial experiments. Variations in these sediment characteristics should be quantified so that potential effects of these parameters on test results can be closely monitored.

Collection

Control sediments should be collected from the amphipod collection site or from another area that can provide a consistent source of sediment with characteristics within the tolerance range of *L. plumulosus*. Sediments showing evidence of chemical contamination should not be used in the NAF/SBM testing program. Any site water overlying the sediment should be retained so that fine particles suspended in the water can be re-combined with the sediment before use. Sediment salinity and temperature should be

recorded at the time of collection. Sediment collected for use should be homogenized and a composite sample prepared for analysis for the parameters outlined above.

Sieving

Sediments collected in the field for culturing and testing purposes should be first press-sieved through a 2,000 □m or similar mesh sieve to remove large debris and then through a 500 μ m mesh sieve to remove any indigenous organisms. Sediments have also been press-sieved through a 250 to 350 μ m mesh sieve prior to testing to aid in the enumeration of amphipods on a 500 μ m mesh sieve at test termination.

Storage

The control sediment should be stored in plastic or glass containers at 4±3°C until test initiation. The sediment should be stored in the dark and should not be allowed to freeze or dry out during storage (E 1367-92).

Test Water

Water used in the NAF/SBM program should be available in sufficient quantities and be acceptable to *L. plumulosus*. The minimum requirement for acceptable water for use in the NAF program is that healthy test organisms survive in the water, and in the water plus control sediment, for the duration of holding and testing without showing signs of disease or stress (ASTM E 1367-99). Another test for acceptability of the test water would be its successful use in the culturing of *L. plumulosus* (with the control sediment).

Natural seawater or synthetic salt water can be used in the NAF program. Natural salt water should be obtained from an uncontaminated area known to support a healthy, reproducing population of *L. plumulosus* or similar sensitive species. Reconstituted salt water can be prepared by adding commercially available sea salt in specified quantities. Natural seawater should be filtered by passing through a 5 micron filter before use. The reader is referred to ASTM E 1367-92 or E 1367-99 for more information concerning test water.

Mixing NAFs or SBMs with Control Sediment

Appendix 3 to Subpart A of Part 435 – Procedure for Mixing Base Fluids with Sediments (40 CFR parts 9 and 435 pages 6901-6902) describes a method for amending control sediments with synthetic-based drilling fluids. This same method can be used to amend control sediments with NAFs and SBMs. The control sediment should be sieved and homogenized before wet to dry weight ratio and density determinations are made and before NAFs are added to the control sediment. The following steps were

given in 40 CFR Appendix 3 for mixing NAFs and SBMs with control sediments (parentheses were added here to provide additional information):

1. Determine the wet to dry weight ratio for the control sediment (three replicates of 30 g each has been used successfully);
2. Determine the density (g/ml) of the control sediment (three replicates of >25 ml is suitable for this purpose);
3. Determine the amount of NAF or SBM needed to obtain a desired test concentration;
    a. Determine the amount of wet sediment required;
    b. Determine the amount of dry sediment in kilograms for each test concentration;
    c. Determine the amount of NAF or SBM required to amend the control sediment at each test concentration;
4. Mix NAF or SBM with control sediment;
5. Test for homogeneity of NAF or SBM in sediment, and;
6. Mix sufficient quantities of NAF or SBM with control sediment for each treatment of amended or spiked sediment.

The six steps given above for base fluids can also be applied to SBMs, except that the third bullet in Step 3 requires a measurement of the density of the SBM. The density of the SBM can then be used to estimate

the quantity required for the desired test concentration. Refer to the formulas below for NAF and SBM calculations:

$$\text{NAF Required (g)} = \frac{\text{Conc Desired (mg/kg)}}{\text{1000g/kg}} \times \frac{\text{Dry Weight Sediment (g)}}{\text{1000 mg/g}}$$

SBM Required = Conc. Desired x Dry Weight Sediment x SBM Density

(g) (ml/kg) (kg) (g/ml)

See 40 CFR parts 9 and 435 pages 6901-6902 for more information regarding this procedure.

Mixing Procedure

Mixing the NAF or SBM with the control sediment can be accomplished by following these steps:

- Place appropriate amounts of weighed NAF or SBM into a stainless steel mixing bowl;
- Tare the mixing bowl weight;
- Add appropriate amount of control sediment;
- Mix for 9 to15 minutes with a hand-held mixer equipped with stainless steel blades (e.g., KitchenAid Model KHM6), and;
- As appropriate, test mixing homogeneity as described below.

The control sediment alone should also be subjected to the mixing procedure to ensure mixing has no effect on sediment toxicity.

Homogeneity of Mixing

As noted above, tests for homogeneity of mixing should be performed, preferably in the procedure development phase (40 CFR part 9 page 6901-6902) by each laboratory performing NAF/SBM toxicity testing. This is to ensure that the NAF or SBM, which can be difficult to homogenize with control sediments, can be evenly mixed with the control sediment by each testing laboratory. Appendix 3 to Subpart A of Part 435 specifies that the coefficient of variation (CV) for a minimum of three replicate samples of the NAF/control sediment mixture must be less than 20%. Determinations of CV should be based on total petroleum hydrocarbon (TPH) content of the NAF or SBM as measured by EPA Methods 3550A and 8015M. . If the initial CV is >20%, then the NAF/SBM-sediment mixture must be re-mixed and reanalyzed until the ≤20% CV limit is achieved.

Homogeneity measurements should be made on the lowest and highest NAF concentrations for a given test. Laboratories should validate mixing efficiency via TPH measurements (as outlined above) of the low and high NAF concentrations. The homogeneity measurements should be made at least once per year.

Recommended Test Conditions

The recommended test conditions for conducting the 10-day or 96-hr sediment toxicity test with *L. plumulosus* are summarized in Table E-1 and are consistent with methods presented in ASTM E 1367-92

and subsequent updates (E 1367-99). Tests should be conducted at 20±1°C at 20±1‰ salinity with a 14h light; 10 h dark photoperiod at approximately 500-1,000 lux (or about 46 to 93 footcandles). Test chambers are 1-L glass containers with about a 10 cm inside diameter opening (or similar glass containers) that can contain about 150 ml sediment and 600 ml overlying water to achieve a 4:1 (v/v) water to sediment ratio. There are five (5) test concentrations plus a control for each NAF and SBM test. Five (5) replicates are included for the control sediment (E 1367-99) and for each test concentration.

The control sediment/test material mixture and test water should be added to test chambers the day before amphipods are added. This will allow for suspended particles to settle and allow time for equilibration of temperature and the sediment-water interface. After the overnight equilibration period, amphipods are randomly distributed to each test chamber. Twenty amphipods are added to each replicate and there are five replicates per test treatment. Amphipods caught on the water surface can be pushed under with a glass rod. Individuals that have not burrowed within 5 to 10 minutes can be replaced, unless they are exhibiting an avoidance response. Amphipods are not removed at any time during the course of the toxicity test even if they appear dead. Test water is not renewed (i.e., static) and the amphipods are not fed during the exposure period. The toxicity test is terminated after 96 hours or 10 days for SBMs and NAFs respectively.

Temperature, salinity, pH, and dissolved oxygen (DO) should be monitored daily. Ammonia should also be monitored in overlying water to ensure that the concentrations of this constituent do not exceed the tolerance range of the test species. For *L. plumulosus*, this is about 60 mg/L (as total ammonia) at pH 7.7 in 10-day tests (USEPA 1994). Ammonia has not been a problem in initial *L. plumulosus* 96-hr and 10-day tests with various NAFs.

Biological Data

Mortality is the endpoint for *L. plumulosus* at the end of the exposure period. At test termination, the contents of each test chamber (amphipods plus test sediment) are sieved through a 500 um mesh screen to remove amphipods. Material retained on the screen should be rinsed into a sorting tray with clean salt water. The total numbers of live and dead amphipods should be recorded. Missing animals are presumed to have died and decomposed during the test and disintegrated. Amphipods should be counted alive if

there are any signs of movement, such as a neuromuscular pleopod twitch (ASTM E 1367-99). Gentle prodding may be used to elicit movement.

Test Acceptability Requirements

Table E-2 provides the acceptability requirements for the 10-day NAF and 96-hr SBM test per ASTM E 1367-92. The primary acceptability requirement for NAF testing is as follows:

- A toxicity test is unacceptable if more than a total of 10% of the control organisms die, or if the coefficient of variation (CV) of control survival is equal to or greater than 40%.

If this acceptability requirement is not met, then the data should be discarded and the experiment repeated. If this requirement is met, then the other acceptability requirements in TableE-2 should be reviewed and a determination made as to the acceptability of the data.

Reference Tests

A single toxicity test will be used to determine satisfactory laboratory performance and to determine whether an NAF or SBM can be discharged as it adheres to drill cuttings. The reference toxicants for the NAF test will be either a C_{16}-C_{18} -internal olefin reference standard or a C_{12}-C_{14} or C_8 ester. The reference toxicant for the SBM testing program will be a C_{16}-C_{18} internal olefin SBM which has also been specified for determining pass/fail for SBMs. The C_{16}-C_{18} Internal Olefin (IO) SBM is a 65/35 blend, proportioned by mass, of hexadecene and octadecene, respectively (40 CFR part 9 6849). These reference toxicity tests will be conducted in conjunction with all NAF or SBM tests to discern possible changes in the condition of the *L. plumulosus* population used in testing. The reference toxicant test must be conducted concurrently with each sample or batch of samples and at a minimum should be conducted at least monthly. Control charts of this reference standard should be maintained to perform statistical analyses, help understand the inherent variability in the reference test, and for long-term quality control. Test conditions for the reference test should follow the experimental conditions presented in Table E-1.

The reference toxicant test should be performed concurrently-and under the same conditions as the NAF or SBM test. The reference toxicant test should be conducted so that control limits (typically set at □2 standard deviations) can be established (USEPA 1994). If the reference test LC_{50} falls outside of this range of control limits generated on the most recent test data points, then the sensitivity of *L. plumulosus* and the credibility of the test results are considered suspect. In this case, the test procedure should be examined and the test repeated with a different batch of amphipods. A sediment test should not automatically be judged unacceptable if the reference test LC_{50} falls outside the expected range or if the control in the reference toxicity test exceeds 10%. The width of the control limits and all performance criteria listed in Table E-2 should be considered when determining the acceptability of a given NAF or SBM test.

Interpretation of Results

Procedures presented in this test method are used to calculate point estimates, or LC_{50} values. The LC_{50} value and 95% confidence limits of the NAF tests should be calculated on the basis of milligrams of NAF per kg dry control sediment (mg/kg) and amphipod mortality. The LC_{50} value and 95% confidence limits

of the NAF tests should be calculated on the basis of milliliters of NAF per kg dry control sediment (ml/kg) and amphipod mortality. A variety of methods can be used to calculate an LC_{50} value and its 95% confidence limits, including probit, moving average, trimmed Spearman-Karber and Litchfield-Wilcoxon methods (ASTM E 1367-99). The method used should take into account the number of partial kills, the number of test chambers per treatment (5), and the number of amphipods per test chamber (20).

The only NAF that will be allowed for use in drilling fluids that are discharge in association with cuttings are those that are as toxic or less toxic, but not more toxic, than the reference NAF (C_{16}-C_{18} internal olefin or C_{12}-C_{14} or C_8 ester).

The only SBMs that will be allowed for discharge are those that are as toxic or less toxic, but not more toxic, than the C_{16}-C_{18} internal olefin reference SBM.

These limitations are expressed as follows:

$$\frac{\text{96 hr. } LC_{50} \text{ RDF}}{\text{96 hr. } LC_{50} \text{ SBM}} \leq 1.00 \qquad \frac{\text{10 day } LC_{50} \text{ Reference Material}}{\text{10 day } LC_{50} \text{ NAF}} \leq 1.00$$

Where RDF = Reference Drilling Fluid

The EPA promulgated a sediment toxicity ratio of less than 1.0, indicating that the NAF or SBM can be equally toxic or less toxic, but not more toxic than the reference toxicant test LC_{50} values for *L. plumulosus*. Hence, the NAF or SBM data should be interpreted by comparing to the reference toxicant test LC_{50} value and whether it exceeds this value.

Culture Methods

Populations of *L. plumulosus* can be maintained through several generations in the laboratory. The culture conditions specified in ASTM E1367-92 and E1367-99 are provided in Table E-3. Besides the conditions specified, there are other conditions that are important in maintaining healthy *L. plumulosus* cultures, including identifying a source of clean sediment, sieving sediments before use, and the quality of the raw materials used to prepare their food. Preferably, the sediment and water used to culture the amphipods should be collected from the same area as those used in NAF tests. Fine-grained sediments have been shown to be suitable for this purpose (E1367-92). Sediments collected in the field for culturing purposes should be first sieved through a 2,000 μ m mesh sieve to remove large debris and then through a 500 μ m mesh sieve to remove any indigenous organisms. *L. plumulosus* cultures should be maintained at 20±1°C and 20±1‰ salinity. If used, natural seawater should be filtered through a 5 micron filter before adding to cultures. New culture chambers should be aerated and allowed to equilibrate overnight before adding amphipods. Water used to start a new culture chamber should be renewed 24 h after initiation and before

amphipods are added to culture chambers; otherwise, culture water should be renewed in conjunction with feeding.

Cultures should be observed daily to ensure sufficient aeration. An abundance of amphipods on the sediment surface during daylight hours may indicate insufficient dissolved oxygen or overcrowding, as amphipods typically remain in their burrows unless they are searching for food or a mate. Culture chambers should be terminated and restarted with fresh sediment about once every 8 weeks to avoid overcrowding. Overcrowding may lead to stress due to food or space limitations, and may also result in reduced female fecundity, thus reducing the relative health of the population of amphipods in a given culture chamber.

Cultures should be routinely inspected for the presence of indigenous worms and copepods, a microbial build-up, or black and sulfurous conditions beneath the sediment surface. Microbial growth appears as a white or gray growth associated with uneaten food, and is indicative of overfeeding. Presence of indigenous species, excess microbial growth, or black and sulfurous conditions may necessitate discarding the affected culture chamber.

Feeding

A mixture of micro-algae, yeast, fish food flakes, alfalfa powder, ground cereal leaves, and shrimp maturation feed has been used to feed cultures (E 1367-92 and E 1367-99). Micro-algae used in culturing include *Pseudoisochrysis paradoxa*, *Phaeodactylum tricornutum*, and *Tetraselmis suecica* mixed in equal parts on a volume basis. These algae provide a source of fatty acids that may otherwise be absent in the diet. In practice, however, it should be noted that *L. plumulosus* has been cultured successfully without the algal mixture and the yeast. The dry food portion of the diet that has been used to successfully culture *L. plumulosus* is shown below.

Dietary Component	Proportion
Fish food flakes (TetraMin®)	48.0%
Alfalfa powder	24%
Ground cereal leaves (dried wheat leaves)	24%
Shrimp maturation feed (Neo-Novum®)	4.0%

This dry food mixture should be homogenized into a fine powder and fed to each culture chamber at a rate of 0.1 to 0.5 g two to three times per week, depending on culture densities. Overfeeding may result in microbial build-up on the sediment surface. The quality of the alfalfa powder and dried wheat leaves may

not be consistent among suppliers, thus potentially adversely affecting culture performance. Feeding should occur immediately after culture water changes.

Obtaining Amphipods for Starting a Test

Immature and adult amphipods of mixed sexes and approximately 3 to 5 mm in length (as measured from the base of the first antenna to the end of the third pleon segment along the dorsal surface) are used in toxicity tests, as they are easier to handle and count than younger individuals. Gravid females are not used in testing. The 3 to 5 mm size class individuals are passed through a 1,000 μ m mesh sieve and are retained on a 710 μ m mesh sieve. A 500 μ m mesh sieve has been used previously to retain amphipods of the size needed, but this results in a wider size range of amphipods used for testing. In preliminary NAF experiments, this wide size range may have contributed to variability in mortality observed that was not present when the 710 μ m mesh sieve was used to retain amphipods in later experiments. The amphipods passing through a 1000 μ m mesh sieve but trapped on a 710 μm mesh sieve provide a more uniform size range of animals that is thought to decrease the previously-observed variability in mortality. Laboratories are encouraged to use this type of approach to reduce the variability in the size of amphipods used in the NAF/SBM testing program.

Table E- 1: Conditions[1] for conducting 96 hour NAF and 10-day SBM sediment toxicity test with *L plumulosus*

Parameter	Conditions
Test type	Static whole sediment toxicity test
Temperature	20±1°C
Salinity	20±1‰
Light quality	Wide-spectrum fluorescent lights
Illuminance	500-1,000 lux
Photoperiod	14h light:10h dark[2]
Test chamber	1-L glass beaker or jar
Sediment volume	150 ml (2 cm depth)
Overlying water volume	600 ml (4:1 [v/v] water to sediment ratio)
Renewal of overlying water	None
Size and life stage of amphipods	3-5 mm; immature and adult
Number of organisms/chamber	20
Number of test concentrations	5
Number of replicate chambers/treatment	5 in both controls and test treatments
Feeding	None
Aeration	Water in each test chamber should be aerated throughout the test.
Overlying Water	Clean natural or synthetic seawater
Overlying water quality	Temperature, salinity, pH, and D.O. daily; ammonia, as needed
Test duration	96 hours
Endpoint	Survival
Test acceptability	Minimum mean control survival of 90% and satisfaction of criteria outlined in Table E-2
Dietary Component	Proportion
Fish food flakes (TetraMin®)	48.0%
Alfalfa powder	24%
Ground cereal leaves (dried wheat leaves)	24%
Shrimp maturation feed (Neo-Novum®)	4.0%

Footnotes:

1. Conditions listed are consistent with test conditions specified in ASTM E 1367-92 and subsequent updates (E 1367-99) unless otherwise noted
2. Although ASTM E1367 specifies 16h light:8h dark, the photoperiod was changed to 14h light:10h dark to be consistent with the *Mysidopsis bahia* bioassay for drilling fluids

(58 CFR 12453, 1993).

Table E- 2: Test acceptability requirements[1] for 10-day NAF and 96 hour SBM test with *L plumulosus*

- A 10-day NAF and 96-hr SBM toxicity tests are unacceptable if more than a total of 10% of the control organisms die, or if the coefficient of variation (CV) of control survival is equal to or greater than 40%.
- Ten-day NAF and 96-hr SBM toxicity tests should usually be considered unacceptable if one or more of the following occurred:
- All test chambers were not identical.
- Test organisms were not randomly or impartially distributed to test chambers.
- Required reference standard was not included in the test.
- All test animals were not from the same population, were not all of the same species, or were not of acceptable quality.
- Amphipods from a wild population were maintained in the laboratory for more than two weeks, unless the effects of prolonged maintenance in the laboratory has been shown to have no significant effect on sensitivity.
- The test organisms were not acclimated at the test temperature and salinity at least 48 hours before they were placed in the test chambers.
- Temperature and dissolved oxygen concentrations were not measured.

Footnotes:

1. Requirements listed are consistent with those specified in ASTM E 1367-92 and subsequent updates (E 1367-99). However, these guidelines are not identical to those listed ASTM E 1367 in part because some acceptability guidelines listed in E1367-92 are not applicable or practical for the NAF/SBM toxicity testing program

Table E- 3: Culture conditions for L plumulosus

Parameter	Conditions
Temperature	20±1°C
Salinity	20±1‰
Light quality	Wide-spectrum fluorescent or cool white lights
Illuminance	500-1,000 lux
Photoperiod	14h light:10h dark
Culture chamber	Shallow plastic tubs or glass aquaria
Sediment volume	1-2 cm depth at bottom of each culture chamber
Renewal of overlying water	Static renewal (30-50% water volume change 2-4 times per week)
Number of organisms/chamber	Start with about 300 mixed age (mostly immature and young adults) individuals per chamber
Feeding	0.1 to 0.5 g dry mixture 2-3 times per week (see text)
Aeration	Continuous gentle to moderate aeration so as to not suspend sediments
Overlying Water	Clean natural or synthetic seawater
Overlying water quality	Salinity, temperature, and ammonia during culture start-up

Footnotes:

1. Conditions listed are consistent with culture conditions specified in ASTM E 1367-92 and subsequent updates (E 1367-99).

References

American Society for Testing and Materials (ASTM). 1997. Standard Guide for Conducting 10-day Static Sediment Toxicity Tests with Marine and Estuarine Amphipods. E 1367-92. Annual Book of ASTM Standards, Vol. 11.05.

American Society for Testing and Materials (ASTM). 2000. Standard Guide for Conducting 10-day Static Sediment Toxicity Tests with Marine and Estuarine Amphipods. E 1367-99. Annual Book of ASTM Standards, Vol. 11.05.

Emery, V.L., D.W. Moore, B.R. Gray, B.M. Duke, A.B. Gibson, R.B. Wright and J.D. Farrar. 1997. Development of a chronic sublethal sediment bioassay using the estuarine amphipod *Leptocheirus plumulosus* (Shoemaker). Environ. Toxicol. Chem. 16:1912-1920.

McGee, B.L. D.J. Fisher, L.T. Yonkos, G.P. Ziegler and S. Turley. 1999. Assessment of sediment contamination, acute toxicity, and population viability of the estuarine amphipod *Leptocheirus plumulosus* in Baltimore Harbor, Maryland, USA. Environ. Toxicol. Chem. 18:2151-2160.

Schlekat, C.E., B.L. McGee and E. Reinharz. 1992. Testing sediment toxicity in Chesapeake Bay with the amphipod *Leptocheirus plumulosus*: an evaluation. Environ. Toxicol. Chem. 11:225-236.

Suedel, B.C. and J.H. Rodgers, Jr. 1991. Variability of bottom sediment characteristics of the continental United States. Water Res. Bull. 27:101-109.

USEPA. 1994. Methods for Assessing the Toxicity of Sediment-associated Contaminants with Estuarine and Marine Amphipods. EPA/600/R-94/025. USEPA Office of Research and Development, June 1994.

USEPA. 2000. Final Effluent Limitations Guidelines and Standards for Synthetic-Based Drilling Fluids Fact Sheet. EPA-821-F-00-014. USEPA Office of Water, December 2000. (www.epa.gov/ost/guide/sbf/final/finalfact.html

APPENDIX F **PROTOCOL FOR THE DETERMINATION OF DEGRADATION OF NON-AQUEOUS BASED FLUIDS IN A MARINE CLOSED BOTTLE BIODEGRADATION TEST SYSTEM: MODIFIED ISO 11734**

Appendix F

Protocol for the Determination of Degradation of Non-aqueous Based Fluids in a Marine Closed Bottle Biodegradation Test System: Modified ISO 11734

Section 1: Summary of Method

This method determines the anaerobic degradation potential of mineral oils, paraffin oils and non-aqueous fluids (NAF)in sediments. These substrates are base fluids for formulating offshore drilling fluids. The test evaluates base fluid biodegradation rates by monitoring gas production due to microbial degradation of the test fluid in natural marine sediment.

The test procedure places a mixture of marine/estuarine sediment, test substrate (hydrocarbon or controls) and seawater into clean 120 ml (150 ml actual volume) Wheaton serum bottles. The test is run using four replicate serum bottles containing 2000 mg carbon/kg dry weight concentration of test substrate in sediment. The use of resazurin dye solution (1 ppm) evaluates the anaerobic (redox) condition of the bottles (dye is blue when oxygen is present, reddish in low oxygen conditions and colorless if oxygen free). After capping the bottles, a nitrogen sparge removes air in the headspace before incubation begins. During the incubation period, the sample should be kept at a constant temperature of 29 (+/-1)ºC. Gas production and composition is measured approximately every two weeks. The samples need to be brought to ambient temperature before making the measurements. Measure gas production using a pressure gauge. Barometric pressure is measured at the time of testing to make necessary volume adjustments.

ISO 11734 specifies that total gas is the standard measure of biodegradation. While modifying this test for evaluating biodegradation of NAF's, methane was also monitored and found to be an acceptable method of evaluating biodegradation Appendix 1 contains the procedures used to follow biodegradation by methane production. Measurement of either total gas or methane production is permitted. If methane is followed, determine the composition of the gas by using gas chromatography (GC) analysis at each sampling. At the end of the test when gas production stops, or at around 275 days, an analysis of sediment for substrate content is possible. Common methods which have been successfully used for analyzing NAF's from sediments are listed in Appendix 2.

Section 2: System Requirements

This environmental test system has three phases, spiked sediment, overlying seawater, and a gas headspace. The sediment/test compound mixture is combined with synthetic sea water and transferred into 120 mL serum bottles. The total volume of sediment/sea water mixture in the bottles is 75 mL. The volume of the sediment layer will be approximately 50 mL, but the exact volume of the sediment will depend on sediment characteristics (wet:dry ratio and density). The amount of synthetic sea water will be calculated to bring the total volume in the bottles to 75 mL. The test systems are maintained at a temperature of 29□1ºC during incubation. The test systems are brought to ambient temperatures prior to measuring pressure or gas volume.

Section 2.1: Sample Requirements

The concentration of base fluids are at least 2000 mg carbon test material/kg dry sediment. Carbon concentration is determined by theoretical composition based on the chemical formula or by chemical analysis by ASTM D5291-96. Sediments with positive, intermediate and negative control substances as well as a C1618 Internal Olefin type base fluid will be run in conjunction with test materials under the same conditions. The positive control is ethyl oleate (CAS 111-62-6), the intermediate control is 1-

hexadecene (CAS 629-73-2), and the negative control is squalane (CAS 111-01-3). Controls must be of analytical grade or the highest grade available. Each test control concentration should be prepared according to the mixing procedure described in Section 3.1.

Product names will be used for examples or clarification in the following text. Any use of trade or product names in this publication is for descriptive use only, and dos not constitute endorsement by EPA or the authors.

Section 2.2: Seawater Requirements

Synthetic seawater at a salinity of 25±1 ppt should be used for the test. The synthetic seawater should be prepared by mixing a commercially available artificial seawater mix, into high purity distilled or de-ionized water. The seawater should be aerated and allowed to age for approximately one month prior to use.

Section 2.3: Sediment Requirements

The dilution sediment must be from a natural estuarine or marine environment and be free of the compounds of interest. The collection location, date and time will be documented and reported. The sediment is prepared by press-sieving through a 2000-micron mesh sieve to remove large debris, then press-sieving through a 500-micron sieve to remove indigenous organisms that may confound test results. The water content of the sediment should be less than 60%(w/w) or a wet to dry ratio of 2.5. The sediment should have a minimum organic matter content of 3% (w/w) as determined by ASTM D2974-87 (95) (Method A and D and calculate organic matter as in section 12 of method ASTM D2974-87).

To reduce the osmotic shock to the microorganisms in the sediment the salinity of the sediment's pore water should be between 20-30 ppt. Sediment should be used for testing as soon as possible after field collection. If required, sediment can be stored in the dark at 4°C with 3-6 inches of overlying water in a sealed container for a maximum period of 2 months prior to use.

Section 3: Test Set up

The test is set up by first mixing the test or control substrates into the sediment inoculum, then mixing in seawater to make a pourable slurry. The slurry is then poured into serum bottles, which are then flushed with nitrogen and sealed.

Section 3.1: Mixing Procedure

Because base fluids are strongly hydrophobic and do not readily mix with sediments, care must be taken to ensure base fluids are thoroughly homogenized within the sediment. All concentrations are weight-to-weight comparisons (mg of base fluid to kg of dry control sediment). Sediment and base fluid mixing will be accomplished by using the following method.

3.1.1. Determine the wet to dry weight ratio for the control sediment by weighing approximately 10 sub-samples of approximately 1 g each of the screened and homogenized wet sediment into tared aluminum weigh pans. Dry sediment at 105□C for 18-24 h. Remove the dried sediments and cool in a desiccator. Repeat the drying, cooling, and weighing cycle until a constant weight is achieved (within 4% of previous weight). Re-weigh the samples to determine the dry weight.

Calculate the mean wet and dry weights of the 10 sub samples and determine the wet/dry ratio by dividing the mean wet weight by the mean dry weight using Formula 1. This is required to determine the weight of wet sediment needed to prepare the test samples.

$$\frac{\text{Mean Wet Sediment Weight (g)}}{\text{Mean Dry Sediment Weight (g)}} = \text{Wet to Dry Ratio} \qquad [1]$$

3.1.2. Determine the density (g/ml) of the wet sediment. This will be used to determine total volume of wet sediment needed for the various test treatments. One method is to tare a 5 ml graduated cylinder and add about 5 ml of homogenized sediment. Carefully record the volume then weigh this volume of sediment. Repeat this a total of three times. To determine the wet sediment density, divide the weight by volume per the following formula:

$$\frac{\text{Mean Wet Sediment Weight (g)}}{\text{Mean Dry Sediment Volume (ml)}} = \text{Wet Sediment Density (g/ml)} \qquad [2]$$

3.1.3. Determine the amount of base fluid to be spiked into wet sediment in order to obtain the desired initial base fluid concentration of 2000 mg carbon/kg dry weight. An amount of wet sediment that is the equivalent of 30 g of dry sediment will be added to each bottle. A typical procedure is to prepare enough sediment for 8 serum bottles (3 bottles to be sacrificed at the start of the test, 4 bottles incubated for headspace analysis, and enough extra sediment for 2 extra bottles). Extra sediment is needed because some of the sediment will remain coated onto the mixing bowl and utensils. Experience with this test may indicate that preparing larger volumes of spiked sediment is a useful practice, then the following calculations should be adjusted accordingly.

3.1.3.1 Determine the total weight of dry sediment needed to add 30 g dry sediment to 8 bottles. If more bottles are used then the calculations should be modified accordingly. For example:

$$\text{30 g dry sediment per bottle} \times 8 = \text{240 g dry sediment} \qquad [3]$$

3.1.3.2 Determine the weight of base fluid, in terms of carbon, needed to obtain a final base fluid concentration of 2000 mg carbon/kg dry weight. For example:

$$\frac{\text{2000 mg carbon}}{\text{per kg dry sediment}} \times \frac{\text{240 g}}{1000} = \text{480 mg carbon} \qquad [4]$$

3.1.3.3 Convert from mg of carbon to mg of base fluid.

This calculation will depend on the % fraction of carbon present in the molecular structure of each base fluid. For the control fluids, ethyl oleate is composed of 77.3% carbon, hexadecene is composed of 85.7% carbon, and squalane is composed of 85.3% carbon. The carbon fraction

of each base fluid should be supplied by the manufacturer or determined before use. ASTM D5291-96 or equivalent will used to determine composition of fluid.

To calculate the amount of base fluid to add to the sediment, divide the amount of carbon (480 mg) by the percent fraction of carbon in the fluid.

For example, the amount of ethyl oleate added to 240 g dry weight sediment can be calculated from the following equation:

480 mg carbon ÷ (77.3/100) = 621 mg ethyl oleate [5]

Therefore, add 621 mg of ethyl oleate to 240 g dry weight sediment for a final concentration of 2000 mg carbon/kg sediment dry weight.

3.1.4. Mix the calculated amount of base fluid with the appropriate weight of wet sediment.

3.1.4.1 Use the wet:dry ratio to convert from g sediment dry weight to g sediment wet weight, as follows:

240 g dry sediment x wet:dry ratio = g wet sediment needed [6]

3.1.4.2 Weigh the appropriate amount of base fluid (calculated in section 3.1.3.3) into stainless mixing bowls, tare the vessel weight, then add the wet sediment calculated in equation 5, and mix with a high shear dispersing impeller for 9 minutes.

The sediment is now mixed with synthetic sea water to form a slurry that will be transferred into the bottles.

Section 3.2: Creating Seawater/Sediment Slurry

Given that the total volume of sediment/sea water slurry in each bottle is to be 75 mL, determine the volume of sea water to add to the wet sediment.

3.2.1 If each bottle is to contain 30 g dry sediment, calculate the weight, and then the volume, of wet sediment to be added to each bottle

30 g dry sediment X wet:dry ratio = g wet sediment added to each bottle [7]

g wet sediment ÷ density (g/mL) of wet sediment = mL wet sediment [8]

3.2.2 Calculate volume of sea water to be added to each bottle

75 mL total volume - mL wet sediment ([8]) = mL of sea water [9]

3.2.3 Determine the ratio of sea water to wet sediment (volume:volume) in each bottle

$$\frac{\text{volume sea water per bottle ([9])}}{\text{volume sediment per bottle ([8])}} = \text{ratio of sea water:wet sediment} \qquad [10]$$

3.2.4 Convert the wet sediment weight from equation 6 into a volume using the sediment density.

g wet sediment ([6]) ÷ density = volume (mL) of sediment [11]

3.2.5 Determine the amount of sea water to mix with the wet sediment.

mL wet sediment([11]) x sea water:sediment ratio ([10])

= mL sea water to add to wet sediment [12]

Mix sea water thoroughly with wet sediment to form a sediment/sea water slurry.

Section 3.3: Bottling the Sediment Seawater Slurry

The total volume of sediment/sea water slurry in each bottle is to be 75 mL. Convert the volume (mL) of sediment/sea water slurry into a weight (g) using the density of the sediment and the sea water.

3.3.1 Determine the weight of sediment to be added to each bottle

mL sediment ([8]) x density of wet sediment (g/mL) = g wet sediment [14]

3.3.2 Determine the weight of sea water to be added to each bottle

mL sea water ([9[) x density of sea water (1.01 g/mL) = g sea water [15]

3.3.3 Determine weight of sediment/sea water slurry to be added to each bottle

g wet sediment ([14]) + g sea water ([15]) = g sediment/sea water slurry [16]

This should provide each bottle with 30 g dry sediment in a total volume of 75 mL.

3.3.4 Putting the sediment:seawater slurry in the serum bottles.

Note: The slurry will need to be constantly stirred to keep the sediment suspended.

Place a tared serum bottle on a balance and add the appropriate amount of slurry to the bottle using a funnel. Once the required slurry is in the bottle remove the funnel, add 2-3 drops (25 µl) of a 1gram/L resazurin dye stock solution. Cap the bottle with a butyl rubber stopper (Bellco Glass, Part #2048- 11800)and crimp with an aluminum seal (Bellco Glass Part #2048-11020).

Using a plastic tube with a (23 gauge, 1 inch long) needle attached to one side and a nitrogen source to the other, puncture the serum cap with the needle. Puncture the serum cap again with a second needle to sparge the bottle's headspace of residual air for two minutes. The nitrogen should be flowing at no more than 100 mL/min to encourage gentle displacement of oxygenated air with nitrogen. Faster nitrogen flow rates would cause mixing and complete oxygen removal would take much longer. Remove the nitrogen needle first to avoid any initial pressure problems. The second (vent) needle should be removed within 30 seconds of removing the nitrogen needle.

Triplicate blank test systems are prepared, with similar quantities of sediment and seawater without any base fluid. Incubate in the dark at a constant temperature of 29±1° C.

Record the test temperature. The test duration is dependent on base fluid performance, but at a maximum should be no more than 275 days. Stop the test after all base fluids have achieved a

plateau of gas production. At termination, base fluid concentrations can be verified in the terminated samples by extraction and GC analysis according to Appendix 2.

Section 4: Concentration Verification Chemical Analyses

Because of the difficulty of homogeneously mixing base fluid with sediment, it is important to demonstrate that the base fluid is evenly mixed within the sediment sea water slurry that was added to each bottle. Of the seven serum bottles set up for each test or control condition, three are randomly selected for concentration verification analyses. These should be immediately placed at 4□C and a sample of sediment from each bottle should be analyzed for base fluid content as soon as possible. The coefficient of variation (CV) for the replicate samples must be less than 20%. The results should show recovery of at least 70% of the spiked base fluid. Use an appropriate analytical procedure described in Appendix 2 to perform the extractions and analyses. If any set of sediments fail the criteria for concentration verification, then the corrective action for that set of sediments is also outlined in Appendix 2.

The nominal concentrations and the measured concentrations from the three bottles selected for concentration verification should be reported for the initial test concentrations. The coefficient of variation (CV) for the replicate samples must be less than 20%. If base fluid content results are not within the 20% CV limit, the test must be stopped and restarted with adequately mixed sediment.

Section 5 Gas monitoring procedures

Biodegradation is measured by total gas as specified in ISO 11734. Methane production can also be tracked and is described in Appendix 1.

Section 5.1 Total Gas monitoring procedures

Bottles should be brought to room temperature before readings are taken. The bottles are observed to confirm that the resazurin has not oxidized to pink or blue. Total gas production in the culture bottles should be measured using a pressure transducer (one source is Biotech International). The pressure readings from test and control cultures are evaluated against a calibration curve created by analyzing the pressure created by known additions of gas to bottles established identically to the culture bottles. Bottles used for the standard curve contain 75 mL of water, and are sealed with the same rubber septa and crimp cap seals used for the bottles containing sediment. After the bottles used in the standard curve have been sealed, a syringe needle inserted through the septa is used to equilibrate the pressure inside the bottles to the outside atmosphere. The syringe needle is removed and known volumes of air are injected into the headspace of the bottles. Pressure readings provide a standard curve relating the volume of gas injected into the bottles and headspace pressure. No less than three points may be used to generate the standard curve. A typical standard curve may use 0, 1, 5, 10, 20 and 40 ml of gas added to the standard curve bottles.

The room temperature and barometric pressure (to two digits) should be recorded at the time of sampling. One option for the barometer is Fisher Part #02-400 or 02-401. Gas production by the sediment is

expressed in terms of the volume (mL) of gas at standard temperature ($0^oC = 273^oK$) and pressure (1 atm = 30 inches of Hg) using Eqn.17.

$$V_2 = \frac{P_1 \text{ X } V_1 \text{ X } T_2}{T_1 \text{ X } P_2} \qquad [17]$$

Where: V_2 = volume of gas production at standard temperature and pressure

P_1 = barometric pressure on day of sampling (inches of Hg)

V_1 = volume of gas measured on day of sampling (mL)

T_2 = standard temperature = 273^oK

T_1 = temperature on day of sampling ($^oC + 273 = {}^oK$)

P_2 = standard pressure = 30 inches Hg

An estimation can be made of the total volume of anaerobic gas that will be produced in the bottles. The gas production measured for each base fluid can be expressed as a percent of predicted total anaerobic gas production.

5.1.1. Calculate the total amount of carbon in the form of the base fluid present in each bottle

Each bottle is to contain 30 g dry weight sediment. The base fluid concentration is 2000 mg carbon/kg dry weight sediment. Therefore:

2000 mg carbon/kg sediment x (30 g/1000) = 60 mg carbon per bottle [18]

5.1.2. Theory states that anaerobic microorganisms will convert 1 mole of carbon substrate into 1 mole of total anaerobic gas production

Calculate the number of moles of carbon in each bottle.

The molecular weight of carbon is 12 (i.e. 1 mole of carbon = 12 g). Therefore, the number of moles of carbon in each bottle can be calculated.

(60 mg carbon per bottle/1000) ÷ 12 g/mole = 0.005 moles carbon [19]

5.1.3. Calculate the predicted volume of anaerobic gas

One mole of gas equals 22.4 L (at standard temperature and pressure), therefore,

0.005 moles x 22.4 L = 0.112L (or 112 mL total gas production). [20]

Section 5.2 Gas Venting

If the pressure in the serum bottle is too great for the pressure transducer or syringe, some of the excess gas must be wasted. The best method to do this is to vent the excess gas right after measurement. To do this, remove the barrel from a 10-mL syringe and fill it 1/3 full with water. This is then inserted into the bottle through the stopper using a small diameter (high gauge) needle. The excess pressure is allowed to vent through the water until the bubbles stop. This allows equalization of the pressure inside the bottle to

atmospheric without introducing oxygen. The amount of gas vented (which is equal to the volume determined that day) must be kept track of each time the bottles are vented. A simple way to do this in a spreadsheet format is to have a separate column in which cumulative vented gas is tabulated. Each time the volume of gas in the cultures is analyzed, the total gas produced is equal to the gas in the culture at that time plus the total of the vented gas.

To keep track of the methane lost in the venting procedure, multiply the amount of gas vented each time by the corrected % methane determined on that day. The answer gives the volume of methane wasted. This must be added into the cumulative totals similarly to the total gas additions.

Section 6: Test Acceptability and Interpretation

Section 6.1 Test acceptability

At day 275 or when gas production has plateaued, whichever is first, the controls are evaluated to confirm that the test has been performed appropriately. In order for this modification of the closed bottle biodegradation test to be considered acceptable, all the controls must meet the biodegradation levels indicated in Table F-1. The intermediate control hexadecene must produce at least 30% of the theoretical gas production. This level may be reexamined after two years and more data has been generated.

Table F- 1: Test Acceptability Criteria

Concentration	Percent Biodegradability as a Function of Gas Measurement		
	Positive control	Squalane negative control	Hexadecene intermediate control
2000 mg carbon/kg	$\geq$ 60% theoretical	$\leq$ 5% theoretical	$\geq$ 30% theoretical

Section 6.2 Interpretation

In order for a fluid to pass the closed bottle test, the biodegradation of the base fluid as indicated by the total amount of total gas (or methane) generated once gas production has plateaued (or at the end of 275

days, which ever is first) must be greater than or equal to the volume of gas (or methane) produced by the reference standard (internal elefin or ester).

The method for evaluating the data to determine whether a fluid has passed the biodegradation test must use the equations:

$$\frac{\text{\% Theoretical gas production of reference fluid}}{\text{\% Theoretical gas production of NAF}} \leq 1.0$$

Where: NAF = stock base fluid being tested for compliance

Reference Fluid = C_{16}-C_{18} internal olefin or C_{12}-C_{14} or C_8 ester reference fluid

Appendix F, Part I

Section A1 Methane monitoring procedures

The use of total gas production alone may result in an underestimation of the actual metabolism occurring since CO_2 is slightly soluble in water. An acceptable alternative method is to monitor methane production and total gas production. This is easily done using GC analysis. A direct injection of headspace gases can be made into a GC using almost any packed or capillary column with an FID detector. Unless volatile fuels or solvents are present in the test material or the inocula, the only component of the headspace gas that can be detected using an FID detector is methane. The percent methane in the headspace gas is determined by comparing the response of the sample injections to the response from injections of known percent methane standards. The percent methane is corrected for water vapor saturation using Eqn. 8 and then converted to a volume of dry methane using Eqn. 9.

$$\text{Corrected \% } CH_4 = \frac{\% \, CH_4}{1 - \dfrac{D \times 22.4 \text{ L/mol}}{18 \text{ g/mol} \times 1000}} \qquad [A1]$$

Where: D = the density of water vapor at saturation (g/m^3, can be found in CRC Handbook of Chemistry and Physics) for the temperature of sampling.

$$V_{CH4}\,(ml) = (S + V) \times \frac{(P - P_w)}{(T + 273)} \times \frac{CH_4}{100} \times \frac{273}{760} \qquad [A2]$$

where:

V_{CH4} (ml)	=	the volume of methane in the bottle
S	=	volume of excess gas production (measured with a pressure transducer)
V	=	volume of the headspace in the culture bottle (total volume - liquid phase)
P	=	barometric pressure (mm Hg, measured with barometer)
T	=	temperature (°C)
P_w	=	vapor pressure of water at T (mm Hg, can be found in CRC Handbook of Chemistry and Physics)
CH_4	=	% methane in headspace gas (after correction for water vapor)

The total volume of serum bottles sold as 125 mL bottles (Wheaton) is 154.8 mL.

The volumes of methane produced are then compared to the volumes of methane in the controls to determine if a significant inhibition of methane production or a significant increase of methane production has been observed. Effective statistical analyses are important, as variability in the results is common due to the heterogeneity of the inoculum's source. It is also common to observe that the timing of the initiation of culture

activity is not equal in all of the cultures. Expect a great variability over the period when the cultures are active, some replicates will start sooner than others, but all of the replicates should eventually reach similar levels of base fluid degradation and methane production.

Section A2 Expected Methane Production Calculations

The amount of methane expected can be calculated using the equation of Symons and Buswell (Eqn. A3). In the case of complete mineralization, all of the carbon will appear as wither CO_2 or CH_4, thus the total moles of gas produced will be equal to the total moles of carbon in the parent molecule. The use of the Buswell equation allows you to calculate the effects the redox potential will have on the distribution of the products in methanogenic cultures. More reduced electron donors will allow the production of more methane, while more oxidized electron donors will cause a production of more carbon dioxide.

$$\mathbf{C_nH_aO_bN_cS_d + (n-a/4 -b/2 + 7c/4 + d/2)\ H_2O \rightarrow (n/2 -a/8+b/4-5c/8 + d/4)\ CO_2 +} \quad [A3]$$

$$\mathbf{(n/2 +a/8 -b/4 -3c/8-d/4)\ CH_4 + cNH_4HCO_3 + dH_2S.}$$

An example calculation of the expected methane volume in a culture fed 2000 mg/kg hexadecene is as follows. The application of Symons and Buswell's equation reveals that hexadecene ($C_{16}H_{32}$) will yield 4 moles of CO_2 and 12 moles of CH_4. Assuming 30 g of dry sediment are added to the bottles with 2,334 mg hexadecene/kg dry sediment (i.e. equivalent to 2000 mg carbon/kg dry sediment) the calculation is as follows.

$$\frac{12 \text{ mole } CH_4}{\text{Mole hexadecene}} \times \frac{224 \text{ L}}{\text{mole } CH_4} \times \frac{1000 \text{ ml}}{\text{L}} \times \frac{1 \text{ mole hexadecene}}{2244 \text{ g hexadecene}}$$

$$\times \frac{2.3 \text{ g hexadecane}}{\text{kg dry soil}} \times \frac{0.03 \text{ kg}}{\text{Culture}} = 84 \text{ ml} \qquad [A4]$$

By subtracting the average amount of methane in control bottles from the test bottles and then dividing by the expected volume an evaluation of the completion of the process may be conducted.

Appendix F, Part II

The Concentration Verification analyses is required at the beginning of the test to ensure homogeneity and confirm that the required amount of fluid was delivered to the sediments at the start of the test

- Three samples per fluid need to be analyzed and achieve ≤20% Coefficient of Variability and an average of ≥70% to ≤120% of fluid delivered to sediment.
- If a third party performs the analysis, then the laboratory should be capable of delivering the homogeneity data within seven days, in order to identify any samples that do not meet the homogeneity requirement as quickly as possible.
- If one sediment/fluid set, out a multiple set batch of samples, fails these criteria, then that one set of samples must be discarded and a fresh set of spiked sediment prepared, started, and analyzed to ensure homogeneity. The same stock sediment is used to prepare the replacement set(s). The remaining sets do not need to be re-mixed or restarted.
- The re-mixed set(s) will need to be run the additional days as appropriate to ensure that the total number of days is the same for all sets of bottles, even though the specific days are not aligned.
- Re-mixing of bottle sets can be performed multiple times as a result of a failure of the analytical criteria, until the holding time for the stock sediment has expired (60 days). If the problem set(s) has not fallen within the acceptable analytical criteria by then, it must not be part of the batch of bottles run. If the problem batch is one of the controls, and those controls were not successfully prepared when the sediment holding time expired, then the entire test must be restarted.

References

The following references identify analytical methods that have historically been successful for achieving the analytical quality criteria:

Continental Shelf Associates report 1998. Joint EPA/Industry screening survey to assess the deposition of drill cuttings and associated synthetic based mud on the seabed of the Louisiana continental shelf, Gulf of Mexico. Analysis by Charlie Henry report Number IES/RCAT97-36 GC-FID and GC/MS

EPA Method 3550 for extraction with EPA Method 8015 for GC-FID

Webster, L; Mackie, P.R.; Hird, S.J.; Munro, P.D.; Brown, N.A. and Moffatt, C.F. (1997) Development of Analytical Methods for the Determination of Synthetic Mud Base Fluids in Marine Sediments *Analyst* 122:1485-1490.

Munro, P.D., B Croce, C.F. Moffet, N.A Brown, A.D. McIntosh, S.J.Hird, R.M. Stagg. 1998. Solid-phase test for comparison for degradation rates of synthetic mud base fluids used in the off shore drilling industry. *Environ. Toxicol. Chem.* 17:1951-1959.

Appendix F, Part III

PROGRAM QUALITY ASSURANCE AND QUALITY CONTROL:

Calibration

- All equipment / instrumentation will be calibrated in accordance with the test method or the manufacture's instructions and may be scheduled or triggered
- Where possible, standards used in calibration will be traceable to a nationally recognized standard (e.g., certified standard by NIST)
- All calibration activities will be documented and the records retained
- The source, lot, batch number, and expiration date of all reagents used with be documented and retained

Maintenance

- All equipment / instrumentation will be maintained in accordance with the test method or the manufacture's instructions and may be scheduled or triggered
- All maintenance activities will be documented and the records retained

Data Management and Handling

- All primary (raw) data will be correct, complete, without selective reporting, and will be maintained
- Hand-written data will be recorded in lab notebooks or electronically at the time of observation
- All hand-written records will be legible and amenable to reproduction by electrostatic copiers
- All changes to data or other records will be made by:
  - □ using a single line to mark-through the erroneous entry (maintaining original data legibility)
  - □ write the revision
  - □ initial, date, and provide revision code (see attached or laboratory's equivalent)
- All data entry, transcriptions, and calculations will be verified by a qualified person
  - □ verification will be documented by initials of verifier and date
- Procedures will be in place to address data management procedures used (at minimum):
  - □ Significant figures
  - □ Rounding practices
  - □ Identification of outliers in data series
  - □ Required statistics

Document Control

- All technical procedures, methods, work instructions, standard operating procedures must be documented and approved by laboratory management prior to the implementation

- All primary data will be maintained by the contractor for a minimum of five (5) years

Personnel and Training

- Only qualified personnel shall perform laboratory activities
- Records of staff training and experience will be available. This will include initial and refresher training (as appropriate)

Test Performance

- All testing will done in accordance with the specified test methods
- Receipt, arrival condition, storage conditions, dispersal, and accountability of the test article will be documented and maintained
- Receipt or production, arrival or initial condition, storage conditions, dispersal, and accountability of the test matrix (e.g., sediment or artificial seawater) will be documented and maintained
- Source, receipt, arrival condition, storage conditions, dispersal, and accountability of the test organisms (including inoculum) will be documented and maintained
- Actual concentrations administered at each treatment level will be verified by appropriate methodologies
- Any data originating at a different laboratory will be identified and the laboratory fully referenced in the final report.

APPENDIX G **DETERMINATION OF CRUDE OIL CONTAMINATION IN NON-AQUEOUS DRILLING FLUIDS BY GAS CHROMATOGRAPHY/MASS SPECTROMETRY (GC/MS)**

Appendix G

Determination of Crude Oil Contamination in Non-aqueous Drilling Fluids by Gas Chromatography/Mass Spectrometry (GC/MS)

1.0 Scope and Application

1.1 This method determines crude (formation) oil contamination, or other petroleum oil contamination, in non-aqueous drilling fluids (NAFs) by comparing the gas chromatography/mass spectrometry (GC/MS) fingerprint scan and extracted ion scans of the test sample to that of an uncontaminated sample.

1.2 This method can be used for monitoring oil contamination of NAFs or monitoring oil contamination of the base fluid used in the NAF formulations.

1.3 Any modification of this method beyond those expressly permitted shall be considered as a major modification subject to application and approval of alternative test procedures.

1.4 The gas chromatography/mass spectrometry portions of this method are restricted to use by, or under the supervision of analysts experienced in the use of GC/MS and in the interpretation of gas chromatograms and extracted ion scans. Each laboratory that uses this method must generate acceptable results using the procedures described in Sections 9.2, 10.1, and 13 of this method.

2.0 Summary of Method

2.1 Analysis of NAF for crude oil contamination is a step-wise process. Qualitative assessment of the presence or absence of crude oil is performed first. If crude oil is detected in this qualitative assessment, quantitative analysis of the crude oil concentration is performed. When more data are available, the NIST calibration may need to be adjusted.

2.2 A sample of NAF is centrifuged, to obtain a solids free supernate.

2.3 The sample to be tested is prepared by removing an aliquot of the solids free supernate, spiking it with internal standard, and analyzing it using GC/MS techniques. The components are separated by the gas chromatograph and detected by the mass spectrometer.

2.4 Qualitative identification of crude oil contamination is performed by comparing the Total Ion Chromatograph (TIC) scans and Extracted Ion Profile (EIP) scans of test sample to that of uncontaminated base fluids, and examining the profiles for chromatographic signatures diagnostic of oil contamination.

2.5 The presence or absence of crude oil contamination observed in the full scan profiles and selected extracted ion profiles determines further sample quantitation and reporting.

2.6 If crude oil is detected in the qualitative analysis, quantitative analysis is performed by calibrating the GC/MS using a designated NAF spiked with known concentrations of a designated oil.

2.7 Quality is assured through reproducible calibration and testing of GC/MS system and through analysis of quality control samples.

3.0 Definitions

3.1 A NAF is one in which the continuous phase is a water immiscible fluid such as an oleaginous material (e.g., mineral oil, enhance mineral oil, paraffinic oil, or synthetic material such as olefins and vegetable esters).

3.2 TIC-Total Ion Chromatograph.

3.3 EIP-Extracted Ion Profile.

3.4 TCB-1,3,5-trichlorobenzene is used as the internal standard in this method.

3.5 SPTM-System Performance Test Mix standards are used to establish retention times and monitor detection levels.

4.0 Interferences and Limitations

4.1 Solvents, reagents, glassware, and other sample processing hardware may yield artifacts and/or elevated baselines causing misinterpretation of chromatograms.

4.2 All Materials used in the analysis shall be demonstrated to be free from interferences by running method blanks. Specific selection of reagents and purification of solvents by distillation in all-glass systems may be required.

4.3 Glassware is cleaned by rinsing with solvent and baking at 400°C for a minimum of 1 hour.

4.4 Interferences may vary from source to source, depending on the diversity of the samples being tested.

4.5 Variations in and additions of base fluids and/or drilling fluid additives (emulsifiers, dispersants, fluid loss control agents, etc.) might also cause interferences and misinterpretation of chromatograms.

4.6 Difference in light crude oils, medium crude oils, and heavy crude oils will result in different responses and thus different interpretation of scans and calculated percentages.

5.0 Safety

5.1 The toxicity or carcinogenicity of each reagent used in this method has not been precisely determined; however each chemical should be treated as a potential health hazard. Exposure to these chemicals should be reduced to the lowest possible level.

5.2 Unknown samples may contain high concentration of volatile toxic compounds. Sample containers should be opened in a hood and handled with gloves to prevent exposure. In addition, all sample preparation should be conducted in a fume hood to limit the potential exposure to harmful contaminates.

5.3 This method does not address all safety issues associated with its use. The laboratory is responsible for maintaining a safe work environment and a current awareness file of OSHA regulations regarding the safe handling of the chemicals specified in this method. A reference file of material safety data sheets (MSDSs) should be available to all personnel involved in these analyses. Additional references to laboratory safety can be found in References 16.1 through 16.3.

5.4 NAF base fluids may cause skin irritation, protective gloves are recommended while handling these samples.

6.0 Apparatus and Materials

Note: Brand names, suppliers, and part numbers are for illustrative purposes only. No endorsement is implied. Equivalent performance may be achieved using apparatus and materials other than those specified here, but

demonstration of equivalent performance meeting the requirements of this method is the responsibility of the laboratory.

6.1 Equipment for glassware cleaning.

6.1.1 Laboratory sink with overhead fume hood.

6.1.2 Kiln - Capable of reaching 450°C within 2 hours and holding 450°C within ±10°C, with temperature controller and safety switch (Cress Manufacturing Co., Santa Fe Springs, CA B31H or X31TS or equivalent).

6.2 Equipment for sample preparation.

6.2.1 Laboratory fume hood.

6.2.2 Analytical balance - Capable of weighing 0.1 mg.

6.2.3 Glassware.

6.2.3.1 Disposable pipettes - Pasteur, 150 mm long by 5 mm ID (Fisher Scientific 13-678-6A, or equivalent) baked at 400°C for a minimum of 1 hour.

6.2.3.2 Glass volumetric pipettes or gas tight syringes - 1.0-mL ± 1% and 0.5-mL ± 1%.

6.2.3.3 Volumetric flasks - Glass, class A, 10-mL, 50-mL and 100-mL.

6.2.3.4 Sample vials - Glass, 1- to 3-mL (baked at 400°C for a minimum of 1 hour) with PTFE-lined screw or crimp cap.

6.2.3.5 Centrifuge and centrifuge tubes - Centrifuge capable of 10,000 rpm, or better, (International Equipment Co., IEC Centra MP4 or equivalent) and 50-mL centrifuge tubes (Nalgene, Ultratube, Thin Wall 25´89 mm, #3410-2539).

6.3 Gas Chromatograph/Mass Spectrometer (GC/MS):

6.3.1 Gas Chromatograph-An analytical system complete with a temperature-programmable gas chromatograph suitable for split/splitless injection and all required accessories, including syringes, analytical columns, and gases.

6.3.1.1 Column - 30 m (or 60 m) x 0.32 mm ID (or 0.25 mm ID) 1 um film thickness (or 0.25mm film thickness) silicone-coated fused-silica capillary column (J&W Scientific DB-5 or equivalent).

6.3.2 Mass Spectrometer - Capable of scanning from 35 to 500 amu every 1 sec or less, using 70 volts (nominal) electron energy in the electron impact ionization mode (Hewlett Packard 5970MS or comparable).

6.3.3 GC/MS interface - the interface is a capillary-direct interface from the GC to the MS.

6.3.4 Data system - A computer system must be interfaced to the mass spectrometer. The system must allow the continuous acquisition and storage on machine-readable media of all mass spectra obtained throughout the duration of the chromatographic program. The computer must have software that can search any GC/MS data file for ions of a specific mass and that can plot such ion abundance versus retention time or scan number. This type of plot is defined as an Extracted Ion Current Profile (EIP). Software must also be available that allows integrating the abundance in any total ion chromatogram (TIC) or EIP between specified retention time or scan-number limits. It is advisable that the most recent version of the EPA/NIST Mass Spectral Library be available.

7.0 Reagents and Standards

7.1 Methylene chloride - Pesticide grade or equivalent. Used when necessary for sample dilution.

7.2 Standards - Prepare from pure individual standard materials or purchased as certified solutions. If compound purity is 96% or greater, the weight may be used without correction to compute the concentration of the standard.

7.2.1 Crude Oil Reference - NIST 1582 Petroleum Crude Oil Standard Reference Material (U.S. Department of commerce national Institute of Standards and Technology, Gaithersburg, MD 20899). This oil will be used in the calibration procedures.

7.2.2 Synthetic Base Fluid - Obtain a sample of clean NAF base fluid (as sent from the supplier-has not been circulated downhole). This NAF base fluid will be used in the calibration procedures.

7.2.3 Internal standard - Prepare a 0.01 g/mL solution of 1,3,5-trichlorobenzene (TCB). Dissolve 1.0 g of TCB in methylene chloride and dilute to volume in a 100-mL volumetric flask. Stopper, vortex, and transfer the solution to a 150-mL bottle with PTFE-lined cap. Label appropriately, and store at ´5°C to 20°C. Mark the level of the meniscus on the bottle to detect solvent loss.

7.2.4 GC/MS system performance test mix (SPTM) standards - The SPTM standards used in the development of this method contained octane, decane, dodecane, tetradecane, tetradecene, toluene, ethylbenzene, 1,2,4-trimethylbenzene, 1-methylnaphthalene and 1,3-dimethylnaphthalene. These compounds can be purchased individually, obtained as a mixture, or substituted for by a comparable mixture (i.e. Supelco, Catalog No.4-7300). Prepare a high concentration of the SPTM standard at 62.5 mg/mL (total SPTM mixture) in methylene chloride. Prepare a medium concentration SPTM standard at 1.25 mg/mL by transferring 1.0 mL of the 62.5 mg/mL solution into a 50 mL volumetric flask and diluting to the mark with methylene chloride. Finally, prepare a low concentration SPTM standard at 0.125 mg/mL by transferring 1.0 mL of the 1.25 mg/mL solution into a 10-mL volumetric flask and diluting to the mark with methylene chloride.

7.2.5 Crude oil/drilling fluid calibration standards - Prepare a 4-point crude oil/drilling fluid calibration at concentrations of 0% (no spike-clean drilling fluid), 0.5%, 1.0%, and 2.0% by volume according to the procedures outlined below using the Reference Crude Oil:

7.2.5.1 Label 4 vials with the following identification: Vial 1-0%Crude in NAF drilling fluid, Vial 2-0.5%Crude in NAF drilling fluid, Vial 3-1%Crude in NAF drilling fluid, and Vial 4-2%Crude in NAF drilling fluid.

7.2.5.2 Vial 1 will not be spiked with Reference Oil in order to retain a ‘‘0%’’ oil concentration, add 5 mL of clean NAF base fluid only.

7.2.5.3 Weigh 90.5 mg of NIST Crude Oil into Vial 2 and add 5 mL of clean NAF base fluid. This will be the 0.5% Crude equivalent in NAF mud standard.

7.2.5.4 Weigh 181 mg of NIST Crude Oil into Vial 3 and add 5 mL of clean NAF base fluid. This will be the 1.0% Crude equivalent in NAF mud standard.

7.2.5.5 Weigh 362 mg in NIST Crude Oil in Vial 4 and add 5 mL clean NAF base fluid. This will be the 2.0% Crude Equivalent in NAF mud standard

7.2.5.6 Thoroughly mix the contents of each of the 4 vial by shaking vigorously.

7.2.5.7 Weigh 0.5 g of the mixture from Vial 1 directly into a tared and appropriately labeled GC straight vial. Spike the 0.5-g supernate with 500 uL of the 0.01 g/mL 1,3,5-trichlorobenzene internal standard solution (see 7.2.3), dilute with methylene chloride, cap with a Teflon lined crimp cap, and vortex for ca. 10 sec.

7.2.5.8 Repeat step 7.2.5.7 except use 0.5 g from Vial 2.

7.2.5.9 Repeat step 7.2.5.7 except use 0.5 g from Vial 3.

7.2.5.10 Repeat step 7.2.5.7 except use 0.5 g from Vial 4.

7.2.5.11 These 4 crude/oil drilling fluid calibration standards are now used for qualitative and quantitative GC/MS analysis.

7.2.6 Precision and recovery standard (mid level crude oil/drilling fluid calibration standard)-Prepare a mid point crude oil/drilling fluid calibration using NAF base fluid and Reference Oil at a concentration of 1.0% by volume. Prepare this standard according to the procedures outlined in Section 7.2.5.4. Remove and spike with internal standard, as many 0.5-g aliquots as needed to complete the GC/MS analysis (see Section 11.6- bracketing authentic samples every 12 hours with precision and recovery standard) and the initial demonstration exercise described in Section 9.2.

7.2.7 Stability of standards

7.2.7.1 When not used, standards are stored in the dark, at -5 to -20°C in screw-capped vials with PTFE-lined lids. A mark is placed on the vial at the level of the solution so that solvent loss by evaporation can be detected. The vial is brought to room temperature prior to use.

7.2.7.2 Solutions used for quantitative purposes shall be analyzed within 48 hours of preparation and on a monthly basis thereafter for signs of degradation. Standard will remain acceptable if the peak area remains within ±15% of the area obtained in the initial analysis of the standard.

8.0 Sample Collection Preservation and Storage

8.1 NAF samples and base fluid samples are collected in 100-to 200-mL glass bottles with PTFE-or aluminum foil lined caps.

8.2 Samples collected in the field will be stored refrigerated until time of preparation (not necessary for routine sample).

8.3 Sample and extract holding times for this method have not yet been established. However, based on tests experience samples should be analyzed within seven to ten days of collection and extracts analyzed within seven days of preparation.

8.4 After completion of GC/MS analysis, extracts should be refrigerated at ca. 4°C until further notification of sample disposal.

9.0 Quality Control

9.1 Each laboratory that uses this method is required to operate a formal quality assurance program (Reference 16.4). The minimum requirements of this program consist of an initial demonstration of laboratory capability, and ongoing analysis of standards, and blanks as a test of continued performance, analyses of spiked samples to assess accuracy and analysis of duplicates to assess precision. Laboratory performance is compared to established performance criteria to determine if the results of analyses meet the performance characteristics of the method.

9.1.1 The analyst shall make an initial demonstration of the ability to generate acceptable accuracy and precision with this method. This ability is established as described in Section 9.2.

9.1.2 The analyst is permitted to modify this method to improve separations or lower the cost of measurements, provided all performance requirements are met. Each time a modification is made to the method, the analyst is required to repeat the calibration (Section 10.4) and to repeat the initial demonstration procedure described in Section 9.2.

9.1.3 Analyses of blanks are required to demonstrate freedom from contamination. The procedures and criteria for analysis of a blank are described in Section 9.3.

9.1.4 An analysis of a matrix spike sample is required to demonstrate method accuracy. The procedure and QC criteria for spiking are described in Section 9.4.

9.1.5 Analysis of a duplicate field sample is required to demonstrate method precision. The procedure and QC criteria for duplicates are described in Section 9.5.

9.1.6 Analysis of a sample of the clean NAF(s) (as sent from the supplier-has not been circulated downhole) used in the drilling operations is required.

9.1.7 The laboratory shall, on an ongoing basis, demonstrate through calibration verification and the analysis of the precision and recovery standard (Section 7.2.6) that the analysis system is in control. These procedures are described in Section 11.6.

9.1.8 The laboratory shall maintain records to define the quality of data that is generated.

9.2 Initial precision and accuracy-The initial precision and recovery test is performed using the precision and recovery standard (1% by volume Crude Equivalent in NAF drilling fluid). The laboratory shall generate acceptable precision and recovery by performing the following operations.

9.2.1 Prepare four separate aliquots of the precision and recovery standard using the procedure outlined in Section 7.2.6. Analyze these aliquots using the procedures outlined in Section 11.

9.2.2 Using the results of the set of four analyses, compute the average recovery *(*X) in weight percent and the standard deviation of the recovery (s) for each sample.

9.2.3 If s and *X* meet the acceptance criteria of 80% to 110%, system performance is acceptable and analysis of samples may begin. If, however, s exceeds the precision limit or *X* falls outside the range for accuracy, system performance is unacceptable. In this event, review this method, correct the problem, and repeat the test.

9.2.4 Accuracy and precision-The average percent recovery (P) and the standard deviation of the percent recovery (Sp) Express the accuracy assessment as a percent recovery interval from P-2Sp to P+2Sp. For example, if P=90% and Sp=10% for four analyses of crude oil in NAF, the accuracy interval is expressed as 70% to 110%. Update the accuracy assessment on a regular basis.

9.3 Blanks-Rinse glassware and centrifuge tubes used in the method with ca. 30 mL of methylene chloride, remove a 0.5-g aliquot of the solvent, spike it with the 500 mL of the internal standard solution (Section 7.2.3) and analyze a 1-mL aliquot of the blank sample using the procedure in Section 11. Compute results per Section 12.

9.4 Matrix spike sample-Prepare a matrix spike sample according to procedure outlined in Section 7.2.6. Analyze the sample and calculate the concentration (% oil) in the drilling fluid and % recovery of oil from the spiked drilling fluid using the methods described in Sections 11 and 12.

9.5 Duplicates-A duplicate field sample is prepared according to procedures outlined in Section 7.3 and analyzed according to Section 11. The relative percent difference (RPD) of the calculated concentrations should be less than 15%.

9.5.1 Analyze each of the duplicates per the procedure in Section 11 and compute the results per Section 12.

9.5.2 Calculate the relative percent difference (RPD) between the two results per the following equation:

$$RPD = \frac{D1 - D2}{(D1 + D2)/2}$$

where: D1 = Concentration of crude oil in the sample

D2 = Concentration of crude oil in the duplicate sample

9.5.3 If the RPD criteria are not met, the analytical system shall be judged to be out of control, and the problem must be immediately identified and corrected and the sample batch re-analyzed.

9.6 Preparation of the clean NAF sample is performed according to procedures outlined in Section 7.3 except that the clean NAF (drilling fluid that has not been circulated downhole) is used. Ultimately the oil-equivalent concentration from the TIC or EIP signal measured in the clean NAF sample will be subtracted from the corresponding authentic field samples in order to calculate the true contaminant concentration (% oil) in the field samples (see Section 12).

9.7 The specifications contained in this method can be met if the apparatus used is calibrated properly, then maintained in a calibrated state. The standards used for initial precision and recovery (Section 9.2) and ongoing precision and recovery (Section 11.6) shall be identical, so that the most precise results will be obtained. The GC/MS instrument will provide the most reproducible results if dedicated to the setting and conditions required for the analyses given in this method.

9.8 Depending on specific program requirements, field replicates and field spikes of crude oil into samples may be required when this method is used to assess the precision and accuracy of the sampling and sample transporting techniques.

10.0 Calibration

10.1 Establish gas chromatographic/mass spectrometer operating conditions given in Table G-1 below. Perform the GC/MS system hardware-tune as outlined by the manufacture. The gas chromatograph is calibrated using the internal standard technique. Note: Because each GC is slightly different, it may be necessary to adjust the operating conditions (carrier gas flow rate and column temperature and temperature program) slightly until the retention times in Table G-2 are met.

Table G- 1: Gas Chromatograph/Mass Spectrometer (GS/MS) Operating Conditions

Parameter	Setting
Injection port	280°C
Transfer line	280°C
Detector	280°C
Initial Temperature	50°C
Initial Time	5 minutes
Ramp	50 to 300°C@ 5°C per minute
Final Temperature	300°C
Final Hold	20 minutes or until all peaks have eluted
Carrier Gas	Helium
Flow rate	As required for standard operation
Split ratio	As required to meet performance criteria (~1:100)
Mass range	35 to 600 amu

Table G- 2: Approximate Retention Times for Compounds

Compound	Approximate Retention Time (minutes)
Toulene	5.6
Octane, n-C8	7.2
Ethylbenzene	10.3
1,2,4 – Trimethylbenzene	16.0
Decane, n-C10	16.1
TCB (Interal Standard)	21.3
Dodecane, n-C12	22.9
1-Methylnaphthalene	26.7
1-Tetradecene	28.4
Tetradecane, n-C14	28.7
1,3-Dimethylnaphthalene	29.7

10.2 Internal standard calibration procedure-1,3,5-trichlorobenzene (TCB) has been shown to be free of interferences from diesel and crude oils and is a suitable internal standard.

10.3 The system performance test mix standards prepared in Section 7.2.4 are primarily used to establish retention times and establish qualitative detection limits.

10.3.1 Spike a 500 uL aliquot of the 1.25 mg/mL SPTM standard with 500 uL of the TCB internal standard solution.

10.3.2 Inject 1.0 uL of this spiked SPTM standard onto the GC/MS in order to demonstrate proper retention times. For the GC/MS used in the development of this method the ten compounds in the mixture had typical retention times shown in Table G-2 above. Extracted ion scans for m/z 91 and 105 showed a maximum abundance of 400,000.

10.3.3 Spike a 500 uL aliquot of the 0.125 mg/mL SPTM standard with 500 uL of the TCB internal standard solution.

10.3.4 Inject 1.0 mL of this spiked SPTM standard onto the GC/MS to monitor detectable levels. For the GC/MS used in the development of this test all ten compounds showed a minimum peak height of three times signal to noise. Extracted ion scans for m/z 91 and 105 showed a maximum abundance of 40,000.

10.4 GC/MS crude oil/drilling fluid calibration -There are two methods of quantification: Total Area Integration (C8-C13) and EIP Area Integration using m/z's 91 and 105. The EIP Area Integration method should be used as the primary method for quantifying oil in NAFs and enhanced mineral oil (EMO) based drilling fluid. Inject 1.0 µL of each of the four crude oil/drilling fluid calibration standards prepared in Section 7.2.5 into the GC/MS. The internal standard should elute approximately 21-22 minutes after injection. For the GC/MS used in the development of this method, the internal standard peak was (35 to 40)% of full scale at an abundance of about 3.5e+07.

10.4.1 Total Area Integration Method-For each of the four calibration standards obtain the following: Using a straight baseline integration technique, obtain the total ion chromatogram (TIC) area from C8 to C13. Obtain the TIC area of the internal standard (TCB). Subtract the TCB area from the C8-C13 area to obtain the true C8-C13 area. Using the C8-C13 and TCB areas, and known internal standard concentration, generate a linear regression calibration using the internal standard method. The r 2 value for the linear regression curve should be ≥ 0.998. Some synthetic fluids might have peaks that elute in the window and would interfere with the analysis. In this case the integration window can be shifted to other areas of scan where there are no interfering peaks from the synthetic base fluid.

10.4.2 EIP Area Integration-For each of the four calibration standards generate Extracted Ion Profiles (EIPs) for m/z 91 and 105. Using straight baseline integration techniques, obtain the following EIP areas:

10.4.2.1 For m/z 91 integrate the area under the curve from approximately 10.5 minutes to 25 minutes, including the internal standard. The internal standard area is used in the calculations.

10.4.2.2 For m/z 105 integrate the area under the curve from approximately 10.5 minutes to 25 minutes.

10.4.2.3 Using the EIP areas for TCB, m/z 91 and m/z105, and the known concentration of internal standard. Calculate the ratio of the total m/z105 area divided by the internal standard area at m/z 91. Generate linear regression calibration curves for the ratios using the internal standard method. The r 2 value for the each of the EIP linear regression curves should be ≥ 0.998.

10.4.2.4 Some base fluids might produce a background level that would show up on the extracted ion profiles, but there should not be any real peaks (signal to noise ratio of 1:3) from the clean base fluids.

11.0 Procedure

11.1 Sample Preparation-

11.1.1 Mix the authentic field sample (drilling fluid) well. Transfer (weigh) a 30-g aliquot of the sample to a labeled centrifuge tube.

11.1.2 Centrifuge the aliquot for a minimum of 15 min at approximately 15,000 rpm, in order to obtain a solids free supernate.

11.1.3 Weigh 0.5 g of the supernate directly into a tared and appropriately labeled GC straight vial.

11.1.4 Spike the 0.5-g supernate with 500 uL of the 0.01g/mL 1,3,5-trichlorobenzene internal standard solution (see 7.2.3), dilute with methylene chloride, cap with a Teflon lined crimp cap, and vortex for ca. 10 sec.

11.1.5 The sample is ready for GC/MS analysis.

11.2 Gas Chromatography. Table G-1 summarizes the recommended operating conditions for the GC/MS. Retention times for the n-alkanes obtained under these conditions are given in Table G-2. Other columns, chromatographic conditions, or detectors may be used if initial precision and accuracy requirements (Section 9.2) are met. The system is calibrated according to the procedures outlined in Section 10, and verified every 12 hours according to Section 11.6.

11.2.1 Samples should be prepared (extracted) in a batch of no more than 20 samples. The batch should consist of 20 authentic samples, 1 blank (Section 9.3), 1 matrix spike sample (9.4), and 1 duplicate field sample (9.5), and a prepared sample of the corresponding clean NAF used in the drilling process.

11.2.2 An analytical sequence is run on the GC/MS where the 3 SPTM standards (Section 7.2.4) containing internal standard are analyzed first, followed by analysis of the four GC/MS crude

oil/drilling fluid calibration standards (Section 7.2.5), analysis of the blank, matrix spike sample, the duplicate sample, the clean NAF sample, followed by the authentic samples.

11.2.3 Samples requiring dilution due to excessive signal should be diluted using methylene chloride.

11.2.4 Inject 1.0 uL of the test sample or standard into the GC, using the conditions in Table G-1.

11.2.5 Begin data collection and the temperature program at the time of injection.

11.2.6 Obtain a TIC and EIP fingerprint scans of the sample (Table G-3).

Table G- 3: Recommended Ion Mass Numbers

Selected Ion Mass Numbers	Corresponding Aromatic Compounds	Typical Retention Times (minutes)
91	Methylbenzene	6.0
	Ethylbenzene	10.3
	1,4-Dimethylbenzene	10.9
	1,3-Dimethylbenzene	10.9
	1,2-Dimethylbenzene	10.9
105	1,3,5-Trimethylbenzene	15.1
	1,2,4-Trimethylbenzene	16.0
	1,2,3-Trimethylbenzene	17.4
156	2,6-Dimethylnaphthalene	28.9
	1,2-Dimethylnaphthalene	29.4
	1,3-Dimethylnaphthalene	29.7

11.2.7 If the area of the C8 to C13 peaks exceeds the calibration range of the system, dilute a fresh aliquot of the test sample weighing < 0.50-g and reanalyze.

11.2.8 Determine the C8 to C13 TIC area, the TCB internal standard area, and the areas for the m/z 91 and 105 EIPs. These are used in the calculation of oil concentration in the samples (see Section 12).

11.2.9 Observe the presence of peaks in the EIPs that would confirm the presence of any target aromatic compounds. Using the EIP areas and EIP linear regression calibrations determine the amount of crude oil contamination equivalent in the sample.

11.3 Qualitative Identification

11.3.1 Qualitative identification is accomplished by comparison of the TIC and EIP area data from an authentic sample to the TIC and EIP area data from the calibration standards (Section 10.4). Crude oil is identified by the presence of C10 to C13 n-alkanes and corresponding target aromatics.

11.3.2 Using the calibration data, establish the identity of the C8 to C13 peaks in the chromatogram of the sample. Using the calibration data, establish the identity of any target aromatics present on the extracted ion scans.

11.3.3 Crude oil is not present in a detectable amount in the sample if there are no target aromatics seen on the extracted ion scans. The experience of the analyst shall weigh heavily in the determination of the presence of peaks at a signal-to-noise ratio of 3 or greater.

11.3.4 If the chromatogram shows n-alkanes from C8 to C13 and target aromatics to be present, contamination by crude oil or diesel should be suspected and quantitative analysis should be determined. If there are no n-alkanes present that are not seen on the blank, and no target aromatics are seen, the sample can be considered to be free of contamination.

11.4 Quantitative Identification

11.4.1 Determine the area of the peaks from C8 to C13 as outlined in the calibration section (10.4.1). If the area of the peaks for the sample is greater than that for the clean NAF (base fluid) use the crude oil/drilling fluid calibration TIC linear regression curve to determine approximate crude oil contamination. (This step will be difficult for NAF samples that have measurable amounts of C8 to C13 peaks in the clean fluid. The EIPs should be used for quantitation of crude oil).

11.4.2 Using the EIPs outlined in Section 10.4.2 determine the presence of any target aromatics. Using the integration techniques outlined in Section 10.4.2 to obtain the EIP areas for m/z 91 and 105. Use the crude oil/drilling fluid calibration EIP ratio linear regression curves to determine approximate crude oil contamination.

11.5 Complex Samples

11.5.1 The most common interferences in the determination of crude oil can be from mineral oil, diesel oil, and proprietary additives in drilling fluids.

11.5.2 Mineral oil can typically be identified by it lower target aromatic content, and narrow range of strong peaks.

11.5.3 Diesel oil can typically be identified by low amounts of n-alkanes from C7 to C9, and the absence of n-alkanes greater than C25.

11.5.4 Crude oils can usually be distinguished by the presence of high aromatics, increased intensities of C8 to C13 peaks, and/or the presence of higher hydrocarbons of C25 and greater (which may be difficult to see in some synthetic fluids at low contamination levels).

11.5.4.1 Oil condensates from gas wells are low in molecular weight and will normally produce strong chromatographic peaks in the C8-C13 range. If a sample of the gas

condensate crude oil from the formation is available, the oil can be distinguished from other potential sources of contamination by using it to prepare a calibration standard.

11.5.4.2 Asphaltene crude oils with API gravity <20 may not produce chromatographic peaks strong enough to show contamination at levels of the calibration. Extracted ion peaks should be easier to see than increased intensities for the C8 to C13 peaks. If a sample of asphaltene crude from the formation is available, a calibration standard should be prepared.

11.6 System and Laboratory Performance

11.6.1 At the beginning of each 8-hour shift during which analyses are performed, GC crude oil/drilling fluid calibration and system performance test mixes are verified. For these tests, analysis of the medium-level calibration standard (1-% Reference Oil in IO Lab drilling fluid, and 1.25 mg/mL SPTM with internal standard) shall be used to verify all performance criteria. Adjustments and/or re-calibration (per Section 10) shall be performed until all performance criteria are met. Only after all performance criteria are met may samples and blanks be analyzed.

11.6.2 Inject 1.0 mL of the medium-level GC/MS crude oil/drilling fluid calibration standard into the GC instrument according to the procedures in Section 11.2. Verify that the linear regression curves for both TIC area and EIP areas are still valid using this continuing calibration standard.

11.6.3 After this analysis is complete, inject 1.0 mL of the 1.25 mg/mL SPTM (containing internal standard) into the GC instrument and verify the proper retention times are met (see Table G-2).

11.6.4 Retention times-Retention time of the internal standard. The absolute retention time of the TCB internal standard should be within the range 21.0 ± 0.5 minutes. Relative retention times of the n-alkanes: The retention times of the n-alkanes relative to the TCB internal standard shall be similar to those given in Table G-2.

12.0 Calculations

The concentration of oil in NAFs drilling fluids is computed relative to peak areas between C8 and C13 (using the Total Area Integration method) or peak areas from extracted ion profiles (using the Extracted Ion Profile Method). In either case, there is a measurable amount of peak area, even in clean drilling fluid samples, due to spurious peaks and electrometer ‘‘noise’’ that contributes to the total signal measured using either of the quantitation methods. In this procedure, a correction for this signal is applied, using the blank or clean sample correction technique described in American Society for Testing Materials (ASTM) Method D-3328-90, Comparison of Waterborne Oil by Gas Chromatography. In this method, the ‘‘oil equivalents’’ measured in a blank sample by total area gas chromatography are subtracted from that determined for a field sample to arrive at the most accurate measure of oil residue in the authentic sample.

12.1 Total Area Integration Method

12.1.1 Using C8 to C13 TIC area, the TCB area in the clean NAF sample and the TIC linear regression curve, compute the oil equivalent concentration of the C8 to C13 retention time range in the clean NAF. Note: The actual TIC area of the C8 to C13 is equal to the C8 to C13 area minus the area of the TCB.

12.1.2 Using the corresponding information for the authentic sample, compute the oil equivalent concentration of the C8 to C13 retention time range in the authentic sample.

12.1.3 Calculate the concentration (% oil) of oil in the sample by subtracting the oil equivalent concentration (% oil) found in the clean NAF from the oil equivalent concentration (% oil) found in the authentic sample. The C8 to C13 TIC area will not work well for clean NAF samples that contain measurable amounts of paraffins in the C8 to C13 range.

12.2 EIP Area Integration Method

12.2.1 Using the ratio of the 105 EIP area to the TCB m/z 91 EIP area in the clean NAF s ample, and the appropriate EIP linear regression curve, compute the oil equivalent concentration of the in the clean NAF.

12.2.2 Using the corresponding information for the authentic sample, compute its oil equivalent concentration.

12.2.3 If the ratio of the of the 105 EIP area to the TCB m/z 91 EIP area for the authentic sample is greater than that for the 1% formation oil equivalent calibration standard, the sample is considered contaminated with formation oil.

13.0 Method Performance

13.1 Specification in this method are adopted from EPA Method 1663, Differentiation of Diesel and Crude Oil by GC/FID (Reference 16.4).

13.2 Single laboratory method performance using an Internal Olefin (IO) drilling fluid fortified at 0.5% oil using a 35 API gravity oil was:

Precision and accuracy 94±4%

Accuracy interval-86.3% to 102%

Relative percent difference in duplicate analysis-6.2%

14.0 Pollution Prevention

14.1 The solvent used in this method poses little threat to the environment when recycled and managed properly.

15.0 Waste Management

15.1 It is the laboratory's responsibility to comply with all federal, state, and local regulations governing waste management, particularly the hazardous waste identification rules and land disposal restriction, and to protect the air, water, and land by minimizing and controlling all releases from fume hoods and bench operations. Compliance with all sewage discharge permits and regulations is also required.

15.2 All authentic samples (drilling fluids) failing the RPE (fluorescence) test (indicated by the presence of fluorescence) shall be retained and classified as contaminated samples. Treatment and ultimate fate of these samples is not outlined in this SOP.

15.3 For further information on waste management, consult ''The Waste Management Manual for Laboratory Personnel'', and ''Less is Better: Laboratory Chemical Management for Waste Reduction'', both available form the American Chemical Society's Department of Government Relations and Science Policy, 1155 16th Street NW, Washington, D.C. 20036.

16.0 References

16.1 Carcinogens-''Working With Carcinogens.'' Department of Health, Education, and Welfare, Public Health Service, Centers for Disease Control [available through National Technical Information Systems, 5285 Port Royal Road, Springfield, VA 22161, document no. PB-277256]: August 1977.

16.2 ''OSHA Safety and Health Standards, General Industry [29 CFR 1910], Revised.'' Occupational Safety and Health Administration, OSHA 2206. Washington, DC: January 1976.

16.3 ''Handbook of Analytical Quality Control in Water and Wastewater Laboratories.'' USEPA, EMSSL-CI, EPA-600/4-79-019. Cincinnati, OH: March 1979.

16.4 ''Method 1663, Differentiation of Diesel and Crude Oil by GC/FID, Methods for the Determination of Diesel, Mineral, and Crude Oils in Offshore Oil and Gas Industry Discharges, EPA 821-R-92-008, Office of Water Engineering and Analysis Division, Washington, DC: December 1992

Appendix H

CWA Part 316(b) Cooling Water Intake Structure (CWIS) Requirements

CWA Part 316(b) Cooling Water Intake Structure (CWIS) Requirements

Appendix H incorporates by reference 40 CFR Part 125, Subpart N requirements applicable to cooling water intake structures for new offshore oil and gas extraction facilities under the CWA 316(b). This Attachment summarizes the Subpart N requirements. Applicants and permittees should consult 40 CFR Part 125, Subpart N, for the specific, applicable requirements. To the extent there are any inconsistencies or missing provisions in this summary Attachment, the applicant and permittee must comply with the Subpart N requirements.

Pursuant to 40 CFR 125.134(a)(1), the owner or operator of a new offshore oil and gas extraction facility must comply with: (i) Track I in 125.134(b) or Track II in 125.134(c) if it is a fixed facility; or (ii) Track I in 125.134(b) if it is not a fixed facility (i.e. non-fixed facility).

A. Application Requirements. A permit applicant for a new fixed facility must submit to the Director a written statement, included in the Notice of Intent, indicating its intent to comply with either the Track I requirements in 40 CFR 125.134(b) as summarized in Paragraph B, below or the Track II requirements in 40 CFR 125.134(c) as summarized in Paragraph C, below. A permit applicant must also submit the application information required in accordance with 40 CFR 125.136(a)(2). Note: a non-fixed facility must comply with Track I requirements.

B. Track I Intake Structure Operational and Other Requirements.

1. Fixed Facilities that Do Not Employ Sea Chests as Intake Structures.

a. The cooling water intake structure(s) must be designed and constructed so that the maximum through-screen design intake velocity is 0.5 ft/s or less;

b. For cooling water intake structures located in an estuary or tidal river, the total design intake flow over one tidal cycle of ebb and flow must be no greater than one (1) percent of the volume of the water column within the area centered about the opening of the intake with a diameter defined by the distance of one tidal excursion at the mean low water level;

c. The permittee shall select and implement design and construction technologies or operational measures for minimizing impingement mortality of fish and shellfish as determined by the Director in accordance with 40 CFR 125.134(b)(4)(i-iii);

d. The permittee shall select and implement design and construction technologies or operational measures for minimizing entrainment of entrainable life stages of fish and shellfish;

e. The applicant/permittee shall submit the applicable information specified in 40 CFR 125.134(b)(6);

f. The permittee shall implement monitoring requirements specified in 40 CFR 125.137 as summarized in Paragraph E, below.

g. The permittee shall implement the record keeping, data recording form creation and use, and applicable annual reporting requirements specified in 40 CFR 125.138 as summarized in Paragraph F, below.

2. Fixed Facilities that Employ Sea Chests as Intake Structures.

a. The cooling water intake structure(s) must be designed and constructed so that the maximum through-screen design intake velocity is 0.5 ft/s or less;

b. For cooling water intake structures located in an estuary or tidal river, the total design intake flow over one tidal cycle of ebb and flow must be no greater than one (1) percent of the volume of the water column within the area centered about the opening of the intake with a diameter defined by the distance of one tidal excursion at the mean low water level;

c. The permittee shall select and implement design and construction technologies or operational measures for minimizing impingement mortality of fish and shellfish as determined by the Director in accordance with 40 CFR 125.134(b)(4)(i-iii);

d. The applicant/permittee shall submit the applicable information specified in 40 CFR 125.134(b)(6);

e. The permittee shall implement monitoring requirements specified in 40 CFR 125.137 as summarized in Paragraph E, below.

f. The permittee shall implement the record keeping, data recording form creation and use, and applicable annual reporting requirements specified in 40 CFR 125.138 as summarized in Paragraph F, below.

3. New Non-Fixed Facilities.

a. The cooling water intake structure(s) must be designed and constructed so that the maximum through-screen design intake velocity is 0.5 ft/s or less;

b. The permittee shall select and implement design and construction technologies or operational measures for minimizing impingement mortality of fish and shellfish as determined by the Director in accordance with 40 CFR 125.134(b)(4)(i-iii);

c. The applicant/permittee shall submit the applicable information specified in 40 CFR 125.134(b)(6);

d. The permittee shall implement monitoring requirements specified in 40 CFR 125.137 as summarized in Paragraph E, below.

e. The permittee shall implement the record keeping, data recording form creation and use, and applicable annual reporting requirements specified in 40 CFR 125.138 as summarized in Paragraph F, below.

C. Track II Intake Operational and Other Requirements.

1. Fixed Facilities With or Without Sea Chests as Intake Structures.

a. The permittee shall comply with the demonstration requirements in 40 CFR 125.134(c)(1);

b. For cooling water intake structures located in an estuary or tidal river, the total design intake flow over one tidal cycle of ebb and flow must be no greater than one (1) percent of the volume of the water column within the area centered about the opening of the intake with a diameter defined by the distance of one tidal excursion at the mean low water level;

c. The applicant/permittee shall submit the applicable information required in 40 CFR 122.21(r)(2) (except (r)(2)(iv)), (3) and (4) and 40 CFR 125.136(c);

d. The operator must implement monitoring requirements specified in 40 CFR 125.137 to demonstrate compliance with applicable requirements.

e. The operator must implement the record keeping requirements specified in 40 CFR 125.138.

D. More Stringent Requirements. The permittee shall comply with any more stringent requirements relating to location, design, construction, and capacity of a cooling water intake structure(s) or monitoring requirements at a new offshore oil and gas extraction facility that the Director deems are reasonably necessary to comply with any provision of federal or state law.

E. Monitoring Requirements. The permittee shall perform monitoring in accordance with the applicable monitoring requirements in 40 CFR 125.137.

1. Track I Fixed Facilities that Do Not Employ Sea Chests as Intake Structures. The permittee shall monitor for entrainment in accordance with 40 CFR 125.137(a)(2), (a)(3) and (a)(5). The permittee shall conduct applicable velocity monitoring in accordance with 40 CFR 125.137(b) and visual or remote inspections in accordance with 40 CFR 125.137(c). The permittee is not required to monitor for impingement unless the Director determines that the information would be necessary to evaluate the need for or compliance with additional requirements in accordance with 40 CFR 125.134(b)(4) or more stringent requirements in accordance with 40 CFR 125.134(d).

2. Track I Fixed Facilities that Employ Sea Chests as Intake Structures. The permittee shall conduct applicable velocity monitoring in accordance with 40 CFR 125.137(b) and visual or remote inspections in accordance with 40 CFR 125.137(c). The permittee is not required to perform biological monitoring unless the Director determines that the information would be necessary to evaluate the need for or compliance with additional requirements in accordance with 40 CFR 125.134(b)(4) or more stringent requirements in accordance with 40 CFR 125.134(d).

3. Track II Fixed Facilities that Employ Sea Chests as Intake Structures. The permittee shall monitor for impingement in accordance with 40 CFR 125.137(a)(2), (a)(3) and (a)(4). The

permittee shall conduct applicable velocity monitoring in accordance with 40 CFR 125.137(b) and visual or remote inspections in accordance with 40 CFR 125.137(c).

4. Track II Fixed Facilities that Do Not Employ Sea Chests as Intake Structures. The permittee shall monitor for both impingement and entrainment in accordance with 40 CFR 125.137(a)(2), (a)(3), (a)(4) and (a)(5). The permittee shall conduct applicable velocity monitoring in accordance with 40 CFR 125.137(b) and visual or remote inspections in accordance with 40 CFR 125.137(c).

5. Non-Fixed Facilities. The permittee shall conduct applicable velocity monitoring in accordance with 40 CFR 125.137(b) and visual or remote inspections in accordance with 40 CFR 125.137(c). The permittee is not required to perform biological monitoring unless the Director determines that the information would be necessary to evaluate the need for or compliance with additional requirements in accordance with 40 CFR 125.134(b)(4) or more stringent requirements in accordance with 40 CFR 125.134(d).

F. Record Keeping and Reporting. Every permittee shall comply with the following record retention, data recording form creation and use, and applicable annual reporting requirements.

1. Record Retention. The permittee shall keep records of all the data used to complete the permit application or NOI and to show compliance with the requirements, any supplemental information developed in accordance with 40 CFR 125.136, and any compliance monitoring data created and/or submitted in accordance with Paragraph E, above for a period of three (3) years from the date that the permittee ceased exploratory facility operations and all authorized discharges at a drilling site for which the data was created or generated. The Director may require the permittee to retain these records for a longer period of time by written notice.

2. Data Recording Forms. The permittee shall create and use written forms to record compliance monitoring data including weekly visual/remote inspection data, velocity monitoring data, and applicable impingement and entrainment sampling data.

3. Yearly Status Report. The permittee shall submit a yearly status report to the Director by March 1 of the following year that includes the biological monitoring records for each CWIS of fixed facilities, velocity and head loss monitoring records, and records of visual and/or remote inspections as required by Paragraph E, above.

ATTACHMENT 1 NOTICE OF INTENT INFORMATION

Attachment 1

Notice of Intent

NOTICE OF INTENT (NOI) / APPLICATION TO DISCHARGE UNDER:

General Permit AKG315100 -

Mobile Oil and Gas Exploration Facilities in State Waters in Cook Inlet

Please submit this NOI electronically to: dec.water.oilandgas@alaska.gov and send a hardcopy to:

ALASKA DEPARTMENT OF ENVIRONMENTAL CONSERVATION

Wastewater Discharge Authorization Program

555 Cordova Street

Anchorage, Alaska 99501

Submittal of this document constitutes notice that the party identified in Section 3 intends to be covered by the Alaska Pollutant Discharge Elimination System (APDES) General Permit AKG315100 – Mobile Oil and Gas Exploration Facilities in State Waters in Cook Inlet (permit). The permit authorizes discharges into waters of the United States resulting from mobile oil and gas exploration and obligates the applicant to comply with the terms and conditions of the permit. Please provide all information below per each site proposed for exploration activities. Attach supplemental information sheets as appropriate.

SECTION 1 – PERMIT INFORMATION

Previous Permit or Authorization No. (if applicable):

Please indicate the coverage requested.

[ ] Existing Permitee: Existing Mobile Cook Inlet Oil & Gas Exploration Facility previously covered under 2007 Cook Inlet General APDES Permit (See Section 1.1.1).

[ ] New Applicant: A new Mobile Oil & Gas Exploration Facility meeting criteria under Sec. 1.1.2 for coverage under this permit.

SECTION 2 – FACILITY INFORMATION

Facility Name:	Phone:	
Name of Contact Person:	Fax:	
Facility Mailing Address (Street/Location):	State: AK	Zip:
Email Address:		

Mobile Facility Type *(check applicable type)*	☐	Jackup	Is the Facility Operated Seasonally? ☐ Yes ☐ No	Approx Start Date:	
	☐	Drill Ship			
	☐	Semisubmersible			
	☐	Other (specify):		Approx End Date:	

SECTION 3 – RESPONSIBLE PARTY INFORMATION

Owner/Operator or Person responsible for overall management of the project and discharge

First Name:	Last Name:	Phone:
Title:		
Mailing Address:		Fax:
City:	State:	Zip:
E-mail Address:		

SECTION 4 – ON-SITE CONTACT/OPERATOR INFORMATION

[ ] Check if same as Responsible Party

First Name:	Last Name:	Phone:
Title:		
Mailing Address:		Fax:
City:	State: Alaska	Zip:
E-mail Address:		

SECTION 5 – BILLING INFORMATION

First Name:	Last Name:	Phone:
Title:		
Mailing Address:		Fax:
City:	State: Alaska	Zip:
E-mail Address:		

Section 6 – DISCHARGE LOCATIONS

ADNR Lease Number:	Block #:

Exploration Facilities are required to designate the sites where they will be operating. Authorizations will be issued per well and/or geographic area. Provide detailed information and vicinity maps on proposed discharge locations.

Do you wish to request to operate in a specific, defined geographical area? [ ] Yes [ ] No

If you answered yes to the above question, please provide a map, and a description of the area of coverage, and the following well information:

Section 6 – DISCHARGE LOCATIONS (Continued…)

WELL #1	Well Name:		Latitude:		Longitude:	
	Well Number:	Estimated Total Volume of Drill Cuttings:	(bbls)	Estimated Total Volume of Drill Fluids:	(bbls)	
	Distance from discharge to shoreline or excluded discharge areas:	Is this a net depositional location in the Cook Inlet? [ ] Yes [ ] No		Have you collected baseline sediment samples at the site? [ ] Yes [ ] No		
	Beginning Drill Date:		Estimated Drilling Depth:			
	Estimated end Date:		Depth below Mean Lower Low Water (MLLW):			
WELL #2	Well Name:		Latitude:		Longitude:	
	Well Number:	Estimated Total Volume of Drill Cuttings:	(bbls)	Estimated Total Volume of Drill Fluids:	(bbls)	
	Distance from discharge to shoreline or excluded discharge areas:	Is this a net depositional location in the Cook Inlet? [ ] Yes [ ] No		Have you collected baseline sediment samples at the site? [ ] Yes [ ] No		
	Beginning Drill Date:		Estimated Drilling Depth:			
	Estimated end Date:		Depth below Mean Lower Low Water (MLLW):			
WELL #3	Well Name:		Latitude:		Longitude:	
	Well Number:	Estimated Total Volume of Drill Cuttings:	(bbls)	Estimated Total Volume of Drill Fluids:	(bbls)	
	Distance from discharge to shoreline or excluded discharge areas:	Is this a net depositional location in the Cook Inlet? [ ] Yes [ ] No		Have you collected baseline sediment samples at the site? [ ] Yes [ ] No		
	Beginning Drill Date:		Estimated Drilling Depth:			
	Estimated end Date:		Depth below Mean Lower Low Water (MLLW):			
WELL #4	Well Name:		Latitude:		Longitude:	
	Well Number:	Estimated Total Volume of Drill Cuttings:	(bbls)	Estimated Total Volume of Drill Fluids:	(bbls)	
	Distance from discharge to shoreline or excluded discharge areas:	Is this a net depositional location in the Cook Inlet? [ ] Yes [ ] No		Have you collected baseline sediment samples at the site? [ ] Yes [ ] No		
	Beginning Drill Date:		Estimated Drilling Depth:			
	Estimated end Date:		Depth below Mean Lower Low Water (MLLW):			
WELL #5	Well Name:		Latitude:		Longitude:	
	Well Number:	Estimated Total Volume of Drill Cuttings:	(bbls)	Estimated Total Volume of Drill Fluids:	(bbls)	
	Distance from discharge to shoreline or excluded discharge areas:	Is this a net depositional location in the Cook Inlet? [ ] Yes [ ] No		Have you collected baseline sediment samples at the site? [ ] Yes [ ] No		
	Beginning Drill Date:		Estimated Drilling Depth:			
	Estimated end Date:		Depth below Mean Lower Low Water (MLLW):			

SECTION 7 – DRILLING FLUIDS TO BE USED IN WELL DRILLING

Category (*check all that apply*)			Group (*check all that apply*)		
	☐	Water-based		☐	Lignosulfonate
	☐	Oil-based		☐	Lime
	☐	Synthetic-based		☐	Gyp
	☐	Other (*specify*):		☐	Sea-water
				☐	Saltwater
Provide a description of the disposal practice of oil-based, synthetic-based, or other drilling fluids proposed to be used in well drilling in the DFP.				☐	Saturated Saltwater
				☐	Non-dispersed (Viscosifier/Polymer) PH/PA

SECTION 8 – INVENTORY OF DISCHARGES

Check all that apply then indicate the depth of discharge and the maximum daily and average discharge rate, and indicate if you will be requesting a default mixing zone for that discharge *(include units of measure).*

	Mixing Zone Requested	Discharge Depth:	Max Daily Discharge Rate	Average Discharge Rate
☐ 001 Drilling Fluids and Drill Cuttings*	☐ Yes ☐ No			
☐ 002 Deck Drainage	☐ Yes ☐ No			
☐ 003 Domestic Wastewater (See Section 10)	☐ Yes ☐ No			
☐ 004 Graywater (Requires Waiver per Section 10)	☐ Yes ☐ No			
☐ 005 Desalination Unit Waste	☐ Yes ☐ No			
☐ 006 Blowout Preventer Fluid	☐ Yes ☐ No			
☐ 007 Boiler Blowdown	☐ Yes ☐ No			
☐ 008 Fire Control System Test Water	☐ Yes ☐ No			
☐ 009 Non-Contact Cooling Water	☐ Yes ☐ No			
☐ 010 Uncontaminated Ballast Water	☐ Yes ☐ No			
☐ 011 Bilge Water	☐ Yes ☐ No			
☐ 012 Excess Cement Slurry	N/A			
☐ 013 Mud, Cuttings, Cement and Seafloor	☐ Yes ☐ No			
☐ 019 Test Fluids	☐ Yes ☐ No			

*Drilling Fluids Plan (DFP) and Environmental Monitoring Plan (EMP)-Study Plan are required.

SECTION 9 - REQUEST FOR MIXING ZONE AND EFFLUENT MODIFICATION FROM DEC

Did you select "Yes" for any Mixing Zone Request(s) in SECTION 8 of this form?
Check an answer below, read the instructions to the right.

	THE FOLLOWING INFORMATION MUST BE PROVIDED IF REQUESTING A MIXING ZONE*		
	USE:	**DISTANCE:**	**UNITS:**
[ ] Yes	Supply for aquaculture		
	Supply for industrial use		
	Contact recreation		
	Secondary recreation		
	Fish spawning		
	Harvesting and consumption of raw fish or other aquatic life		
[ ] No	If you answered "No" to requesting a mixing zone or have questions concerning mixing zones, please contact the DEC.		

***NOTE:** The NOI and all requested information below will be reviewed to determine if the discharges associated with the mixing zone request are consistent with the permit conditions and that the site conditions meet the permit requirements. The burden of proof for justifying a mixing zone through demonstrating compliance with the requirements of 18 AAC 70.240 – 18 AAC 70.270 rests with the applicant. Additional information may be requested by DEC based on this review.

SECTION 10 – COMPLIANCE WITH WASTEWATER DISPOSAL REGULATIONS (18 AAC 72)

DOMESTIC WASTEWATER TREATMENT: Provide a brief description of the domestic wastewater treatment process(es) of the facility, including the level of treatment and type of disinfection (if any). Include all makes, models, treatment capacities of the wastewater treatment units, and a schematic flow diagram of the wastewater treatment process.

Will graywater (as defined by 18 AAC 72.990(35)) be discharged as a segregated wastewater stream?	Maximum Rated Personnel Capacity of the Facility:	Average Estimated Personnel on this Facility:
[ ] Yes - A waiver is required for Graywater Discharge (003) [ ] No		

TREATMENT SYSTEM TYPE:	**STAFFING CLASSIFICATION:**
☐ MSD ☐ MSD/BTU ☐ BTU	☐ M10 ☐ M9IM

NOTE: All combinations of Treatment System Types and Staffing Classifications will require a Waiver for Domestic Discharge (004) except M10/BTU's.

ENGINEERED PLAN REVIEW: Proof of a current Approval to Operate (ATO) from DEC for the mobile exploration facility indicated in this NOI, satisfies requirements of 18 AAC 72.205, 72.200, and 72. 600. Provide the dates of plan submittal and ATO (if applicable). If you do not have an ATO or have not yet submitted plans, please indicate in the spaces provided below.

Engineered Plan Review Submittal	Approval to Operate Issue Date
Date:	Date: (Attach ATO Letter)

SECTION 10 – COMPLIANCE WITH WASTEWATER DISPOSAL REGULATIONS (18 AAC 72) (Continued…)

MINIMUM TREATMENT WAIVER: In accordance with 18 AAC 72.050(d)(1) – (5) and 18 AAC 72.060(b), an applicant seeking a waiver from the minimum treatment requirements of 18 AAC 72.050(a)(1) or (a)(4) for domestic wastewater discharge 003 or graywater discharge 004, shall provide proof of previous approval or submit a report prepared by a registered engineer. The department will review the report and determine if a waiver or modification will be made in accordance with 18 AAC 72.060. Provide the submittal date for any applicable waiver requests and the approval (if applicable). If you do not have a Minimum Treatment Waiver or have not yet requested one, please indicate in the spaces provided below.

Minimum Treatment Waiver Submittal: Date: Waiver for: (indicate discharge)	Minimum Treatment Waiver Approval (attach Approval): Date:

SECTION 11 – CERTIFICATION

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Signature	Title
Printed Name	Date

NOTICE OF INTENT (NOI) CHECKLIST OF ATTACHEMENTS (Permit Number AKG315100) The applicant must submit the following information (if applicable) with the NOI:		
Site Map	☐ Included	Submit a site map showing the exact location of the facility and discharges associated with the project. Mobile facilities must indicate the intended areas of operation, a description of operations within those areas, and the initial latitude and longitude of the facility.
Initial Site Assessment	☐ Included	Submit initial site assessment with NOI documenting that the drill site is not located in or near a sensitive marine environment specifically excluded from coverage by this permit (see Section 9 of this NOI or Prohibited Areas in Permit Section 1.4).
Line Drawings and Flow Balances	☐ Included	Submit line drawings that show the flow, including rates/volumes of each discharged waste stream through facility. The line drawings must contain flow balances showing average and maximum flow rates between intakes, operations, treatment units, and outfalls.
Environmental Monitoring Program (EMP) Plan of Study	☐ Included	Submit EMP Plan of Study (i.e., EMP design and detailed scope of work), including dilution, plume and deposition monitoring (Permit Section 2.2.7.4). Include references to or copies of any previously completed EMP Reports.
Other Environmental Reports and Related Plans	☐ Included	Provide copies of exploration plans, biological surveys, and environmental reports for the site required by other state (e.g., ADNR, ADFG) and federal (e.g., BOEM, BSEE, NMFS, USFWS) agencies.
Drilling Fluid Plan	☐ Included	Submit a plan for the formulation and control of drilling fluid/chemical additive systems for each well.
Best Management Practices (BMP) Plan	☐ Included	Submit the BMP Plan that incorporates practices to achieve the objectives and specific requirements of the permit.
Quality Assurance Project Plan (QAPP) Certification	☐ Acknowledge	Submit a letter certifying that a QAPP for all monitoring required by this general permit has been developed and implemented. Submittal is required with the NOI or within 90 days of discharging.
Cooling Water Intake Structure Requirements 316(b)	☐ Yes ☐ No _____ Date	Indicate whether the facility meets the applicability criteria in Section 2.12 of the permit. If so, mobile exploration facilities under this permit must comply with Track I requirements as described in Appendix H of the permit and Section 10.4 of the Fact Sheet. If not, please indicate the date of construction for the facility
Plan Review for All Discharges (001-013)	☐ Included	Submit proof of prior approval or an engineering plan to DEC for written approval before constructing, installing, or modifying a domestic or nondomestic wastewater treatment works (18 AAC 72.200 and 18 AAC 72.600).
Waiver from minimum treatment requirements for domestic wastewater (if applicable).	☐ Included	Submit proof of prior approval or an engineering report with a request for written approval of a waiver to DEC's minimum treatment requirements (18 AAC 72.050).

ATTACHMENT 2 NONCOMPLIANCE NOTIFICATION

Attachment 2

Noncompliance Notification

Alaska Department of Environmental Conservation

Division of Water, Compliance and Enforcement Program
555 Cordova Street
Anchorage, Alaska 99501
Nationwide Toll Free: 1(877) 569-4114 Anchorage/International: (907) 269-4114
Fax: (907) 269-4604 E-mail address: dec-wqreporting@alaska.gov.

NONCOMPLIANCE NOTIFICATION

GENERAL INFORMATION	**PERMIT# (if any):**	
Owner or Operator:	**Facility Name:**	**Facility Location:**
Person Reporting:	**Phone Numbers of Person Reporting:**	**Reported How? (e.g. by phone):**
Date/Time Event was Noticed:	**Date/Time Reported:**	**Name of DEC Staff Contacted:**

VERBAL NOTIFICATION MUST BE MADE TO ADEC WITHIN 24 HOURS OF DISCOVERY OF NONCOMPLIANCE

INCIDENT DETAILS (attach additional sheets, lab reports, and photos as necessary)

Period of Noncompliance	**Start Date/Time** (exact)**:**	**End Date/Time** (exact)**:**

If noncompliance has not been corrected, provide a statement regarding the anticipated time the noncompliance is expected to continue:

Estimated Quantity involved (volume or weight):

Description of the noncompliance and its cause (be specific):

Actions taken to reduce, eliminate, and prevent reoccurrence of noncompliance and Actual/Potential Impact on Environmental Health (describe in detail) (e.g. Supplied drinking water to nearby well owners and informed well owners not to drink from wells until further notice)

Permit Condition Deviation (Identify each permit condition exceeded during the event.)

Parameter (e.g. BOD pH)	**Permit Limit**	**Exceedance (sample result)**	**Sample Date**

Corrective Actions (Attach a description of corrective actions taken to restore the system to normal operation and to minimize or eliminate chances of recurrence.)

Environmental Damage: (if yes, provide details below) ☐ **Yes** ☐ **No** ☐ **Unknown**

Actual /Potential Impact on Environment/Public Health (describe in detail)

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Name: **Title:** **Signature:** **Date:**

FORMS MUST BE SENT TO ADEC WITHIN FIVE DAYS OF BECOMING AWARE OF THE EVENT.